



# **BRISBANE CITY COUNCIL BRISBANE WATER**

## **Australia Trade Coast Sewer Project**

**SP298**

**Lytton Rd No. 4 Pump Station**

**Operation & Maintenance Manual**

**Contract No. BW30137-02/03**

**Volume No. 5**

BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<u>Volume</u>	<u>Section</u>	<u>Description</u>	<u>Pages</u>
1	1	<b>Table of Contents</b>	7
		Electronic copy of complete Operation & Maintenance Manual on CD.	
		<a href="#">Hyperlink Files\Title Page Volume 1.doc</a> <a href="#">Hyperlink Files\Title Page Volume 2.doc</a> <a href="#">Hyperlink Files\Title Page Volume 2.1.doc</a> <a href="#">Hyperlink Files\Title Page Volume 3.doc</a> <a href="#">Hyperlink Files\Binder Labels.doc</a> <a href="#">Hyperlink Files\Title Page Volume 4.doc</a> <a href="#">Hyperlink Files\Title Page Volume 5.doc</a> Volume/Title Pages & Binder Labels	
		<a href="#">Hyperlink Files\Revisions Page.xls</a> Revisions	1
	1.1	<b>Introduction and System Overview Lytton Road No.4 P/S SP298</b>	
		<a href="#">Hyperlink Files\OMM SP298 Introduction Description Design and Process RevA.doc</a> Subsection 1	6
		<a href="#">Description of System and Overview Locality Keyplan</a> Subsection 1.1	
		<a href="#">Design and Process</a> Subsection 1.2	
		<a href="#">Pumping System Operation</a> Subsection 1.3	
		<a href="#">Inlet Valve Pit at SP298 No.4 Interconnected Rising Mains</a> Subsection 1.4	
		<a href="#">Interconnected Rising Mains Manual Operated Valves</a> Subsection 1.5	
		<a href="#">Flow Diverted from SP298 No.4 to Gibson Island WWTP</a> Subsection 1.6	
		<a href="#">Pump Station SP298 No.4 Layout</a> Subsection 1.7	
	1.2	<b>Pump Station Equipment Operation</b>	
		Functional Specification SP298 Lytton Rd 4 described in this document are in addition to the standard functionality detailed in SPSV3 57pages. 1.1 <a href="#">General Process Description</a> 2.1 <a href="#">Standard Equipment</a> 2.2 <a href="#">Non Standard Equipment</a> 2.2.3 <a href="#">Actuated Valves</a> 3.1 <a href="#">Normal Operation</a> Figure 3: <a href="#">SP298 Station Level Set Points</a> 3.4 <a href="#">Non Standard Control</a> 3.6 <a href="#">Non Standard IDTS Picture</a>	18
		<a href="#">Hyperlink Files\SPSV3.doc</a> Standard Functional Specification SPSV3	57
2	2	<b>Proprietary Equipment Manuals/Maintenance and Service</b>	
	2.1	<b>Weir Services: Hydrostal Pumps</b>	
		<a href="#">Hyperlink Files\Hydrostal Pump I &amp; O manual Lytton Rd - rev A.doc</a> Including the following	52
		<a href="#">Description of Equipment</a>	
		<a href="#">Operation and Maintenance</a>	
		<a href="#">Maintenance and Service</a>	
		<a href="#">Impeller Clearance Adjustment for Wear</a>	
		<a href="#">Recommended Spare Parts</a>	

Issue Date: 11 OCT 05

Page 1 of 7

Rev: A

G:\CNPMS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<u>Volume</u>	<u>Section</u>	<u>Description</u>	<u>Pages</u>
		<u>Appropriate Records</u> Pump Declaration of Conformity/ Pump Volute Casing Water Pressure Test/Pump Workshop Test Records Q/H & NPSH etc/	
		<u>Hyperlink Files\wd8159 2 Layout1 (1).pdf</u> Pump General Arrangement Drg	
	<b>2.2</b>	<b><u>SE Power Equipment: Generator Set</u></b>	
		<u>Hyperlink Files\Section 1 - Instructions for Use.doc</u> SE Power Equipment: Generator Operation & Maintenance Manuals	4
		<u>Hyperlink Files\Section 2 - John Deere Operation Manual.pdf</u> Diesel Engine Generator Operator's Manual	86
		<u>Hyperlink Files\Section 3 - Stamford Installation, Service &amp; Maintenance Man.pdf</u> AC Generator Installation, Service & Maintenance Manual	44
		<u>Hyperlink Files\Section 4 - Part 1 PLC GE Fanuc.pdf</u> GE Fanuc Automation Series 90TM-30 PLCs	2
		<u>Hyperlink Files\Section 4 - Part 2 PLC GE Fanuc.pdf</u> GE Fanuc Automation Programmable Control Products Series 90TM-30 PLC Installation and Hardware Manual	67
		<u>Hyperlink Files\Section 4 - Part 3 GE Fanuc.pdf</u> GE Fanuc Automation Programmable Control Products Series 90TM-30 Programmable Control Troubleshooting Guide	18
		<u>Hyperlink Files\Section 5 - Functional Description.doc</u> Local Control Panel Functional Description	14
		<u>Hyperlink Files\SE Power Equipment Generator Drg.pdf</u> Diesel Engine/Generator Drg	6
		<u>Hyperlink Files\SE Power Works Test ITP Generator.pdf</u> SE Power Works Test ITP Generator	19
		<u>Hyperlink Files\BW Factory Test Report Generator.doc</u> BW Factory Test Report Generator	12
		<b>Stanby Generator Software (ON DISK)</b>	
	<b>2.3</b>	<b><u>Cathodic Protection</u></b>	
		<u>Hyperlink Files\Cathodic Protection System Manual SP298.pdf</u> Cathodic Protection Installation Performed Testing & Maintenance.	15
<b>2.1</b>	<b>2.4</b>	<b><u>Common Logic: Main Switchboard &amp; Associated Equipment</u></b>	
		<u>Hyperlink Files\JH42MC01 Lytton Rd.pdf</u> Main Switchboard Manual. Including the following.	12

Issue Date: 11 OCT 05

Page 2 of 7

Rev: A

G:\CNPMS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian  
Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<u>Volume</u>	<u>Section</u>	<u>Description</u>	<u>Pages</u>
		Section 1.0 General Description of Operation	
		Section 2.0 General Description of System (Componenets)	
		<a href="#">Hyperlink Files\Common Logic.pdf</a> Section 3.0 As Construction Drawings. Including Door Key Allocation	13
		<a href="#">Hyperlink Files\Drg Transmittal Common Logic.pdf</a> Section 3.1 Drawing Transmittal	3
		<a href="#">Hyperlink Files\Parts List Common Logic.pdf</a> Section 4.0 Part List	3
		<a href="#">Hyperlink Files\Tech Data Sheets Common Logic.pdf</a> Section 5.0 Technical Manuals and Data Sheets	1
		<a href="#">Hyperlink Files\TDS1804S277.pdf</a> Section 5.0 TDS-DinLine Surge Suppressor. Installation Instructions	32
		<a href="#">Hyperlink Files\TDF10A240V.pdf</a> Section 5.0 Transient Discriminating Filter Model Number TDF-10A-240V. Installation Instructions	2
		<a href="#">Hyperlink Files\DAR275V.pdf</a> Section 5.0 DinLine Alarm Relay (DAR) Model Number DAR275v. Installation Instructions.	2
		<a href="#">Hyperlink Files\3000-000-06.pdf</a> Section 5.0 Rotork Circuit Diagram N0-REV 3000-000-06	1
		<a href="#">Hyperlink Files\Rotork Electric E170E2.pdf</a> Section 5.0 Rotork IQ Range Installation and Maintenance Instructions	86
		<a href="#">Hyperlink Files\RWS300 (IQ IQT Remote Control 24Vdc).pdf</a> Section 5.0 Rotork Standard IQ/IQT Remote Control Circuitry (24V DC)	1
		<a href="#">Hyperlink Files\multitrode mtr international-datasheet.pdf</a> Section 5.0 Liquid Level Control Relay	2
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\AustSol\CA10 switches.pdf</a> Section 5.0	56
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\CROMPTON\analogue244.pdf</a> Section 5.0	21
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\CROMPTON\din250 trip relay.pdf</a> Section 5.0	8
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\Mann Ind\MannIndQS_FTXDMV.pdf</a> Section 5.0	2
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\Phoenix Contact\3004032[1].pdf</a> Section 5.0	7
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\Phoenix Contact\3004100[1].pdf</a> Section 5.0	7
		<a href="#">Hyperlink Files\Switchboard Electrical Accessories\Phoenix</a>	2

Issue Date: 11 OCT 05

Page 3 of 7

Rev: A

G:\CNPMS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<u>Volume</u>	<u>Section</u>	<u>Description</u>	<u>Pages</u>
		<a href="#">Contact\uk5n_en.pdf</a> Section 5.0	
		<a href="#">Hyperlink Files\Vegabar27525-EN.pdf</a> Section 5.0 Vegabar 64 Pressure Transmitter 4—20 mA/HART. Operating Instructions	72
		<a href="#">Hyperlink Files\Vegadis20591-EN.pdf</a> Section 5.0 Adjustment Module for Pressure Transmitter. Operating Instructions	16
		<a href="#">Hyperlink Files\Vegawell27630-EN.pdf</a> Section 5.0 Vegawell 72 is a suspension pressure transmitter for level and gauge measurement. Operating Instructions	48
		<a href="#">Hyperlink Files\MagMaster flowmeter.pdf</a> Section 5.0 Instruction Manual	24
		Section 5.1 Contents Sheet	
		<a href="#">Hyperlink Files\mg10p222.pdf</a> Section 6.0 Danfoss VFD Instruction Manual Modbus RTU	33
		<a href="#">Hyperlink Files\SP298 VFD Settings Pump No 1 and No. 2 As Built rev 1.pdf</a> Section 6.1 VFD Settings and Parameters	3
		<a href="#">Hyperlink Files\doc C 1 MG80A802.pdf</a> Section 6.2 Danfoss VFD Operating Instructions VLT 8000 AQUA	197
		<a href="#">Hyperlink Files\Lytton Rd ITP.pdf</a> <a href="#">Hyperlink Files\Lytton Rd FAT.pdf</a> Section 7.0 ITP Procedure, Test Sheets & Factory Acceptance Test	5 11
		<a href="#">Hyperlink Files\BW Factory Acceptance Test Document Switchboard.pdf</a> BW Factory Acceptance Test Document Switchboard	4
<b>3</b>	<b>3</b>	<b>Drawings &amp; Drawing Register</b>	
		Electronic copy of the following drawings on CD. Table of Contents	
	<b>3.1</b>	<a href="#">Hyperlink Files\Drawing Register.xls</a>	7
		<a href="#">Hyperlink Files\486 5 7-TR201 001.pdf</a> Locality Keyplan Drawing	1
		<a href="#">Hyperlink Files\Location Map SP298.doc</a> Street Location Map	1
		<b>As Constructed Drawings Rising Mains</b>	
	<b>3.2</b>	<a href="#">Hyperlink Files\Pages from Rising Main Lindum Rd to Lytton Rd.pdf</a> Sewer Rising Main from Connection to Kiawanah Road P/S SP49 Rising Main at Lindum Road to Lytton Road No 4 Pump Station.	10
	<b>3.3</b>	<a href="#">Hyperlink Files\Pages from Rising Main Prichard St to Lytton Rd.pdf</a> Sewer Rising Main Prichard Street Pumping Station to Lytton Road No.4	13

Issue Date: 11 OCT 05

Page 4 of 7

Rev: A

G:\CNPMS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian  
Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<b>Volume</b>	<b>Section</b>	<b>Description</b>	<b>Pages</b>
		Pumping Station	
	3.4	<a href="#">Hyperlink Files\Rising Main Drg Lytton Rd to Serpentine Rd.pdf</a> Sewer Rising Main Lytton Road Pump Station (SP298) to Serpentine Road Pump Station (SP300)	16
		<b>As Constructed Drawings Pump Station SP298 Mechanical/Electrical/Switchboard/Generator/Pit Covers</b>	
	3.5	<a href="#">Hyperlink Files\lytton rd.pdf</a> As-constructed drawings Lytton Rd Pump Station SP298. Mechanical/Electrical/Switchboard/Generator/Pit Covers	89
		<b>Weir Services: Pump General Arrangement Drawing</b>	
	3.6	<a href="#">Hyperlink Files\wd8159_2 Layout1 (1).pdf</a>	1
4	4	<b>Traning/System Testing/Pre-Commissioning/Installation Method Statement/QA Records</b>	
		<b>BW Site Based Traning</b> <a href="#">Hyperlink Files\BW Site Based Training.pdf</a>	4
	4.1	<b>BW: System Integration Testing</b>	
		<a href="#">Hyperlink Files\SP298 SP300 System Integration Testing Procedure Rev 1.doc</a> (BW) System Integration Testing Procedure SP 298 Lytton Rd Pump Station & SP 300 Serpentine Rd Pump Station. Including the following	7
		<a href="#">Hyperlink Files\BW ITP 001 Rev0.pdf</a> (BW) ITP: 001 Rev.0 EQUIPMENT: Sewer RM Pritchard St PS to Lytton Rd PS. Sewer RM from connection to Kiawanah Rd PS SP49 RM at Lindum Rd to Lytton Rd PS.	1
		<a href="#">Hyperlink Files\BW ITP 002 Rev0.pdf</a> (BW) ITP: 002 Rev.0 (Separable Portion 2 SP298 Lytton Rd Pump Station) EQUIPMENT: Pumping Station Site System Commissioning	1
		<a href="#">Hyperlink Files\BW ITP 003 Rev0.pdf</a> (BW) ITP: 003 Rev.0 (Separable Portion 2 SP300 Serpentine Rd Pump Station) EQUIPMENT: Pumping Station Site System Commissioning	1
		<a href="#">Hyperlink Files\Check List 1.pdf</a> (BW) Inspection Check List No1 Lytton Rd	1

Issue Date: 11 OCT 05

Page 5 of 7

Rev: A

G:\CNPMS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<u>Volume</u>	<u>Section</u>	<u>Description</u>	<u>Pages</u>
		<a href="#">Hyperlink Files\Check List 2.pdf</a> (BW) Inspection Check List No 2 Serpentine Rd	1
		<a href="#">Hyperlink Files\SP300 Serpentine Road Functional Spec 1-10.doc</a> <a href="#">Hyperlink Files\SP300 FS Document Signoff Approval.pdf</a>	24 1
		<a href="#">Hyperlink Files\SP300 Functional Specification Rev 3.doc</a> Parsons Brinckerhoff Date of Issue: 4 November 2004	26
		<a href="#">Hyperlink Files\SP298 Lytton Road 4 Functional Spec 1-10.doc</a> <a href="#">Hyperlink Files\SP298 FS Document Signoff Approval.pdf</a> (BW) 1-05. doc	18 1
		<a href="#">Hyperlink Files\SP298 Functional Specification Rev 4.pdf</a> Parsons Brinckerhoff Date of Issue: 5 November 2004	24
		<a href="#">Hyperlink Files\Trends SP298 13-06-2005 (2-6-24 hours).pdf</a> Lytton Rd P/S SP298 No.4 Pump Trends (2/6/24hours)	3
		<a href="#">Hyperlink Files\Trends SP300 - Concrete Main - 06-10-2005 (2-6-24 hours).pdf</a> Serpentine Rd P/S SP300 Pumping into the DN1840 Concrete Rising Main. Eagle Farm at Maximum Flow. Pump Trends (2/6/24hours)	3
		<a href="#">Hyperlink Files\Trends Steel Main SP300 11-06-2005 (2-6-24 hours).pdf</a> Serpentine Rd P/S SP300 Pumping into the DN1370 Steel Rising Main. Pump Trends (2/6/24hours)	3
		<a href="#">Hyperlink Files\BW Site Acceptance Test Document Switchboard.pdf</a> BW Site Acceptance Test Document Switchboard	3
		<a href="#">Hyperlink Files\BW IDTS Point Commissioning Sheet Switchboard.pdf</a> BW IDTS Point Commissioning Sheet Switchboard	5
		<a href="#">Hyperlink Files\BW Site Inspection Report Switchboard.pdf</a> BW Site Inspection Report Switchboard	6
<b>4.2</b>		<b>Leighton/Parsons Brinckerhoff: Pre-Commissioning Report</b>	
		<a href="#">Hyperlink Files\Letter Electrical Installation in accordance with AS3000.pdf</a> Letter from REDILEC (who was working under Leighton direction) to certify that the electrical works is in accordance with AS3000.	1
		<a href="#">Hyperlink Files\RPT020Bvb - Precommissioning Lytton Rd PS.pdf</a> Pre-commissioning Report Lytton Road Pump Station SP298. Including the following.	34
		Introduction	
		Appendix A: Pre-commissioning plan	
		Appendix B: Temporary pre-commissioning pipework arrangement	
		Appendix C: Manufacturers test data	
		Appendix D: Pre-Commissioning test data	

Issue Date: 11 OCT 05

Page 6 of 7

Rev: A

G:\CNPMSS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



BRISBANE CITY COUNCIL  
Brisbane Water  
Lytton Road P/S SP298 Australia Trade Coast Sewer Project

BW30137-02/03

<u>Volume</u>	<u>Section</u>	<u>Description</u>	<u>Pages</u>
		Appendix E: Pump data comparison graphs	
		Conclusion	
	<b>4.3</b>	<b>Leighton: Work Method Statement</b>	
		<a href="#">Hyperlink Files\Q1112-CS-701 CMS SP1 Rising Main.pdf</a> Leighton Construction Method Statement: Rising mains from Pritchard St P/S to Lytton Rd P/S and Lytton Rd P/S to Lindum Rd pipeline.	9
		<a href="#">Hyperlink Files\Q1112-CS-703 CMS of SP2 Rising Main.pdf</a> Leighton Construction Method Statement: Rising mains from Lytton Rd P/S to Serpentine Rd P/S.	8
		<a href="#">Hyperlink Files\Q1112-CS-704 CMS of Lytton Road pump station.doc</a> Leighton Construction Method Statement: Lytton Rd P/S	9
	<b>4.4</b>	<b>Leighton: Installation QA Records</b>	
		<a href="#">Hyperlink Files\QA Records.zip</a> Open Lytton QA Register (xls) first for Abbreviated Description	
<b>5</b>	<b>5</b>	<b>Leighton/Parsons Brinckerhoff: Design Report</b>	
		<a href="#">Hyperlink Files\SP298 design report.zip</a> Revised Developed Design Report Separable Portion No.2 Lytton Road Pump Station SP298. Including the following	213
		Introduction	
		Design Summary	
		Drawings	
		Input Design Data	
		Developed Design	
		Environmental Management	
		Permits and Approvals	
		List of Appendices A to I	

Issue Date: 11 OCT 05

Page 7 of 7

Rev: A

G:\CNPMSS\Asset Creation Program\STTG -Australia TradeCoast Sewer\2004-2005\COMMISS\Reg McGIRR\Australian Trade Coast Sewer Project\OMM SP298\Table of Contents SP298.doc



<b>5</b>	<b>5</b>	<b>Leighton/Parsons Brinckerhoff: Design Report</b>	
		<a href="#">Hyperlink Files\SP298 design report.zip</a> Revised Developed Design Report Separable Portion No.2 Lytton Road Pump Station SP298. Including the following	213
		Introduction	
		Design Summary	
		Drawings	
		Input Design Data	
		Developed Design	
		Environmental Management	
		Permits and Approvals	
		List of Appendices A to I	











# Australia Trade Coast Sewer Project Contract No. BW 30137-02.03

## *Revised Developed Design Report Separable Portion No. 2 Lytton Road Pump Station SP298*

August 2004

---

Brisbane Water

---

### Awards won in 2003



Winner  
Engineering  
Excellence Award  
Category: Project Management  
Highly Commended  
Engineering  
Excellence Award  
Category: Project Management



Winner  
National and Queensland  
Case Earth Award  
Category 3: Environmental  
Excellence - projects over  
\$10 million



Highly Commended  
Queensland Stormwater  
Industry Association  
State Award  
Category: Major W/SUD Project  
>\$1.0 million

**Stormwater**



Minister's Grand Prize  
Healthy Waterways Awards  
Category: Industry Award

Finalist  
Healthy Waterways Awards  
Category: Industry Award



Commendation  
Public Domain Awards  
Category: Bridges



Parsons Brinckerhoff Australia Pty Limited ACN 078 004 798 and  
Parsons Brinckerhoff International (Australia) Pty Limited ACN 006 475 056  
trading as Parsons Brinckerhoff ABN 84 797 323 433

12th floor, IBM Centre  
348 Edward Street  
Brisbane Qld 4000  
GPO Box 2907  
Brisbane Qld 4001  
Australia  
Telephone +61 7 3218 2222  
Facsimile +61 7 3831 4223  
Email brisbane@pb.com.au

ABN 84 797 323 433  
NCI Certified Quality System ISO 9001

2138110B-RPT018Cic

©Parsons Brinckerhoff Australia Pty Limited and Parsons Brinckerhoff International (Australia) Pty Limited trading as Parsons Brinckerhoff ("PB"). [2004]

Copyright in the drawings, information and data recorded in this document ("the information") is the property PB. This document and the information are solely for the use of the authorised recipient and this document may not be used, copied or reproduced in whole or part for any purpose other than that for which it was supplied by PB. PB makes no representation, undertakes no duty and accepts no responsibility to any third party who may use or rely upon this document or the information.

Author: Ian Cameron, Design Manager.....

Signed: .....

Reviewer: Victor Bowyer, Pump Station Designer .....

Signed: .....

Approved by: Ian Cameron, Design Manager.....

Signed: .....

Date: 6 August 2004, Revision C.....

Distribution: Brisbane Water .....



# Contents

	Page Number
<b>1. Introduction .....</b>	<b>1</b>
<b>2. Design summary .....</b>	<b>2</b>
2.1 Lytton Road SP298	2
2.1.1 Pump station	2
2.1.2 Construction access	2
2.1.3 Operations and maintenance access	2
2.2 Associated rising main	2
<b>3. Drawings.....</b>	<b>3</b>
<b>4. Input design data .....</b>	<b>6</b>
4.1 Survey	6
4.2 Public utility plant (PUP) location	6
4.2.1 Dial Before You Dig (DBYD)	6
4.2.2 Lytton Road SP298	6
4.2.3 On-site service location	6
4.3 Service authorities	6
4.4 Geotechnical information	7
4.4.1 Brisbane Water	7
4.4.2 Coffey Geosciences	7
4.4.3 Parsons Brinckerhoff	7
4.4.4 Settlement issue	8
4.5 Land and property issues	9
<b>5. Developed design .....</b>	<b>10</b>
5.1 Lytton Road SP298	10
5.1.1 Site	10
5.1.2 Structures	10
5.1.3 Design construction requirements	11
5.1.4 Structural design outcomes	12
5.1.5 Construction methods	13
5.1.6 Duty points	13
5.1.7 Pumps	13
5.1.8 Starters	13
5.1.9 Discharge system	14
5.1.10 Power supply	14
5.1.11 Controls and instrumentation	14
5.1.12 Control philosophy	14
5.1.13 Water hammer analysis	15
5.1.14 Odour and septicity equipment	17
5.2 Associated rising main	17
5.2.1 Pipe sizing	17
5.2.2 Pipe material	17
5.2.3 Pigging point	17
5.2.4 Siphoning issue	18
5.2.5 Momentum issue	18
5.3 Changes since tender design	18
<b>6. Environmental management.....</b>	<b>20</b>
<b>7. Permits and approvals .....</b>	<b>21</b>



Australia Trade Coast Sewer Project  
 Contract No. BW30137-02.03  
 Revised Developed Design Report  
 Separable Portion No. 2  
 Lytton Road Pump Station SP298

## Contents (continued)

Page Number

### List of appendices

Appendix A	Permits and approvals
	A1 — S51 Fisheries Act
	A2 — Brisbane City Council (DRS)
	A3 — POBC
Appendix B	Communications
	B1 — Energex
Appendix C	Design Calculations SP298
Appendix D	Odour and Septicity Study (In Progress)
Appendix E	Geotechnical Information
	E1 — Coffeys Reports
	E2 — PB Report
Appendix F	Dynamic Surge Analysis Information
Appendix G	SUR Plan and RP Plan
Appendix H	Control Philosophy
Appendix I	Cardno MBK Structural Report



# 1. Introduction

This Developed Design Report has been prepared in accordance with the requirements of Section 1.12.1 of Annexure 4:Part 1 (Engineering Design) to the Contract.

The Report consolidates, in relation to Separable Portion 2, design information relating to the underlying design concepts, calculations and assumptions, correspondence relating to discussions with statutory authorities and other relevant stakeholders, and details permits and approvals that have been obtained for the Lytton Road SP298 pump station and associated rising mains.

Separable Portion 2 consists of:

- design and construction of a new sewage rising main between the proposed Lytton Road SP298 and the Brisbane River;
- design and construction of a new sewage rising main under the Brisbane River;
- design and construction of new sewage rising main from the Brisbane River (Yarra Street) to proposed Serpentine Road SP300.

The above works are described in the *Separable Portion 2 Pipelines Developed Design Report*. The following SP2 works are described in this report.

This design report has been prepared for the following proposed works:

- Lytton Road SP298 pump station works.

It should be noted that a separate design report has been prepared for the proposed Serpentine Road SP300 pump station.

This Design Report has been revised to reflect Leighton Contractor review comments and Brisbane Water (BW) comments provided for the SP299 Viola Place Design Report (as applicable to SP298).

This Design Report supersedes the previous Design Report dated 16 July 2004.

## 2. Design summary

### 2.1 Lytton Road SP298

#### 2.1.1 Pump station

The flow required to be pumped by SP298 (160 L/s) was nominated by BW in the tender documentation.

#### 2.1.2 Construction access

For the construction of SP298 and associated rising main to the Brisbane River, construction access will be available from Lytton Road.

#### 2.1.3 Operations and maintenance access

Permanent access to SP298 will be maintained off Lytton Road.

The proposed roadworks associated with SP298 have been designed for articulated trucks as instructed by BW.

### 2.2 Associated rising main

The Separable Portion 2 pipeline associated with the Lytton Road SP298 may be summarised as follows:

Section	Length	Pipe Materials
SP298 to River	606 m	DN450 PN12.5 PE100
River Crossing	749 m	DN400 PN20 PE100
River to SP300	2073 m	DN450 PN12.5 PE100
<b>Total</b>	<b>3428 m</b>	



### 3. Drawings

The Developed Design Report should be read in conjunction with the following design drawings:

#### Lytton Road SP298

Drawing No	Description
486/5/7-WR101/000	Drawing List
486/5/7-WR101/020	Locality and Site Plan
486/5/7-WR101/021	Road Plan
486/5/7-WR101/022	River Access Road Plan
486/5/7-WR101/023	Road Sections
486/5/7-WR101/024	General Arrangement
486/5/7-WR101/025	Pump Station Overflow
486/5/7-WR101/026	Roof Plan
486/5/7-WR101/030	Sectional Plan
486/5/7-WR101/031	Sections
486/5/7-WR101/032	Structural – General Notes
486/5/7-WR101/033	Concrete Details-1
486/5/7-WR101/034	Concrete Details-2
486/5/7-WR101/035	Concrete Details-3
486/5/7-WR101/036	Reinforcement Details-1
486/5/7-WR101/037	Reinforcement Details-2
486/5/7-WR101/038	Reinforcement Details-3
486/5/7-WR101/039	Future Pig Launcher Concrete Details
486/5/7-WR101/040	Odour Scrubbing and Septicity Control
486/5/7-WR101/041	Future Pig Launcher
486/5/7-WR101/042	Future Pig Launcher Reinforcement Details
486/5/7-WR101/043	Hardstand and Ladder Details
486/5/7-WR101/050	Rag Reduction Tube for the Vega Level
486/5/7-WR101/051	Power Distribution Schematic Diagram
486/5/7-WR101/052	Pump 01 Schematic Diagram
486/5/7-WR101/053	Pump 02 Schematic Diagram
486/5/7-WR101/054	Motorised Valve 01 Schematic Diagram
486/5/7-WR101/055	Motorised Valve 02 Schematic Diagram
486/5/7-WR101/056	Generator Control Schematic Diagram
486/5/7-WR101/057	DC Power Supply Schematic Diagram
486/5/7-WR101/058	MITS RTU Digital Input



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

<b>Drawing No</b>	<b>Description</b>
486/5/7-WR101/059	MITs RTU Digital Input
486/5/7-WR101/060	MITs RTU Digital Output
486/5/7-WR101/061	MITs RTU Analogue Input
486/5/7-WR101/062	PLC Digital Inputs Slot 3
486/5/7-WR101/063	PLC Digital Inputs Slot 4
486/5/7-WR101/064	PLC Digital Inputs Slot 5
486/5/7-WR101/065	PLC Digital Inputs Slot 6
486/5/7-WR101/066	PLC Analogue Inputs Slot 7
486/5/7-WR101/067	PLC Analogue Inputs Slot 8
486/5/7-WR101/068	PLC Analogue Inputs Slot 9
486/5/7-WR101/069	Switchboard General Arrangement
486/5/7-WR101/070	Switchboard Construction Notes
486/5/7-WR101/071	Equipment List
486/5/7-WR101/072	Switchboard Construction Details
486/5/7-WR101/073	Switchboard Label Schedule Diagram
486/5/7-WR101/074	Electrical Site Layout
486/5/7-WR101/075	Cabling Block diagram
486/5/7-WR101/076	Cable Schedule
486/5/7-WR101/077	Cathodic Protection Wiring Diagram
486/5/7-WR101/078	Sump Pump Electrical Schematic

### **BCC Standard Drawings**

486/5/25-SC002/1	"G" Type Maintenance Hole General Arrangement
486/5/25-SC002/2	"G" Type Maintenance Hole Top Slab Reinforcement
486/5/25-SE001/1	Standard Overflow Flap Type 1 Chamber Details
486/5/25-SE001/2	Standard Overflow Flap Type 1 Top Slab & Flap Details
486/5/25-SF002/1	Maintenance Hole Cover Sewer Class B – Conc Infill Frame Details
486/5/25-SF002/2	Maintenance Hole Cover Sewer Class B – Conc Infill Frame Details
486/5/25-SF002/3	Maintenance Hole Cover Sewer Class B – Conc Infill Lifting Hole Details
486/5/25-SF003/1	Maintenance Hole Cover Sewer Class B – Bolt Down Frame Details
486/5/25-SF003/2	Maintenance Hole Cover Sewer Class B – Bolt Down Cover Details
486/5/25-SF003/3	Maintenance Hole Cover Sewer Class B – Bolt Down Cover Details





Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

486/5/25-SF009	Standard M.S. Ladders and Associated Fittings
486/5/25-S25	Standard 2440 Dia Sewage Pump Station Section B
486/5/25-S26	Standard 2440 Dia Sewage Pump Station Section C
486/5/25-S27	Standard 1830 Dia Dia Grit Collector Maintenance Hole Details
486/5/25-S28	Standard 1830 Dia Grit Collector Maintenance Hole Details
486/5/25-S29	Standard 1830 Dia Grit Collector Maintenance Hole Details
486/5/25-S30	Standard 2440 Dia Sewage Pump Station Vent Pole Details
486/5/25-S31	Standard 2440 Dia Sewage Pump Station Potable Water Details
486/5/25-S32	Standard 2440 Dia Sewage Pump Station Level Probe Bracket Detail
486/5/25-S33	Standard 2440 Dia Sewage Pump Station Level Probe Bracket Detail
486/5/25-S34	Standard 2440 Dia Sewage Pump Station Anode Hook Detail
486/5/25-S35	Standard 2440 Dia Sewage Pump Station Electrical Connection Box Detail
486/5/25-S50	Standard 1830 Dia Grit Collector Maintenance Hole Bar Screen Details
486/5/25-S51	Standard 1830 Dia Grit Collector Maintenance Hole Bar Screen Details

### IPWEAQ Standard Drawings

R-0080	Kerbs and Channels Profiles and Dimensions
G-0030	Electrical Cable Drawing Pits
G-0041	Fencing Chain Wire Security Fencing
D-0050	Field Inlet and Overflow Gully Type 1 and Type 2
D-0080	Inlet and Outlet to Stormwater Drains

### HALLCO Standard Drawings (Sample only)

BCC-03	1650x1600 Valve Pit Cover details of Recesses for Cover Installation
BW-1/1	Recess Details – P.S. 1/1 For 2400x2600 C/O cover for Cover Installation
BW-01	Multi-part Removable Alum. Cover
BW-02	Multi-part Removable Alum. Cover
BW-03	Multi-part Removable Alum. Cover
BW-10	Multi-part Removable Alum. Cover
HE-02	End & Centre Hinge Details

## **4. Input design data**

### **4.1 Survey**

BW provided topographic survey in the vicinity of SP298. Additional survey has been carried out by Leighton Contractors to validate the survey provided by BW and to provide supplemental information, including the location of services, location of RP boundaries and changes to ground profiles that have occurred since the BW survey was carried out.

### **4.2 Public utility plant (PUP) location**

#### **4.2.1 Dial Before You Dig (DBYD)**

DBYD searches have been carried out and relevant services are shown on the Drawings.

#### **4.2.2 Lytton Road SP298**

Details of existing PUP in the vicinity of Lytton Road SP298 have been obtained from the as-constructed drawings and potholing by Leighton Contractors and relevant services are shown on the Drawings.

#### **4.2.3 On-site service location**

All services, identified from DBYD information, site inspection and discussions with service authorities, which may influence the alignment or construction of the works have been located on site by potholing and surveying. The location and level of each service has been surveyed and recorded.

### **4.3 Service authorities**

Following a review of DBYD searches information, field verification of service locations was completed by LCPL construction personnel using visual inspection and pipeline location equipment.

On-site meetings with all relevant service authorities have also been completed either to verify the location of services and or to supervise the potholing and surveying of buried services.

The detailed services information was provided to drafting staff to design the pump station and associated pipelines.



## 4.4 Geotechnical information

### 4.4.1 Brisbane Water

For the proposed Separable Portion 2 pipeline works, BW had completed extensive geotechnical investigations for the river crossing and for the pipeline routes north and south of the Brisbane River.

A significant volume of geotechnical reports was included in the tender documents for the project, the most relevant of which for the SP298 works were the following:

- *Geotechnical Data Report, Australia Trade Coast Sewerage Project, Brisbane River Crossing, Lytton to Pinkenba, BCC, City Design, March 2003.*

During the detailed design phase of the project, BW supplied the following geotechnical report:

- *Supplementary Geotechnical Data Report, Australia Trade Coast Sewerage Project, Lytton Road to Brisbane River, Lytton, BCC, City Design, 7 November 2003.*

We have not included the above geotechnical reports in this Developed Design Report, due to the volume of information included in the above reports, and readers are referred to the existing documentation held by BW.

### 4.4.2 Coffey Geosciences

Coffey Geosciences (Coffeys) were commissioned by PB to complete settlement investigations at the SP298 Lytton Road pump station site.

A further assessment of the site was undertaken by Coffey Geosciences to indicate the likely settlements of the site under the additional loading to be applied to the site by the construction of the pump station.

A total settlement of 80 mm is predicted after 50 years for an applied loading of 10 kPa, with a possibility of 33% that this settlement will be exceeded by more than 10%. A copy of the Coffeys reports are included in Appendix E1.

### 4.4.3 Parsons Brinckerhoff

Parsons Brinckerhoff (PB) completed a geotechnical review of available information for SP298 based upon previous BW geotechnical investigations.

A copy of the PB geotechnical report is included in Appendix E2 (and includes comments upon SP299 and SP300 also).

#### 4.4.4 Settlement issue

Due to the poor ground conditions identified at SP298, the project team recommended that a settlement analysis be completed to determine likely long term settlement rates.

Geotechnical engineers from PB initially reviewed the available geotechnical information. This review confirmed the weak nature of the underlying soils and showed that settlements were likely under any additional loading. It was determined that the additional allowable bearing pressure should be limited to 15 kPa at a depth below RL-6.8m to limit settlement to 25–30 mm.

PB completed a preliminary settlement analysis which is included in Appendix E2.

Coffey Geosciences were subsequently commissioned to complete a study, the results of which are included in Appendix E1. Additional information is also included in Design Minutes of 2 June 2004.

The following results summarise the calculated settlement rates:

Consultant	Settlement Information
Parsons Brinckerhoff (Memo 27/4/04)	<ul style="list-style-type: none"> <li>Not greater than 25–30 mm (long term settlement)*</li> <li>About 150 mm settlement from dewatering excavation*</li> </ul>
Coffey Geosciences (Design Minutes 2/6/04)	<ul style="list-style-type: none"> <li>20 kPa loading produces 75 mm settlement in 0.1 year</li> <li>Benefit of preloading</li> <li>Settlement of 50–100 mm expected after 10 years</li> <li>Differential settlement could be 25–50 mm</li> </ul>

Note: \*Based upon limited data.

Based upon the settlement investigations to date the following recommendations have been adopted:

- preloading of fill for construction purposes is recommended (fill placed at end of May 2004);
- move pump station an extra three metres away from the mangrove lined open drain;
- combine valve pit, pump well, and grit collector into a single structure to minimise differential settlement and to prevent tilting of structures; and
- adopt “neutral buoyancy” design for structures.





## 4.5 Land and property issues

There are a number of land and property issues which have impacted upon the design and construction of the proposed SP298 works, as detailed below:

Lytton Road SP298:

- Port of Brisbane Corporation (POBC) transfer of land to BCC for SP298 Lytton Road access and drainage reserve and vegetation/wildlife corridor; and
- Development Approval (DA) from POBC for the proposed works;

Part of Lot 719 SP110610 has been excised (2308 m<sup>2</sup>) to provide vehicular access and a route for rising mains and services into SP298. (Refer to Appendix G for detailed information.)

A Development Application (DA) was submitted to POBC for the proposed works as part of the purchase agreement with the Brisbane City Council (BCC) for the land excised from Lot 719 SP110610. The DA was approved by POBC.

## 5. Developed design

### 5.1 Lytton Road SP298

#### 5.1.1 Site

The Lytton Road SP298 pump station is located on land in the process of ownership being transferred from POBC to Brisbane City Council and described as part of Lot 719 RP110610.

The Lytton Road SP298 site adjoins the common boundary with Lot 716 SP110610 which with Lot 713 SP110610 will form a vegetation corridor linking Lytton Road to the Brisbane River.

It should be noted that the SP1 pipeline works have been designed and constructed so that Pritchard Street SP085 pumps to Gibson Island WWTP, until such time as the SP298 pump station is commissioned.

When SP298 is commissioned, manually operated valves on Lytton Road at the entrance to SP298 will be operated to direct Pritchard Street SP085 and Kianawah Road SP049 flows into SP298.

#### 5.1.2 Structures

Cardno MBK were responsible for the structural design of the Lytton Road Pump Station SP298.

The structures comprising the pump station include the wet well, valve pit, grit collector manhole, ferric chloride dosing area slab, odour scrubber pad, transformer base, switchboard base, generator pad, pig launcher pit and unlet valve pit.

Structures will include:

- 3.6 m diameter RC wet well with valve chamber and grit chamber as single structure;
- non-standard BW grit collector maintenance hole (volume increased);
- an inlet valve pit with actuated valves on rising mains from Kianawah Road SP049 (and Pritchard Street SP085); and
- overflow (without screen) discharging to the open drain adjacent to SP298.

Concrete structures have been designed in accordance with *AS 3600 Concrete Structures* except where *AS 3735 Concrete Structures for Retaining Liquids* requires greater cover to steel reinforcement.

It should be noted that the grit chamber design has been modified to include the following features:

- submerged inlet with 500 mm above obvert of inlet pipe to invert level of connecting pipe (375 ND) to wet well; and
- size of grit chamber increased by inserting 500 mm straight section to elongate the structure between the 900 ND radius circular ends; and
- the overflow has been relocated from the grit collector to the wet well.

### 5.1.3 Design construction requirements

#### Settlement

It was realised that settlement of the pump station structures was inevitable as the minimum depth of fill applied to the site for the construction of the required pavements would apply significant loading and result in consolidation of the underlying soil. As a result, design was directed towards the design of structures with uniform foundation bearing pressures to ensure that structures would settle uniformly, rather than tilting. The performance of the pump station would not be affected by uniform settlement provided sufficient flexibility was allowed in connecting pipework to allow for differential movement between adjacent structures. Similarly, any pipelines leading to or from the pump station would be not affected by the consolidation as the settlement bowl would extent out from the pump station due to the depth of compressible material.

#### Construction issues

The tender method of construction for the pump station was developed by Coffey Geosciences Pty Ltd (Reference facsimile dated 16 June 2003 to PB). This method comprised the use of an open excavation above the water table and a steel sheet pile supported excavation for the structures below the water table.

Leighton Contractors developed an alternative method of construction for the pump station that eliminated the requirement for steel sheet piling. This alternative method recognised the strength of the near surface soils and the ability for open excavations to remain stable for a limited period of hours. The excavation would be made and stabilised with a rapidly placed internal lining of mass concrete.

The near surface soils have been observed to have a low permeability, indicating that ground water seeping into the open excavations will be unlikely to be a major issue and can be readily managed using small drainage sumps and dewatering pumps during the work.

#### Design issues

There are two design cases for the in-ground pump stations.

- Provision of sufficient mass in the structure to overcome buoyancy forces under high water table conditions. It is considered that the design should allow for the water table to be located at the ground surface. The weak soil conditions also indicate that no allowance should be made for friction on the surrounding soil assisting to hold down the structures.



- Limiting the additional bearing pressure to the underlying soils during dry conditions when the ground water level is low.

In both cases, the centre of buoyancy and the centre of mass should correspond to limit tilting.

#### 5.1.4 Structural design outcomes

##### General arrangement

The design process considered several arrangements of the valve pit, pump well and grit collector manhole to develop a layout acceptable to Brisbane Water that would address the geotechnical issues of the site.

The design development arrangements considered were as follows.

- A standard arrangement of valve pit and wet well combined in a single structure was considered. It was found that uniform foundation bearing pressures could not be achieved to ensure uniform settlement. The use of fly ash as backfill to the structures to control settlement was considered but was not viable due to the overall settlement of the pump station.
- The use of separate valve pit and wet well structures was considered as each structure would have uniform foundation bearing pressures and hence would settle uniformly. The use of extended foundation slabs to limit non-uniform settlement was considered. Brisbane Water rejected this arrangement.
- It was found that an acceptable bearing pressure distribution could be obtained by combining the valve pit, wet well and grit collector manhole into a single structure as the valve pit would balance the grit collector manhole opposite from the valve pit.

The final solution comprises the valve pit and grit collector balancing each other on opposite sides of the wet well. The grit collector manhole is attached to the wet well by twin reinforced concrete walls.

It was preferable to locate the grit collector manhole adjacent to the pump well to minimise the requirements for the structural members joining the wet well and grit collector manhole. BW required the grit collector to be located further from the wet well and this resulted in a significant increase in the size of the connecting members.

The other structures, including the ferric chloride dosing area slab, odour scrubber pad, transformer base, generator slab, pig launcher pit and inlet valve pit were designed with uniform foundation bearing pressures. The majority of these structures were sized to limit the maximum additional bearing pressure applied to the subgrade.

##### Structural details

All structures were detailed in reinforced concrete. All significant structures were founded on a compacted clean sand-bedding layer placed on the soft subsoils on completion of excavation to provide a sound-bearing surface. Blinding concrete was specified to provide a firm surface for construction of the structures.

Sand was also specified to be used for the backfilling of excavations as this material can be readily placed and compacted using light equipment.

A jointed reinforced concrete pavement was designed for the access roadway to the pump station to provide a stable base for maintenance vehicle parked at the pump station. The pavement consists of a 200 mm concrete slab and 200 mm sub-base of CBR 25 material overlying the natural subgrade or construction fill.

The foundation for the substation comprises a ground slab at depth supporting a standard Energex unculvert precast transformer base and substation plinth.

### **Corrosion**

The pump station is located in recent alluvium identified as having significant potential acid sulphate soil conditions and groundwater very aggressive towards concrete structures. The concrete structures should be protected against groundwater attack.

However, the general soil permeability is low and little groundwater movement is expected once equilibrium conditions develop following the completion of construction. An appropriate treatment to protect the concrete structures against attack include a double layer of polyethylene sheeting either laid under the structures prior to the pouring of concrete and placed on completed concrete surfaces prior to backfilling. This protection should extend under all foundations and walls located below RL 2.2 m.

An exposure classification of B2 is considered appropriate for concrete protected against the corrosive groundwater as described above.

## **5.1.5 Construction methods**

Concrete structures containing sewage will be cast in-situ in accordance with BW's requirements. Constructability reviews by LCPL have indicated that sheetpiling will not be required for construction of the wet well. The lower section of the wet well will be constructed using a blinding layer of concrete against the excavation and an internal form for the wet well.

### **5.1.6 Duty points**

160 L/s at 26.0 m with one pump operating (peak). (See Appendix C for additional information.)

### **5.1.7 Pumps**

Two Hidrosta H08K-M02R 68 kW submersible pumps in duty/standby arrangement. (See Appendix C for additional information.) The power supply for the pumps and associated equipment on the site will be provided from a pad mounted transformer within the fenced perimeter of the site.

### **5.1.8 Starters**

Two Danfoss VLT8000 variable speed drives.

### 5.1.9 Discharge system

DN200/DN250 DICL discharge pipework connected to a single DN450 PE100 PN12.5 rising main with magnetic flowmeter. The HDD river crossing will be constructed in DN400 PE100 PN 20 pipework, with the remaining rising main to SP300 constructed in DN450 PE100 PN 12.5 pipework.

### 5.1.10 Power supply

Negotiations with Energex–Greenslopes have resulted in a commitment to provide an underground power supply to the Lytton Road SP298 site from the opposite side of Lytton Road.

The underground power supply to SP298 will be constructed in conduits terminating at a pad mounted transformer (500 kVA) constructed on the northern side of the access driveway.

A contribution by BW for the proposed works is required (see Appendix B1).

SP298 will incorporate a 150 kVA diesel powered backup generator that will cut in if the main power supply is unavailable. The generator will have sufficient capacity to start and run one of the duty pumps, plus any essential loads from ancillary equipment such as lighting, chemical dosing and control gear.

### 5.1.11 Controls and instrumentation

The following equipment is proposed:

- one “multitrode” digital level switch;
- one ABB Magmaster magnetic flow transmitter controlling pump set points of 90 L/s and 160 L/s;
- one Vega D84 analogue pressure transmitter;
- PLC to be free-issued by BW; and
- telemetry equipment to be free-issued by BW.

### 5.1.12 Control philosophy

The incoming flows to SP298 will come from the Pritchard Street SP085 pump station and the Kianawah Road SP049 pump station.

Sewage from the developing SP298 catchment will be discharged into the inlet valve pit at SP298, under pressure to the grit chamber and then gravitate to the SP298 wet well.

An actuated valve on the Kianawah Road SP049 rising main will regulate the amount of flow discharged to SP298. Under some operating conditions, BW will direct flows from Kianawah Road SP049 towards the Gibson Island WWTP, rather than to SP298.

As part of contingency planning, BW has requested that an actuated valve be installed on the SP085 Pritchard Street rising main so that SP298 may be bypassed for operational purposes. (See details in S2.2.7 of Functional Specification [Appendix H].)





SP298 will operate as a flow banded pump station using the variable speed drives (VSDs) which will be supplied and installed. The DN450 ABB Magmaster electromagnetic flowmeter on the discharge line will be used for a control function for the pump set points.

The control philosophy for the SP298 pump station is included in Appendix H.

### 5.1.13 Water hammer analysis

#### Initial assessment

Design Detail and Development was commissioned by PB as a specialist sub-consultant to complete the water hammer analysis for the overall project.

The water hammer report for SP298 and associated rising main Separable Portion 2 works is included in Appendix F, and the following conclusions were reached:

- *transient pressures are within the design rating of the pipe material;*
- *compliance with WSA 01 has been met;*
- *check valves do not require counterweights;*
- *the use of variable speed drives for the pumps will further reduce any possible fatigue damage of pipeline components or the pumps; and*
- *the manual air vent should be changed to a DN100 automatic double acting air valve.*

Design Detail and Development have completed water hammer modelling work for a number of options for the provision of double acting air valves.

The least air is drawn into the SP298 rising main when two double acting air valves are constructed, with the following volumes of air drawn in upon pump trip and pump stop:

- DN100 DAV at SP298 (0.7 m<sup>3</sup>); and
- DN100 DAV at CH492 (5.3 m<sup>3</sup>).

#### Subsequent assessment

On the basis that the BW Operations Group does not prefer air valves because of odour and other operational issues, PB was requested to re-consider the design of the SP298 to SP300 pipeline and to eliminate the air valves.

Following a review of possible options by PB Principal Engineer David Kent, a change in pump philosophy to flow banding was identified as a possible solution for momentum and water hammer issues:

- upper part of wet well 160 L/s; and
- lower part of wet well 90 L/s.

Design Detail and Development was subsequently requested to run new scenarios for the water hammer analysis to determine if the air valves could be eliminated for both normal pump stop and power failure using the revised pump control philosophy.



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

The following parameters were modelled for the new scenarios, with the elevated inlet at SP300 at RL 2.25, as outlined in the PB letter to Leighton Contractors dated 4 August 2004 (included in Appendix F).

Flow banding has been adopted as follows:

- Duty A to 160 L/s RL 0.25
- Duty A to 90 L/s RL -0.18
- Stop Duty B RL -0.38
- Stop Duty A RL -0.98

The scenarios which were modelled were as follows:

- pump stop is normally from 90 L/s;
- pump stop is normally controlled from 160 L/s to 90 L/s;
- single pump trip at 90 L/s, due to loss of power; and
- single pump trip at 160 L/s, due to loss of power.

#### Modelling results

A copy of the "Supplement to the Review of Unsteady State Hydraulic Design, SPS 298 Lytton Road to SPS 300 Serpentine Road" (2 August 2004) is attached as Appendix F (in this report).

The extra water hammer analysis may be summarised as follows:

Event	Integrated Volume (cu. m.)	Minimum Volume Available to BWL (cu. m.)
90 L/s Single Pump Trip Due to Loss of Power	1.85	3.3
160 L/s Single Pump Trip Due to Loss of Power	3.75	9.5

Note: 3.6 m diameter pump well has a cross-sectional area of 10.2 m<sup>2</sup>.

**Conclusion:** The SP298 wet well has sufficient capacity not to empty under normal stop or power failure mode provided the nominated set points are used with VSD control of the pumps.

On the basis of the successful water hammer modelling the following revised settings are recommended:

- Duty A to 160 L/s RL 0.15
- Duty A to 90 L/s RL -0.30
- Stop Duty B RL -0.60
- Stop Duty A RL -1.10

The final pump settings will be optimised during the commissioning of the SP298 pump station. This will allow minimisation of the volume of sewage in the wet well after a normal pumping cycle.



The following conclusions were drawn from the additional water hammer review of the system of Lytton Road PS to SPS 300 Serpentine Road PS DN 450 PE100 PN 12.5/DN 400 PE100 PE20 pipeline that crosses the Brisbane River:

- *transient pressures are within the design rating of the pipe material;*
- *compliance with WSA 01 has been met;*
- *check valves do not require counterweights;*
- *the use of variable speed drives for the pumps will further reduce any possible fatigue damage of pipeline components or the pumps; and*
- *two speed operation overcomes the concern by Brisbane Water of using air valves on sewage systems.*

Readers are referenced to the "Supplement to Review of Unsteady State Hydraulic Design" (2 August 2004) included in Appendix F.

#### **5.1.14 Odour and septicity equipment**

A specialist odour and septicity sub-consultant, The Odour Unit has been commissioned by PB to analyse liquid and gas phase results sampled by BW.

The need for odour scrubbing and/or septicity control will be investigated further following receipt of the report from The Odour Unit.

It is likely that odour scrubbing equipment and septicity control equipment will be constructed at SP298 at this time.

A standard BW 12.5 m high vent pole will be constructed to vent the wet well and grit chamber.

## **5.2 Associated rising main**

### **5.2.1 Pipe sizing**

The sizing of the rising mains has been based on a suitable flow velocity to provide a trade-off between minimising headloss and maximising slime stripping and sediment transport.

The rising main from the Lytton Road SP298 to will be DN450/DN400 (River Crossing section).

### **5.2.2 Pipe material**

All rising mains will be constructed from PE100 PN12.5 pipe, except for the river crossing which will be constructed in PE100 PN20 pipe.

### **5.2.3 Pigging point**

The installation of a pigging point is recommended to allow for the removal of grit and slimes between SP298 and SP300. The SP300 inlet works will be designed to receive and recover

the pig launched at SP298. (BW has decided at this time not to proceed with the construction of the pigging point.)

#### 5.2.4 Siphoning issue

In order to prevent the siphoning of raw sewage from the wet well of SP298, the following measures will be implemented:

- use of flow banded controls for SP298 pumps using VSD control; and
- construction of an inlet at SP300 with top water level of RL 2.25 m AHD.

#### 5.2.5 Momentum issue

In the event of a sudden failure of the SP298 pumps (e.g. power failure), prior to the standby generator activating, there was some risk of the momentum of the water column to drain the SP298 pump well. Additional water hammer modelling has however identified a solution based upon flow banded pumping from SP298.

The momentum issue can be controlled by using VSD drives, flow banded pumping at 90 L/s and 160 L/s and the elevated inlet at SP300.

### 5.3 Changes since tender design

The following changes have been catalogued between the tender drawings and the developed design drawings:

#### General arrangement

- Linear pump station layout beside open drain.
- Provision for articulated truck access.
- Inlet valve pit rather than gravity inlet.
- Combined structure grit collector/pump well/valve pit.

#### Inlet pipework

- Additional high level pipe between grit chamber and wet well (added and deleted by BW).
- Extra actuated valve added in inlet valve pit.

#### Pumps

- Change to Hidrostral pumps — 68 kW (from Flygt pumps — 44 kW).

#### Pigging point

- Pigging point recommended and included in design (construction on hold).

#### Level of pump station

- Reduced from RL 4.0 m to RL 2.75 m AHD.



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

#### **Electricity supply**

- Change from overhead 11 kV to underground supply to pad mounted transformer.

#### **Rising main**

- Elevated breather air release at RL 2.25 m at SP300 inlet works.

## 6. Environmental management

Environmental management issues associated with the proposed works include the following:

- presence of marine clays;
- presence of mangroves which need to be protected;
- tidal drains in the vicinity of the proposed works;
- the presence of acid sulphate soils;
- the presence of high groundwater levels; and
- declared Fire Ant area.





Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## 7. Permits and approvals

The following permits and approvals have been obtained and are contained in Appendix A:

- S51 Fisheries Act
- BCC/DRS
- POBC







Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix A

---

Permits and approvals

A1. S51 Fisheries Act

A2. Brisbane City Council (DRS)

A3. POBC





Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## A1. S51 Fisheries Act

---

23-APR-2004 FRI 14:24

FAX NO.

P. 02



Department of  
Primary Industries

Enquiries: Matthew Johnston  
Telephone: +61 7 3817 8554  
Your Ref: CD/44-040201/JEE9  
Our Ref: 04DEC530/533

23 April 2004

Mr Peter Turnbull  
Product Manager  
City Design  
Brisbane City Council  
Locked Mail Bag 6986  
ALBION QLD 4010

Dear Mr Turnbull

**Section 51 Fisheries Act application**

**Proposed ATC sewer main – Marine Parade, Eagle Farm Road and Unknown Road,  
Pinkenba, and Clunies Flat section, Lytton**

I refer to your application of 19 December 2003, and your correspondence, for a Permit under Section 51 of the *Fisheries Act 1994* to remove marine plants associated with the construction of the Australian Trade Coast (ATC) sewer pipeline at Marine Parade, Eagle Farm Rd, Serpentine Rd and Unknown Rd, Pinkenba, and Clunies Flat, Lytton.

I would advise that consideration of your application has now been finalised. Please find attached:

- A Permit (No. 04SODB0007), and a Plan (No. 04SODB9543MP0007), to authorise removal / disturbance of marine plants as requested;
- A Receipt (No. 1400290583 dated 11 March 2004) for the \$1353.00 Assessment Fee (Cheque Number 118779).
- Invoice No. 530266 to the Brisbane City Council for \$600.00 Survey Fee.

The Department of Primary Industries is required to notify and consider comments of relevant indigenous groups prior to final assessment of any applications for approvals under Section 51 of the *Fisheries Act*. The relevant indigenous groups were notified. QF6 will advise the relevant Indigenous bodies of the issue of Permit No. 04SODB0007.

Please note that the onus is on you, the Permittee, to be aware of the provisions of the *Fisheries Act 1994* and *Fisheries Regulations 1995* with respect to the issue of Permits for the removal/disturbance of Marine Plants. A list of the most relevant sections is attached for your information.

CC: Mr Don Garnett, District Support Officer, Qld Boating & Fisheries Patrol, PO Box 10,  
PINKENBA QLD 4008

**Queensland Fisheries Service**

Southern Fisheries Centre  
13 Beach Road  
Box 78  
Deception Bay Queensland 4508

Facsimile +61 7 3817 8522  
Email  
Mobile  
Website www.dpi.qld.gov.au  
Call Centre 13 25 23  
RecFind 00/RecFind 40007 GovAus.doc

ABN 78 342 684 030

23-APR-2004 FRI 14:24

FAX NO.

P. 03

Your attention is drawn to the Schedule of Conditions on Permit and the need to comply with all Conditions. You should also be aware that under fisheries legislation there are requirements that all Permit holders must adhere to, and these requirements include:

- the holder is required to make the Permit or a copy available at the works site for inspection at any time by an officer authorised under the *Queensland Fisheries Act 1994*;
- this Permit does not grant permission to pass through or enter upon lands and does not infer the issue of any other Permit or Approval necessary to the purpose proposed.

If you wish to obtain a copy of the legislation it is available from Goprint, 371 Vulture Street, Woolloongabba, Qld, 4102 (Telephone (07) 3246 3399). You must also comply with all other legislation (Local, State and Commonwealth) relevant to your activities. Please note all legislation is law and penalties apply to breaches.

Additionally, QFS would draw your attention to conditions 1, 2 and 4 of the Permit. Failure to notify this Department of the commencement and completion of works by the specified dates is a breach of the Permit conditions and may render the applicant open to prosecution.

I advise that there is provision under the *Fisheries Act* for appeal, under certain circumstances, should you feel dissatisfied with the Authority's decision. For further information you should contact the Secretary of the Fisheries Tribunal on (07) 3239 3734. You should note that a notice of appeal against a decision of the Authority must be lodged with the Tribunal within twenty-eight (28) days after receiving notice of the decision. In special circumstances, the Tribunal may extend the period for filing of the notice of appeal.

If you have any further queries please contact Mathew Johnston on (07) 3817 9554.

Yours sincerely



Dan Mayer  
Habitat Manager (South)  
Fisheries & Aquaculture Development

Att/Enc

23-APR-2004 FRI 14:24

FAX NO.

P. 04

**Fisheries Act 1994 and Fisheries Regulation 1995 Sections referring to marine plants:**

**Fisheries Act**

**Section 4 - Main definitions:-** "aquaculture", "area", "fish", "fisheries resources", "fish habitat", "marine plant", "permit", "tidal land", "tribunal", "unlawfully".

**Section 5 - Fish**

**Section 7 - Fishery**

**Section 8 - Marine plants**

**Sections 32, 33, 34, 35, 36, 39, 40, 41, 42 - Management plans/ process/ content**

**Sections 49, 50, 51, 52, 53, 54, 55, 57, 59, 60 - Authorities**

**Section - 123, 124, 125 - Protection of marine plants, rehabilitation and restoration**

**Section - 196, 197, 198, 199 - Appeals**

**Fisheries Regulations:**

**Section 12, 13 - Management plans/ process/ content**

**Section 34, 39 - Permit issue/ restrictions**

**Section 77 - Aquaculture**

**Section 79 - Authority does not apply**

**Section 85 - Contravening an authority**

**Section 112, 113 - Fees/ payment/ waive**

**Schedule 10 - Fees payable**



Cheques and other negotiable instruments are accepted subject to clearance

Qty	Particulars	Value (incl GST)	GST Amount	Price (incl GST)
1	BCC - APPLIC. FOR MARINE PERMIT	1,353.00	0.00	1,353.00
<div style="text-align: center;"> <p><b>DOCUMENT</b></p> <p><b>SFC - 23 APR 2004</b></p> <p><b>23 APR 2004</b></p> <p><b>DO NOT REMOVE</b></p> <p>REGISTERED VENDOR MUST BE SHOWN ON FRONT COVER.</p> <p>File Location: _____</p> <p>Action By: _____</p> <p>Registered VENDOR CODE: _____</p> </div>				
Amount Paid:		\$ 1,353.00	\$ 0.00	\$ 1,353.00

<b>BRISBANE CITY COUNCIL</b> <b>LOCKED MAIL BAG 6996</b> <b>ALBION 4010</b>	
Name and Address Receipt Details	Customer ABN Date Cheque No Drawn Payment Amount Page
BRISBANE CITY COUNCIL 4000118779 11-03-2004 \$ 1,353.00 1 of 1	4818BANE CITY COUNCIL \$ 1,353.00 1 of 1

**TAX INVOICE/RECEIPT**  
**1400290583**  
 PRIMARY INDUSTRIES BUILDING, 80 ANN ST, GPO  
 BOX 46, BRISBANE QLD 4001.

**Queensland**  
 Government  
 Department of  
 Primary Industries  
 and Fisheries  
 ABN 78 342 684 030



23-APR-2004 FRI 14:24

FAX NO.

P. 05

**QUEENSLAND**  
**FISHERIES ACT 1994**  
**Section 51**  
**FISHERIES REGULATIONS 1995**


**PERMIT NUMBER** 04SODB0007

**MARINE PLANT PERMIT**

This is to certify that THE CHIEF EXECUTIVE OFFICER OF BRISBANE CITY COUNCIL  
 of LEVEL 3 TC BRIERNE CENTRE 315 BRUNSWICK STREET MALL FORTITUDE VALLEY  
 QLD 4006  
 is authorised to: remove, damage, destroy and transplant marine plants  
 at the approved area described as:  
 WITHIN LOT 716 ON SP 110610 AND PART OF LOT 717 ON SP 110610, WESTERN EDGE OF CLUNIES  
 FLAT, as described in DPI Plan No 04SODB0007  
 WITHIN UNCONSTRUCTED ROAD, RESERVE, NAKKARA ROAD AND AN ESTATE ROAD,  
 PINKENBA, as described in DPI Plan No 04SODB0007  
 WITHIN THE CONSTRUCTED ROAD, RESERVE, NAKKARA ROAD AND AN ESTATE ROAD,  
 PINKENBA, as described in DPI Plan No 04SODB0007  
 for the purpose of: construction of part of the Lytton Sewerage Construction Scheme  
 for the period: 1 April 2004 until 31 March 2005  
 Issued at DECEPTION BAY this 29th day of April 2004

Page 1 of 3 of Marine Plant Permit No. 04SODB0007

Delegate of the  
 Chief Executive



**CONDITIONS**

- 1 The District Officer of the Queensland Boating and Fisheries Patrol, PO Box 10, PINKENBA, QLD 4008 (Fax. No. 3860 3550), and the Habitat Manager, Department of Primary Industries and Fisheries, PO Box 76, DECEPTION BAY, QLD 4508 (Fax. No. 3817 9522), must be notified, in writing, of the date of commencement of works, fifteen (15) days prior to the commencement of works.
- 2 Works are only authorised if the holder has notified the Queensland Boating and Fisheries Patrol and the Habitat Manager, Department of Primary Industries and Fisheries of the commencement of works PRIOR to the commencement of those works. Any works commenced without prior notification are deemed not to be authorised.
- 3 A survey fee of \$600.00 (for monitoring and repair preparation) must be paid to the Department of Primary Industries, PO Box 76, DECEPTION BAY, QLD 4508, prior to the commencement of works, but in no case later than thirty (30) days after the effective date of this Permit.
- 4 A written report which must be completed and submitted to the Department of Primary Industries and Fisheries, PO Box 76, DECEPTION BAY, QLD 4508, within fifteen (15) days of completion of works to the District Officer, Queensland Boating and Fisheries Patrol, PINKENBA, and the Habitat Manager, Department of Primary Industries and Fisheries, PO Box 76, DECEPTION BAY, QLD 4508.
- 5 This Permit authorises the holder to carry out the works described in the authorised activities and the approved plans, and the holder must comply with the conditions of the Permit, and the holder must obtain approval from the relevant authorities for any activity not authorised by the Permit.
- 6 The holder must comply with the conditions of the Permit, and the holder must obtain approval from the relevant authorities for any activity not authorised by the Permit.
- 7 At least two (2) signs must be placed at the entrance to the works site in positions where they are clearly visible to the public, and the holder must ensure that the signs are maintained in good condition throughout the duration of the works. The signs must be placed in positions where they are clearly visible to the public, and the holder must ensure that the signs are maintained in good condition throughout the duration of the works.
- 8 The holder must ensure that the works are carried out in accordance with the approved plans, and the holder must ensure that the works are carried out in accordance with the approved plans.
- 9 The holder must ensure that the works are carried out in accordance with the approved plans, and the holder must ensure that the works are carried out in accordance with the approved plans.
- 10 The holder must ensure that the works are carried out in accordance with the approved plans, and the holder must ensure that the works are carried out in accordance with the approved plans.

Page 2 of 3 of Marine Plant Permit No. 0450DB0007

Delegate of the  
Chief Executive

Page 3 of 3 of Marine Plant Permit No. 04S0DB0007

Delegated to the  
Chief Executive

*[Signature]*

**SCHEDULE OF FEES**

Date	Fee	Receipt No	Fee Type
5/01/2004	\$147.00	130282	Marine Plant Permit Fee - 2002 - GST exempt
11/03/2004	\$1,353.00	1400290583	Assessment Fee - Marine Plant Permit - 2003 - GST exempt

**CONDITIONS (continued)**


11 All marine plants authorised for removal, exclusive of those to be used for a restoration project acceptable to the Department of Primary Industries, and other debris, is to be removed from the intertidal zone and disposed of in a neat and tidy manner.

12 The holder must pay the annual fee by the due date each year.

23-APR-2004 FRI 14:25

FAX NO.

P. 08







Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## **A2. Brisbane City Council (DRS)**

---



Contact Name: John Donaghy  
 Telephone: 3403 8888  
 Fax (Direct): 3407 0750  
 Your Ref: 21381108-LTR01

RECEIVED

18 FEB 2004

# 438110B

#39  
RML

Brisbane City Council  
 ABN 72 002 765 795

North Regional Business Centre  
 Development and Regulatory Services  
 Customer & Community Services Division  
 960 Gympie Road  
 Chermside Qld 4032  
 Locked Bag 960 Virginia Qld 4014

Telephone 07 3403 8888  
 Facsimile 07 3407 0750

February 16, 2004

Parsons Brinckerhoff  
 GPO Box 2907  
 BRISBANE QLD 4001

Noted  
 GRB  
 18/2/04

Attn: Ian Cameron - Design Manager

Dear Sir,

**NOTICE OF INTENTION TO PERFORM WORK ON ROAD**  
**at Lytton Road Pump Station to Serpentine Road Pump Station -**  
**Re: Australia Trade Coast Sewer Project -**  
**Approval of Alignments for Sewerage Rising Mains**

I refer to your notice, dated 10 February 2004, in which you seek permission to perform work at the above location.

The alignment for the work is to be as per Drawings submitted and any work in footways is to have a permanent level of 1:50 above the top of kerb. You are required to adopt this alignment for the full length of the proposed works.

Service Pillars or Boxes are to be placed on an alignment of 0.6m from the Real Property Alignment. If your proposal includes the placement of any RIMs, RCMs or any type of Cabinet in new subdivisions they are to be placed in parkland or in a small area of land inside the real property alignment excised by the developer.

Any variation to any of the above conditions or alignments must be authorised by the Region's Team Leader, Licensing and Compliance, Development and Regulatory Services.

Local Area Precincts, Queen Street and Brunswick Street Malls will require separate approvals.

If you require a work zone permit, the hooding or removal of parking meters, or a road or part road closure permit you will be required to lodge a separate application. The approval to commence the proposed work does not allow you to park vehicles on footways, loading zones, bus stops or any restricted parking area.

The preferred method of laying of cables, conduits or pipes within the City of Brisbane is by boring or tunnelling.

As you are responsible for the repair of any damage that you may cause to any Council asset during this proposed work, you will be required to fully restore the asset. Repair of the asset may involve full restoration of any signature type of asset. You are also required to notify this office stating the date of repair and type of damage that has been caused to Council's assets. You should also be aware that Council requires you to maintain any repairs to its assets for a period of not less than six (6) months from the date of notification of the repairs. Council will not accept repairs that do not conform to Council Standards.

Road trenching where necessary is to be saw cut and backfilling is to be compacted to Mod 95% AASHO before resealing. Council may require proof from you that this compaction has been attained. All roadwork is to conform to Brisbane City Council's Standard Road Patching Design Guide.

Concrete footpath is to be removed in 1m sections by saw cutting and replaced to standard drawing UMS.231 or for full width concrete footpath UMS.232. Signature and Banded Footpath is to be fully replaced. Pavers are to be lifted (not saw cut) and stored in a secure location until replaced.

Concrete kerb and channel is to be saw cut in a minimum length of 1m and replaced to standard drawing UMS.211. The use of paint for marking site locations is to be kept to a minimum and all paint marks are to be removed at the completion of work.

Where damage may occur to Council Footpath Trees, Council's Vegetation and Pest Services are to be contacted prior to commencement of work. Where damage may occur to Bushland Rehabilitation Areas, Council's Local Assets Services are to be contacted prior to commencement of work.

Driveways across footpaths are considered by Council to be privately owned by the property owner, prior to commencing any work, that may damage a private driveway, you should negotiate with the property owner and agree on the standard of repair.


It is also your responsibility to check for any heritage, vegetation or environmental listings and also to check for the location of all other Public Utility Services, and to repair any damage that may occur to any street furniture or Council asset.

Council has a policy of notifying the Ward Councillor, all residents and local businesses that may be affected by any planned works in advance of the commencement of this work. It is considered that part of your consultation process should be the same and to also notify any other person that may be affected by your proposed work.

***Where work is to be performed on roads under the control of Department of Main Roads, then they are to be contacted for approval of the works, prior to the commencement of any work.***

Development and Regulatory Services has no objection to you proceeding with the proposed work from the date of this letter

Yours sincerely

John Donaghy

Licensing and Compliance Officer North  
**DEVELOPMENT AND REGULATORY SERVICES**



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## A3. POBC

---



**Parsons  
Brinckerhoff**

12th floor, IBM Centre  
348 Edward Street  
Brisbane Qld 4000  
GPO Box 2907  
Brisbane QLD 4001  
Australia  
Telephone +61 7 3218 2222  
Facsimile +61 7 3831 4223  
Email brisbane@pb.com.au

ABN 84 797 323 433  
NCSI Certified Quality System ISO 9001

Our Reference: 2138110B-LTR003Aic:rmk

15 December 2003

Projects Branch  
Brisbane Water  
GPO Box 1434  
BRISBANE QLD 4001

**Attention: Project Manager, Mr Andrew Bannink**

Dear Andrew

## **Australia Trade Coast Sewerage Project Proposed Lytton Road Sewage Pump Station Site Excision of Port of Brisbane Corporation Land**

In relation to the proposed excision of Part of Lot 719, SP110610 to create a site for the proposed Lytton Road sewage pump station SP298, we provide the following information on the proposed works on the subject land.

### **A. Construction Phase (by Leighton Contractors)**

1. Construction access road.
2. Laydown area for construction materials and equipment.
3. Sheetpiling for formwork for construction of pump well.
4. Excavation of spoil material.
5. Construction of reinforced concrete submersible sewage pump station including dual pumps, switchboard and SCADA control system.
6. Installation of standby generator for pump station and odour control equipment.
7. Provide access to south bank of Brisbane River to allow for construction of river crossing either by horizontal directional drilling (HDD) or micro-tunnelling.

### **B. Operations Phase (by Brisbane Water)**

1. Visits by Brisbane Water operations and maintenance staff to check on pump station.
2. Visits for maintenance activities at the pump station.
3. Access for vacuum trunks to pump out the pump well for emergency repairs to the pump station.

**Over a Century of  
Engineering Excellence**

Parsons Brinckerhoff Australia Pty Limited ACN 078 004 798 and Parsons Brinckerhoff International (Australia) Pty Limited ACN 006 475 056 trading as Parsons Brinckerhoff ABN 84 797 323 433





.../2

2138110B - LTR003Aic:rmk

We trust that this information meets your requirements. Should further information be required, please call me on 07 3218 2644 or 0401 148 142.

Yours sincerely


A handwritten signature in black ink, which appears to read 'Ian Cameron'. The signature is written in a cursive, flowing style.

**Ian Cameron**

Water Executive

Parsons Brinckerhoff Australia Pty Limited

**Over a Century of  
Engineering Excellence**



DESIGN MANAGER		R.P.S.D. NO. 2241		DATE 20/06/03		CADD FILE		DESIGN		PROJECT		TITLE		SCALE		A.H. DATUM	
MANAGER ENGINEERING		DATE		SURVEYED		FIELD BOOK		DRAFTING CHECK		PROJECT		TITLE		SCALE		A.H. DATUM	
NO. DATE		AMENDMENT		INITIALS		SURVEY NO.		FIELD BOOK		DRAFTING CHECK		PROJECT		TITLE		A.H. DATUM	



**PROJECT**  
AUSTRALIA  
TRADE COAST SEWERAGE  
PROJECT

**TITLE**  
BASE PLAN  
CLUNIES FLAT AREA

**SCALE**  
AS SHOWN

**DRAWING NO.**  
PD206

**CONTRACT NO.**  
30137-02/03

**LEICHTON JOB NO.**  
2138110A

**NO. OF SHEETS**  
1

**AMEND.**







Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix B

---

Communications  
B1 — Energex



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## **B1. Communications — Energex**

---





05-JUN. '04 (SAT) 10:30

ENERGEX PLANNING

TEL: 61 7 30008886

P. 001

5 June 2004

# 21381108  
Noted JLBe-copy to  
Andrew Bannink  
7-6-04

Parsons Brinkerhoff  
GPO Box 2907  
Brisbane QLD 4001

Attention Ian Cameron

Dear Sir

**AUSTRALIA TRADE COAST SEWER PROJECT –  
POWER SUPPLY FOR LYTTON ROAD PUMP STATION SP298**

ENERGEX has now finalised all the arrangements regarding the installation of a 500kVA Padmount Transformer for the above development, I advise as follows;

The customers responsibilities:

- To prepare the Substation site 3.0m x 2.8m to ENERGEX Specifications. This includes the supply and installation of the culvert.
- To pay a Padmount Transformer fee of \$4,400 plus \$440 GST and an excess cable fee of \$7,500 plus \$750 GST (Total \$11,900 plus \$1,190 GST = \$ 13,090).
- To supply and install 4 x 125mm conduits from the proposed transformer site to 150mm beyond the front property boundary to ENERGEX Specifications.
- The customer's point of supply will be from the low terminals of the transformer. The maximum fault level for a 500KVA transformer is 15.7kA

Please note a tax invoice will be issued when the supply of goods or services has been completed. For tax invoice purposes, could you please provide ENERGEX with the name of whom the invoice is to be made out to, including their address and A.B.N. number etc.



Enquiries  
Robert Mitchell  
Telephone  
(07) 3000 8882  
Facsimile  
(07) 3407 6600  
Email  
robertmitchell  
@energex.com.au

Corporate Office  
150 Charlotte Street  
Brisbane Qld 4000  
GPO Box 1461  
Brisbane Qld 4001  
Telephone (07) 3407 4000  
Facsimile (07) 3407 4600  
www.energex.com.au

Reference C0054564

ENERGEX Limited  
ABN 40 078 849 055

05-JUN. '04 (SAT) 10:30

ENERGEX PLANNING

TEL:61 7 30008886

P. 002

2

Please find attached:

A 'Business Connection – Electricity & Gas' form, which is to be filled out by the customer and returned to this office with all other associated paperwork and payments.

A 'Metering CT Order' form, which is to be filled out by the electrician when they require the new CT's. In order for this form to be filled out in full, the customer must have first returned the above 'Business Connection – Electricity & Gas' form to obtain their new account number.

Two copies of the 'Proposed Electricity Supply Arrangements' form, which summarises the supply arrangements including dates and explains the customer's responsibilities. Please read this form, sign one copy and return it to this office with all other associated paperwork and payments.

ENERGEX has nominated a target date for supply of the 30/09/2004. To achieve this target the substation site is to be ready by the 10/09/2004 for inspection. All paperwork and payments are to be received at our Greenslopes Office by the 30/07/2004.

The transformer will be placed on site on the 17<sup>th</sup> of September 2004, the electrician has the week from the 17<sup>th</sup> of September 2004 to the 24<sup>th</sup> of September 2004 to pull their consumer mains into the transformer whilst the transformer is de-energised. After the transformer is energised on the 24<sup>th</sup> of September 2004, the electrician will need to pay for a safety observer to open the transformer, over see their work, and then close the substation on completion.

Should you require any further information regarding the above, please do not hesitate to contact myself on telephone (07) 3000 8882.

Yours sincerely

Robert Mitchell  
Planning Officer



05-JUN.'04 (SAT) 10:30

ENERGEX PLANNING

TEL: 61 7 30008886

P: 003



160 Charlotte Street Brisbane 4000  
GPO Box 1461 Brisbane Queensland 4001

2226 DPIS Ver 0.08  
Page 1 of 2

## Proposed Electricity Supply Arrangements

### Industrial and Commercial Customers requiring a Substation Site

<b>Project</b>				
Reference Numbers	ENERGEX - C0054564		Location - Greenslopes Depot	
Project Name	Australia Trade Coast Sewer Project - 6P298			
Location of Project	Lytton Rd, Hemmant			
Real Property Description	Lot 716 on SP110610			
<b>Customer Details</b>				
Name of Customer (please print)				
Customer's Representative	Parsons Brinckerhoff			
Telephone Number	3218 2222	Facsimile Number	3831 4223	
Address	GPO Box 2807 Brisbane QLD 4001			
Contact Person (please print)	Ian Cameron			
Exist Account No.(s)				
<b>Supply Information</b>				
Type of Industry or Purpose of Building				
AS 3000 Calculated Demand	500kVA	Estimated Demand	500kVA	
Size of Largest Motor / Special Apparatus	kW			
Location of Substation	Located as per ENERGEX fax dated 18-04-2004			
Type of Substation	Padmount Transformer			
Major ENERGEX Equipment and Rating	Initially	500kVA	Ultimately	500kVA
High Voltage Method of Supply	From	the existing underground mains in Lytton Road.	To	to the RMU inside the proposed padmount transformer.
Low Voltage Circuits	To Customer	ONE	To ENERGEX Network	Up to three.
Metering Type (High Voltage / Low voltage)	Low			
Customer to install/migrate metering CT's (yes/no)	Yes			
Customer's Point of Supply (Customer's Terminals) is the LV terminals of the transformer				
Possible Fault Level at Customer's Point of Supply	15.7kA at 433V			
Customer to Carry Out	Preparation of substation site as per ENERGEX Specifications. Install 4 x 125mm conduits from the proposed padmount transformer site to 150mm beyond the front property boundary to ENERGEX Specifications.			
Customer to Bear Cost of	All costs to prepare the substation site including the supply of the culvert. The cost to supply and install the conduits. A transformer fee of \$4,400 plus \$440 GST and excess cable fee of \$7,500 plus \$750 GST (Total \$13,090). Any work required outside normal working hours.			
ENERGEX Contacts	Type	Name	Telephone No.	Facsimile No.
	Design	Rob Mitchell	(07) 3000 8882	(07) 3407 6660
	Metering/Inspection of Customer's Installation	Gary McCormick	(07) 3407 6606	(07) 3407 6600
	Construction and Transformer Delivery	Rob Mitchell	(07) 3000 8882	(07) 3407 6660
Relevant Drawings	*Enclosed			
Application for Supply	*To be lodged	Date Lodged	/ /	
Date Supply Required	30/09/2004			

\* Cross out where not applicable

05-JUN.'04 (SAT) 10:31

ENERGEX PLANNING

TEL:61 7 30008886

P. 004

2226 DPPIS Ver 8.08  
Page 2 of 2**To be completed by ENERGEX**

ENERGEX will proceed with detailed planning for supply to the above project after receipt of acceptance of the supply arrangements as set out in this form and the drawings above.

**Note:** If this is a new account, the customer is required to apply for electricity supply and provide the relevant security deposit before electricity supply can be connected to the property. This can be done by telephoning ENERGEX's Call Centre on telephone number 13 12 63. Please quote ENERGEX project number D1401385 when making application for supply.

Nothing contained herein or shown on the drawings absolves the customer from obtaining building approval for the proposed substation from the relevant Authority.

Under the provisions of the Electricity Act 1994 -

- 1 the space necessary for and suitable to the erection of a substation shall be provided free of cost to ENERGEX
- 2 right-of-way for electricity lines and cables and access to install, maintain and remove its equipment without hindrance or obstruction shall be available at all times to ENERGEX
- 3 maintenance and repair of the substation space including building structure to the requirements of ENERGEX shall be the responsibility of the Customer

The Customer shall make the transformer site ready for inspection by the date nominated and is required to notify ENERGEX to arrange a site inspection. Failure of the site to pass inspection or be ready by the required date may delay the supply availability date.

Details of the time and date of delivery will be negotiated between the Customer and ENERGEX's representative after the site has passed inspection. A minimum period of five (5) working days shall be allowed for delivery to the site. ENERGEX estimate that supply will be made available within 10 working days of delivery of the transformer(s) to site.

Once the transformer has been placed on site, the customer's electrician will have 5 working days, prior to energising of the transformer, to pull the consumers mains into the transformer. If the electrician fails to install the consumer's mains into the transformer prior to energising of the transformer, ENERGEX will require the electrician to engage an approved safety observer at their cost. The safety observer will open the transformer, oversee the task and close the transformer on completion of works.

Name (please print) Rob Mitchell

Position (please print) Electrical Paraprofessional

Signature (for Chief Executive)

Date 05/06/2004

**To be completed by the Customer or Customer's Representative**

I, on behalf of the Customer specified in this document, accept the electricity supply arrangement as described in the above information. I confirm that the substation site will be completed to ENERGEX's requirements and ready for inspection by ENERGEX on 10/09/2004. Taking into account the lead times required by ENERGEX, I also confirm that the "Date Supply Required" 30/09/2004.

Name (please print)

Position (please print)

Organisation

Signature

Date / /

19-APR.'04 (MON) 12:47

ENERGEX PLANNING

TEL: 61 7 30008886

P. 001



Attention	Michael Brand		
Company	PB		
Fax Number	3831 4223	Reference	C0054564
Date	19 April 2004	Number of Pages	14
Subject	LYTTON ROAD SEWAGE PUMPING STATION POWER SUPPLY		

*Noted  
4-5-04*

Dear Sir

Further to your fax dated the 20<sup>th</sup> of February 2004 regarding the electrical supply to the above development, I advise as follows;

Customer's responsibilities:

- To supply and install 4 x 125mm conduits to ENERGEX Specifications.
- To prepare the padmount transformer site to ENERGEX Specifications. This includes the supply and installation of the culvert.
- The customer is pay a transformer fee of \$4,400 plus GST and an excess cable fee of \$7,500 plus GST (Based on 75m run). Total \$11,900 plus \$1,190 GST Totalling \$13,090.
- Customer's point of supply will be from the fuse terminals of the LV board inside the transformer. The maximum fault level for a 500kVA transformer is 15.7kA.

ENERGEX Responsibilities:

- To run 4 x 125mm conduits under Lytton Rd to Pole 39752.
- Run 240mm underground cable from pole 39752 to the proposed transformer site and terminate to the transformer.



Enquiries  
Robert Mitchell  
Telephone  
(07) 3000 8882  
Facsimile  
(07) 3407 6660  
Email  
robertmitchell  
@energex.com.au

Corporate Office  
150 Charlotte Street  
Brisbane Qld 4000  
GPO Box 1461  
Brisbane Qld 4001  
Telephone 07 3407 4000  
Facsimile 07 3407 4809  
www.energex.com.au

ENERGEX Limited  
ABN 40 078 849 055

Confidentiality

This message and any accompanying documents are intended only for the person or entity to whom addressed and may contain information that is confidential and privileged. Confidentiality and privilege are not lost by their having been received by the wrong person. If you are not the intended recipient or the person responsible to deliver it to the intended recipient, please notify us by phone and return this fax by mail. Any distribution, reproduction, or other use of this fax by an unintended recipient is prohibited.

19-APR. '04 (MON) 12:47

ENERGEX PLANNING

TEL:61 7 30008886

P.002

---

2

---

- The installation of a 500kVA padmount transformer at the proposed transformer site, including all required earthing.

Please note the transformer site on the opposite side of the road to your Switchboard. Because there is no low voltage network in the street, this transformer is not able to be tied into the common MEN network and will require its own separate earthing. This means that the transformer must be separated by a minimum of 5 meters from any other structure or building.

ENERGEX has noted your required supply date of the end of August 2004 and on written acceptance of the above offer, ENERGEX will program the date. To achieve your required supply date ENERGEX will require acceptance by the 30<sup>th</sup> of April 2004.

Attached is a brief of the ENERGEX Specifications for padmounted transformers, the full Specifications can be found on the ENERGEX web Page ([www.energex.com.au](http://www.energex.com.au)). From the home page there is a heading in the top right called "Service Providers", click on it and then click on "Technical Documents", scroll half way down the page to "Commercial And Industrial Padmounted Substations".

If you have any questions, please call.

Yours sincerely




Robert Mitchell  
Planning Officer

---

**Confidentiality**

This message and any accompanying documents are intended only for the person or entity to whom addressed and may contain information that is confidential and privileged. Confidentiality and privilege are not lost by their having been received by the wrong person. If you are not the intended recipient or the person responsible to deliver it to the intended recipient, please notify us by phone and return this fax by mail. Any distribution, reproduction, or other use of this fax by an unintended recipient is prohibited.





19-APR. '04 (MON) 12:47

ENERGEX PLANNING

TEL: 61 7 30008886

P. 004

## UNCONTROLLED COPY

### 1 Introduction

This specification covers padmounted distribution substations on consumers' premises. Sites and foundations for these substations are to be prepared according to the site sketch and design standards contained in this document.

**The consumer's consultant is responsible for ensuring that all information and drawings are passed on to the relevant contractor(s). ENERGEX may charge for the supply of additional copies.**

### 2 Site

#### 2.1 General

Where practicable, padmount substation sites for commercial and industrial developments shall be located at the real property street alignment with the substation cabinet doors facing the adjoining footpath. Sites located on the street alignment shall be surveyed and dedicated as part of the road reservation.

The site shall:

- have stable soil conditions
- be flood free
- have level topography
- where possible free from steep batters
- be at least 4 metres from the edge of permissible residential dwelling construction area

Services such as drains, sewers, water services, air-conditioning installations, electrical and communications cables etc, other than those specified by ENERGEX, must not pass through or encroach into the substation site.

Along coastal areas, the padmount substation site must be located as far as possible from the shoreline and sheltered from salt spray.

#### 2.2 Preparation

Padmounted substation sites shall be prepared in accordance with the included construction drawings.

#### 2.3 Space Requirements

The recessed area off the footpath required for "square"-type padmounted substations shall be:

- level sites 3000 mm length x 2800 mm depth
- retaining wall sites 3400 mm length x 3000 mm depth

##### 2.3.1 Restricted Areas

If the padmounted substation site does not front the road reserve, then an additional minimum width of 2.0 metres of clear access shall be provided in front and for the full width of the substation site (making a 4.8 m deep site). This will provide a safe working platform and access around the lockable doors when opened for emergency operations.

##### 2.3.2 Landscaped Areas

When the padmounted substation is located in a landscape area (gardens) the following shall be complied with:

- An additional minimum width of 2.0 metres of clear access shall be provided in front and for the full width of the substation site (4.8 m depth). This will provide a safe working platform and access around the lockable doors when opened for emergency operations.

## UNCONTROLLED COPY

19-APR. '04 (MON) 12:48

ENERGEX PLANNING

TEL: 61 7 30008886

P. 005

## UNCONTROLLED COPY

- A formed pathway from the footpath real property street alignment to the padmounted substation site. This will provide safe access to the substation site for field personnel.

When planting vegetation in landscaped areas and gardens, take into consideration the fully matured size of vegetation, ensuring access to the site, one metre clear access around the sides and back of the substation is maintained and two metres clear access to the front of the substation is maintained.

The site surface is to be finished with a concrete slab (refer to the construction drawings).

The 2.0 metre wide apron in front of the substation cabinet shall be finished with a concrete slab sectioned with construction joints for easy removal to excavate.

The formed pathway is to be a concrete slab (refer to the construction drawings). The concrete pathway slab shall be clear of cables and conduits to the substation.

The surface of the pathway slab may be finished with clay brick pavers or concrete tiles over the slab. Installation to be in accordance with the paver/ tile manufacturer's installation specification.

### 2.3.3 Truncated Street Alignment

If the padmounted substation site boundary is located at a truncated section of the street alignment, the following applies:

- The front edge of the substation plinth shall be 200 mm from and as near to parallel as possible to the real property street alignment.
- A minimum of 600 mm clear access around the substation sides and back shall be maintained to the real property boundary.

### 2.3.4 Spacing Between Padmount and Other Metal Objects – Separate Earthing

The distance between the edge of the plinth and the consumer's building/ residences, fences, LV switchboard earth and metal builder's poles, shall be a minimum of 5 metres at sites where separate LV and HV earthing systems are installed. The additional area shall be road reserve or an easement to prevent encroachment.

The distance between the edge of the plinth and telecommunications plant and equipment shall be 15 metres at sites where separate LV and HV earthing systems are installed.

## 3 Concrete Apron

The site surface is to be finished with a concrete slab (refer to the construction drawings). The 2.0 metre wide apron in front of the substation cabinet shall be finished with a concrete slab sectioned with construction joints for easy removal to excavate.

## 4 Retaining Walls

Retaining walls shall be constructed to ENERGEX standards around the perimeter of a padmounted substation site when a change in ground level of 300 mm or more occurs within two metres of the boundary of the padmounted substation site.

## 5 Future Development

Sites that may restrict future development of the premises should be avoided. Future relocation of the substation and electrical equipment would be extremely costly to the owner of the premises. In addition future development of the site must not encroach on the agreed access route to the substation.

UNCONTROLLED COPY



19-APR. '04 (MON) 12:48

ENERGEX PLANNING

TEL: 61 7 30008886

P. 006

## UNCONTROLLED COPY

### 6 Site Access to Restricted Areas

#### 6.1 Personnel Access

ENERGEX staff must have access to the substation at all times without having to enter security areas. The onus is on the consumer to maintain access 24 hours a day, seven days a week.

#### 6.2 Heavy Equipment

Padmounted transformers are transported by flat bed trucks with self contained cranes. As such an all-weather access roadway suitable for use by these vehicles is required from the street to the substation site. An equipment handling area and room for vehicle manoeuvring must be allowed for adjacent to the substation.

Suitable headroom is required along the route of passage of the vehicles and in the equipment handling area and vehicle manoeuvring room such that operation of the crane is not impeded. The headroom required is not less than 4.3 m, for structures on a level access route. Where the access route is on sloping ground and/or where there are humps or dips in the access route, the headroom for structures must be increased as necessary to compensate. Each case will need to be determined to the satisfaction of ENERGEX's liaison officer.

The width of the access route should be increased on bends and in the manoeuvring area near the substation site to allow for the off loading of the padmounted transformer from the truck.

The above clearance requirements must be achieved after completion of building surface treatments including cladding of overhead structures, and paving of the access route.

Any reinstatement necessary in the event of damage to concrete slab, paving tiles or road surfaces, doors etc., is the responsibility of the owner of the property.

### 7 Foundations

#### 7.1 General

Where padmounted substation sites are very unstable, and conventional foundation construction techniques as described in this document cannot be applied, a special design shall be required.

In such circumstances, the developer shall provide a certified design from a civil engineer (RPEQ) for ENERGEX's consideration. No special designs for padmount substation foundation construction shall be used without the approval of ENERGEX (design).

#### 7.2 Uniculvert Foundation

Uniculvert foundations for both stable and unstable soil conditions shall be constructed in accordance with the construction drawings.

#### 7.3 Concrete Pier Foundation

Concrete piers shall be installed where the site ground conditions do not provide an even or equal bearing capacity for the padmount foundation.

The concrete pier foundation is suitable for substations from 200 to 500 kVA 11 kV/ 433- 250 V only.

For 750 to 1000 kVA 11 kV/ 433- 250 V, use the uniculvert foundation type if applicable.

19-APR. '04 (MON) 12:49

ENERGEX PLANNING

TEL: 61 7 30008886

P. 007

## UNCONTROLLED COPY

Concrete piers shall be constructed in accordance with the construction drawings.

### 8 Backfilling and Final Restoration of Surface

All backfill of the padmount substation site must be compacted before final restoration of the site surface.

Sealing of the cable apertures in the precast concrete plinth and construction of the concrete surround slab over the ground surface shall be in accordance with the construction drawings.

### 9 Cable Conduits

#### 9.1 General

ENERGEX cable conduits for the development may be placed in the substation site and shall pass down the sides or through the unculvert foundation. No conduits shall pass under the unculvert foundation. Conduits shall be 600 mm minimum depth below the finished surface level. Ensure end wall knockouts are grouted with a high strength sand and cement grout after conduit/ cable installation through unculvert foundation.

#### 9.2 Specification

All conduits, associated fittings and bends shall comply with the requirements of AS/ NZS 2053.

Conduits shall be 125 mm or 150 mm as specified by ENERGEX and shall be supplied and installed by the consumer.

To provide for a change in direction of conduits, bends shall be installed. Bends can be cut to suit the particular deviation angle required. Conduit bends shall be of the same class and colour as the conduits. All conduit couplings shall be fitted in accordance with the manufacturer's instructions.

An adequate quantity of solvent and cement shall be used in performing connections; and shall be disposed of using the approved manufacturer's method.

#### 9.3 Draw Rope

A continuous length of draw rope having a minimum breaking strength of 1.0 kN, shall be left in the full length of conduits.

#### 9.4 Cleaning and Testing

After completing the laying and backfilling of each section of conduit, the bore of the conduits shall be cleaned of dirt or other substances and tested for obstructions.

#### 9.5 Sealing


After completing the laying and backfilling of each section of conduit, the bore of the conduits shall be cleaned of dirt or other substances and tested for obstructions.

#### 9.6 Entry to Permanent Structures

Where conduits enter any permanent construction such as a pit or a substation building, the conduit entry aperture is to be resealed. The exposed ends of all conduits shall be squarely cut and plugged.

## UNCONTROLLED COPY



**UNCONTROLLED COPY**

For SEPARATE LV & HV earthing provide a five metre clearance zone from the edge of the plinth. The clearance zone is to be maintained free from metallic objects, buildings and structures.  
- including their foundations.

**NOTE:**

1. ENERGEX's 3000mm x 2800mm access area (road reserve) shall be levelled and surrounding area graded to ensure NO PONDING of water occurs.
2. No services other than the ENERGEX's electric cables shall pass through this substation site.
3. Clear access to the transformer shall be maintained for ENERGEX's personnel and heavy equipment.
4. After installation is complete the site surface is to be finished with a concrete slab.
5. Mature landscaping (including trees, sprinklers etc) shall not encroach onto the substation site.
6. The finished surface of the adjacent footpath in front of the padmount cabinet shall be level to ensure padmount doors will swing into the fully open position.

A ORIGINAL ISSUE

**UNCONTROLLED COPY**

© COPYRIGHT 2002 ENERGEX  
This document must not be reproduced in part or whole without written permission from ENERGEX

SCALE	1:50
APP'D	D Lloyd
DATE	31 May 2002
REC'D	D Taylor
CK'D	J Tunney
ORN	W.M.
	CAD

**PADMOUNTED TRANSFORMER**  
CONSTRUCTION  
SITE PREPARATION  
SLOPING SITE - MAXIMUM CUT & FILL

SHEET 1 OF 2

FILE: \US 2002\Comp\SP298\SP298-0176.dwg

7472-A4

A

P.008

TEL: 61 7 30008886

ENERGEX PLANNING

19-APR. '04 (MON) 12:49

1. For SEPARATE LV & HV earthing provide a five metre clearance zone from the edge of the plinth. The clearance zone is to be maintained free from metallic objects, buildings and structures - including their foundations.
2. HV earth electrodes are to be contained within the padmount site.
3. The clearance zone shall be turfed or landscaped with mulched beds and shrubs.
4. Every attempt should be made to locate separately earthed padmounts in areas remote from residential dwellings.
5. The clearance zone shall be road reserve or an easement to prevent encroachment.





P.010

TEL: 61 7 3000886

ENERGEX PLANNING

19-APR-'04 (MON) 12:50

**NOTES:**

- Foundation design details are as follows:
  - Unstable soils are soft clay to sandy gravel with a soil strength 50 - 150 kPa. These soil types **REQUIRE** a base slab as shown.
  - Stable soils are very stiff clay to shale/rock with soil strength of 150KPa or higher. These soil types **DO NOT REQUIRE** a base slab.
- Lift the unculvert and Base Slab separately with 4 x 1.3t Reid Swiftlift lifting eyes. Refer to construction drawing.
- Position the top face of the Uniculvert at the finished ground level of the site, as detailed on the Project's Civil Construction drawings.
- The unculvert shall be constructed level. Under no circumstances shall it be allowed to tilt forward towards the footpath.
- If a deep excavation is constructed under the transformer cabinet and in front of the foundation then the front edge of the plinth shall be propped for the period the excavation remains open.

**UNCONTROLLED COPY**

A ORIGINAL ISSUE

**UNCONTROLLED COPY**

©COPYRIGHT 2002 ENERGEX

This document must not be reproduced in part or whole without written permission from ENERGEX

SCALE 1:50  
 APP'D D Lloyd  
 DATE 31 May 2002  
 RECD D Taylor  
 CKD J Turney  
 DRN W.W.  
 CAD

**PADMOUNTED TRANSFORMERS**  
 CONSTRUCTION - PADMOUNTED SUBSTATION  
 TRANSFORMER  
 UNICULVERT FOUNDATION DETAILS

SHEET 1 OF 2

7468-A4

A

P. 011




TEL: 61 7 30008866

ENERGEX PLANNING

19-APR.'04 (MON) 12:50

**Notes:**

Lifting, Handling and Installation of precast concrete foundations on a construction project shall be in strict accordance with the requirements and regulations of the Workplace Health & Safety regulations 1989 including latest amendments.

**SECTION DETAIL 1****DETAIL 1****Notes:**

The "Reid Swiftlift" concrete lifting system is used for lifting modules.  
 (Manufacturer - Alan H Reid Pty Ltd)  
 Use only nominated Reid Swiftlift components to lift foundation by Swiftlift anchors.  
 Lift foundation from all four anchors only.  
 The load will always be shared between two diagonal points and  
ANGLE  $\alpha^\circ$  IS NOT TO EXCEED  $60^\circ$ .

**A** ORIGINAL ISSUE**UNCONTROLLED COPY**

©COPYRIGHT 2002 ENERGEX

This document must not be reproduced in part or whole without written permission from ENERGEX

SCALE	NTS
APP'D	D Lloyd
DATE	31 May 2002
RECO	D.Taylor
EKO	J.Turney
DRN	W.M.
	CAD


**PADMOUNTED TRANSFORMERS**  
 CONSTRUCTION - PADMOUNTED SUBSTATION  
 UNICULVERT FOUNDATION  
 LIFTING & HANDLING DETAILS

SHEET 1 OF 1

FILEDUS 000 0000000000 0000000000

**7469-A4****A**

UNCONTROLLED COPY



A ORIGINAL ISSUE

UNCONTROLLED COPY

A46508



©COPYRIGHT 2002 ENERGY  
This document must not be reproduced in part or whole without written permission from ENERGY

SCALE	1:25
APPD	D Lloyd
DATE	31 May 2002
REC'D	D Taylor
CHKD	J Tunney
DRN	W.W.
CAD	

PADMOUNTED TRANSFORMERS  
CONSTRUCTION  
UNSTABLE SOIL CONDITIONS  
PIER FOUNDATION DETAILS

SHEET 1 OF 3  
7470-A4 A

P.012

TEL:61 7 30008886

ENERGEX PLANNING

19-APR.'04 (MON) 12:51

**UNCONTROLLED COPY****NOTES:**

1. The foundation is suitable for substations from 200 to 500kVa-11kV/433-250V only. For 750 to 1000kVa-11kV/433-250V use the unculvert foundation.
2. The diameters of concrete piers is dependant on the supporting stratum bearing capacity as detailed from the table below.
3. The minimum depth of a pier shall be at least 450mm into the stratum of the undisturbed natural soil and 600mm below cable entry excavation. If the material is unsuitable then the hole shall be drilled deeper until a firm bearing stratum is reached.
4. A bored pier up to eight times the pier diameter (depth  $< 8\phi$ ) shall be constructed in mass concrete and poured continuously in one operation. Bored piers of depth greater than eight times the diameter (depth  $> 8\phi$ ) shall be reinforced.
5. Plain round steel bar reinforcement to AS1302 shall be installed.
6. Hoop reinforcement shall be 4mm diameter and spaced at 750mm centres.
7. The minimum concrete cover to steel shall be 50mm.
8. The minimum concrete strength shall be 25MPa.
9. Concrete piers shall be constructed using a continuous single concrete pour.
10. The top of piers shall be level. The maximum variation between the 4 piers shall be 3mm.

SUPPORTING STRATUM	ALLOW. BEARING CAPACITY (kPa)	BORED PIER DIA ' $\phi$ ' (mm)	DIMENSION 'A' (mm)	DIMENSION 'B' (mm)	DIMENSION 'C' (mm)	DIMENSION 'D' (mm)	OFFSET 'E' (mm)	DIMENSION 'F' (mm)	REINF. WHEN PIER DEPTH $> (8 \times \phi)$	
									No. OF RODS	DIA. OF RODS (mm)
FIRM	50	500	520	460	635	635	35	1150	8	12
STIFF	100	400	700	510	610	610	-	1250	6	12
VERY STIFF	200	250	1060	585	610	610	-	1350	4	10
HARD	400	250	1060	585	610	610	-	1350	4	10

A ORIGINAL ISSUE

**UNCONTROLLED COPY**

©COPYRIGHT 2002 ENERGEX

This document must not be reproduced in part or whole without written permission from ENERGEX

SCALE	NTS
APP'D	D Lloyd
DATE	31 May 2002
REC'D	D.Taylor
CHKD	J.Tunney
DRN	W.W.
	CAD

**PADMOUNTED TRANSFORMERS**  
**CONSTRUCTION**  
 UNSTABLE SOIL CONDITIONS  
 PIER FOUNDATION DETAILS

SHEET 2 OF 3

FILE FOR THE CONSTRUCTION OF THE PIER

7470-A4

A

P.013

TEL: 61 7 30008886

ENERGEX PLANNING

19-APR '04 (MON) 12:51

P.014

TEL: 61 7 3000886

ENERGEX PLANNING

19-APR '04 (MON) 12:51

**NOTES**

1. CABLE CONDUIT SHALL BE OF THE FOLLOWING TYPE:  
- LIGHT DUTY ELECTRICAL CONDUIT TO AS/NZS 2053. CONDUIT BENDS SHALL HAVE A MINIMUM RADIUS OF 1830mm.
2. CONDUITS SHALL BE 125mm OR 150mm AS SPECIFIED BY ENERGEX AND SHALL BE SUPPLIED AND INSTALLED BY THE DEVELOPER.
3. CONDUITS SHALL BE SECURELY SEALED TO PREVENT INGRESS OF DIRT UNTIL CABLE INSTALLATION BY ENERGEX AND THEN RESEALED BY ENERGEX.
4. EACH CONDUIT TO BE FITTED WITH A 6mm BRAID POLYPROPYLENE DRAW ROPE (MINIMUM BREAKING STRENGTH OF 10kN).
5. ENERGEX MAY NEED TO INSTALL AN EARTH WIRE AND EARTH RODS IN CONDUIT TRENCHES FROM THE SUBSTATION SITE.
6. ELECTRICITY SUPPLY CONDUITS AND CABLES SHALL HAVE POLYMERIC CABLE PROTECTION COVER STRIPS PLACED 75mm ABOVE THE TOP CONDUIT FACE OF THE ELECTRICITY SUPPLY CONDUITS AND CABLES. CABLE PROTECTION COVER STRIP SHALL BE LAPPED WHEN PLACED TOGETHER; 100mm MINIMUM ALONG THE LONGITUDINAL AXIS, 40mm MINIMUM ALONG THE TRAVERSE AXIS AND SHALL EXTEND 40mm MINIMUM PAST THE EXTERNAL EDGES OF THE CONDUIT/CABLE BANK.
7. POLYMERIC CABLE PROTECTION COVER SHALL BE A MINIMUM OF 5mm THICK AS DESCRIBED IN THE AUSTRALIAN STANDARD; AS4702 FPR POLYMERIC CABLE PROTECTION COVERS.


FINISHED SURFACE

ELECTRICAL WARNING TAPE  
ON CENTRE LINE OF TRENCH  
230mm DEEP

ORDINARY FILL

CABLE PROTECTION COVER STRIP  
3x 200mm STRIP (5mm THICK) Min.

ELECTRICAL CONDUITS

LEVEL OF BEDDING  
MATERIAL PRIOR TO THE  
ENERGEX'S INSPECTIONPIT SAND OR FINE  
GRANULAR SOIL70mm<sup>2</sup> EARTH WIRE TO  
BE INSTALLED AS REQUIRED BY ENERGEX  
(NOTE: EARTH WIRE MAY BE  
INSTALLED IN CONDUIT)**PY**

TYPICAL CONDUIT DETAIL

A ORIGINAL ISSUE

**PY**

COPYRIGHT 2002 ENERGEX

This document must not be  
reproduced in part or  
whole without written  
permission from ENERGEX

SCALE	NTS
APP'D	D Lloyd
DATE	31 May 2002
REC'D	D Taylor
CKD	J Turney
DRN	W.W.
<b>CAD</b>	

**TRENCH SECTIONS**

CONSTRUCTION - CONDUITS  
COMMERCIAL AND INDUSTRIAL SITES AND  
PRIVATE PROPERTY

SHEET 1 OF 1

PLEASE USE FOR CONSTRUCTION PURPOSES ONLY

**7576-A4****A**

# 74501917

;

4







Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix C

---

### Design Calculations SP298

Parsons Brinckerhoff Australia

ABN. 84 797 323 433

**REVISION RECORD**

Document Type: <b>DESIGN CALCULATIONS</b>				PB Document Name: <b>SP 298 Design</b>	Page <b>Cover</b>
Document Title: <b>SP 298 (Lytton Rd) DESIGN CALCULATIONS</b>					Rev.: <b>1.9</b>
Rev No.	Prepared Initials & Date	Verified Initials & Date	Approved Initials & Date (Effective Date)	Description	
0.0	MB 21-May-03			Initial issue	
0.1	MB 1-Jun-03			Flotation calcs added	
0.2	MB 17-Jun-03			Various crossing sizes analysed	
0.3	MB 23-Jun-03			For Tender	
1.0	MB 28-Jan-04			Start of Detailed Design	
1.1	MB 6-Feb-04			HDD reduced to OD400 PN20	
1.2	MB 9-Feb-04			Hydraulic algorithm standardised	
1.3	MB 5-Mar-04			Issue for Pump Selection Report	
1.4	MB 31-Mar-04			Design changed to fixed speed PS	
1.5	MB 14-Apr-04			Surface levels lowered	
1.6	MB 12-May-04			For Purchase	
1.7	MB 29-May-04			Top slab level altered	
1.8	MB 18-Jun-04			HDD length altered	
1.9	MB 25-Jun-04			Hidrostal performance curve added	
Project Use					
Notes:					
Client: <b>Brisbane Water</b>			Client Project No:		Client Rev.:
Plant Area: <b>SP 298 - Lytton Rd Lytton</b>			Client Doc No:		
Superintendent: <b>Rod Richards</b>			Project Name: <b>Australia Trade Coast Sewerage Project</b>		
PB Project Manager: <b>Ian Cameron</b>					
The information contained in this document is subject to Copyright and may not be copied or otherwise used without the express authority of PB			PB Project No.: <b>2138110B</b>		

I:\2138110B Trade Coast Sewerage post-Award\WORK\Pumping Stations\SPS 298 Lytton Road\SP 298 Design Rev 1.9.xls\REVISION

Parsons Brinckerhoff - Brisbane Office

Client: Brisbane Water

Project: Australia Trade Coast Sewerage Project

PB Job Code: 2138110B

## Comments and Questions

9/05/2003

Design friction factors based on Sydney Water's design values for sewage rising mains

<u>material</u>	<u>k value</u>
MSCL / DICL	0.60 mm
PE	0.15 mm

9/05/2003

Initial friction factors based on AS2200 values for sewage rising mains

<u>material</u>	<u>k value</u>
MSCL / DICL	0.03 mm
PE	0.003 mm

15/05/2003

### Brisbane Water - Water and Sewerage Standards

- 2.1.2.1 PWWF of 1200L/ep.day  
two pumps - one duty one standby  
three pumps - two duty one standby
- 2.1.2.2 Types of pumps standardised. Info available from BCC.
- 2.1.2.3 Std overflows required. Preferably off incoming sewer.
- 2.1.2.5 Minimum 10m x 10m area.  
Access road min 4m wide, all weather, heavy vehicles  
Fenced and landscaped.
- 2.1.3.1 Preferable velocity 0.9m/s to 1.5m/s.  
Min 0.6m/s, max 3.0m/s.
- 2.1.3.3 Bedding to comply with reqts for DICL gravity sewers.
- 2.1.3.4 Rising mains to be located in road verge or road pavement.  
Minimum easement width 6m.
- 2.1.3.5 Cover 600mm - but check Table 2.9 for other reqts.
- 2.1.3.6 Air valves -std dwg SB006
- 2.1.3.7 Scours - std dwg SB005
- 2.1.3.8 Discharge MH - std dwg SC005  
Not in private property.

- 2.1.8 Dwg stds
- 2.2.7 Accredited pipe laying programmes  
Metal detector tapes on plastic pipes
- 2.2.10.4 Pipe testing
- 2.3.2 Pipe, valve and fitting materials
- 2.3.3 Manhole construction

4/03/2004

All head loss calcs checked against ITT Flygt Colebrook White calculator in FLYPS.

30/03/2004

Design changed to fixed speed PS

Parsons Brinckerhoff - Brisbane Office  
Client: Brisbane Water  
Project: Australia Trade Coast Sewerage Project  
PB Job Code: 2138110B

Entered  
Calculated

SUMMARY OF DUTY FOR SP 298

SP 298 - Lytton Rd

Design PWWF (Tender Docs)	160.0 L/s	per duty pump
Total Flow (Tender Docs)	160.0 L/s	maximum duty flow
Static Head (from Pump Calcs)	1.5 m	
Total Head (from Pump Calcs)	26.0 m	design duty
Smooth Pipe Duty Head (at 160L/s)	20.4 m	smooth pipe duty (insert smooth k in calcs)



Parsons Brinckerhoff - Brisbane Office  
 Client: Brisbane Water  
 Project: Australia Trade Coast Sewerage Project  
 PB Job Code: 21381108

Entered  
 Calculated


## SP 298 DIMENSIONS AND LEVELS (Datum is AHD)

### Proposed SP 298

	Source	Design Values
Wet Well Internal Diameter	dwg WR101 / 031	3.60 m
Max Water Depth: Overflow Level to SPS FLS	calc	4.36 m
Total Depth: FSL to Underside of Base	calc	4.96 m
Incoming "Sewer" Diameter [to GCMH]	dwg WR101 / 031	300 mm
Rising Main Diameter	OD450 PE100 PN12.5	450 mm
Discharge Pipe and Valve Diameter	velocity < 3m/s at max flow from single pump (160L/s)	300 mm
Switchgear Level	150 above top slab	2.90 RL
Roof Slab - Finished Level	LCPL (constructability)	2.75 RL
Flood Level	Q100 is at RL2.58	2.56 RL
Finished Surface Level	build up to 300 below top slab	2.45 RL
Roof Slab - Underside	nominal 350 thick	2.40 RL
Air Vent - Obvert Level (horizontal section)	directly under top slab - check ground cover and overflow level	2.40 RL
Physical Overflow Level (OF)	dwg WR101 / 031 (300 above IL of high level pipe)	2.45 RL
Surcharge Occurring Level	25 below OF	2.43 RL
High Level Pipe Invert at Wet Well		0.90 RL
Surcharge Imminent Alarm Level	300 below OF	2.15 RL
Station Inhibited Start Level	200 below Surcharge Imminent	1.95 RL
Discharge Pipework - Invert Level	dwg WR101 / 031	1.92 RL
Rising Main - Invert Level	dwg WR101 / 031	1.76 RL
Station Inhibited Stop Level	200 below Station Inhibited Start	1.75 RL
Valve Pit Floor - Invert Level	400 below discharge pipework IL	1.52 RL
Incoming RMs - Invert Level	dwg WR101 / 031	0.75 RL
Wet Well High Alarm (TWL)	400 above Start Duty A	0.65 RL
Incoming Sewer to GCMH - Invert Level	dwg WR101 / 031	0.55 RL
Start Duty B	150 above Start Duty A	0.40 RL
Start Duty A	300 below Incoming sewer	0.25 RL
Grit Collector - Invert Level	900 below Incoming sewer	-0.35 RL
Stop Duty B	150 above Stop Duty A	-1.01 RL
Stop Duty A	GOAL SEEK THIS TO GIVE 10 STARTS PER HOUR ON DUTY PUMP	-1.16 RL
Wet Well Low Alarm (BWL)	150 below Stop Duty A	-1.31 RL
Required Pump Submergence	Hidrostal submergence not supplied - use Flygt CP3231 (680mm)	0.75 m
Wet Well Invert Level	Stop Duty A less submergence	-1.91 RL
<b>Flotation Calcs:</b>		
Top Level of Roof Slab	from above	2.75 RL
Roof Slab Thickness	assume 350	0.35 m
Diameter of Roof Slab	well ID + 2 x wall thickness	4.30 m
Mass of Roof	calc at 2400kg/m <sup>3</sup>	12198 kg
Wall Thickness	assume 300	0.30 m
Depth of Walls (excluding roof and floor)	calc	4.31 m
Mass of Walls	calc at 2400kg/m <sup>3</sup>	44976 kg
Floor Slab Thickness	change this by goal seek (see below)	0.60 m
Mass of Floor	calc at 2400kg/m <sup>3</sup>	20912 kg
Total Concrete Mass	calc at 2400kg/m <sup>3</sup>	78086 kg
Total Volume of Structure	volume of wet well	42 m <sup>3</sup>
Total Mass of Water Displaced	assume 1000kg/m <sup>3</sup>	42450 kg
Net Buoyancy (positive down)	GOAL SEEK THIS TO ZERO BY CHANGING FLOOR THICKNESS	35636 kg
Underside of Structure	calc	-2.51 RL

ground cov  
 OF can be

### Station Levels (NTS)



Parsons Brinckerhoff - Brisbane Office  
 Client: Brisbane Water  
 Project: Trade Coast Sewerage D&C  
 PB Job Code: 21381108

DYNAMIC LOSS CALCULATION			DN200 DI CL K12
Pump Discharge Pipework (DN200 sections)			
Flow rate	576.0 m <sup>3</sup> /hr	0.16 m <sup>3</sup> /s	<b>Flowrate</b> 160.0 L/s
Pipe internal diameter	232.0 mm	0.23 m	single pump flow (2031)
Surface area	0.042 m <sup>2</sup>	9 inch	
Water velocity	3.785 m/s	0.0006 m	
Reynolds Number	872,859.08		
Roughness coefficient	0.600 mm	1.01E-06 m <sup>2</sup> /s	
Equivalent length of pipe	0 m		
Temperature	20 deg. C		
Kinematic viscosity	1.006 m <sup>2</sup> /s		
Hydraulic gradient	79.57 m/km		
Pipe dynamic loss	0.00 m		
Component fitting losses:	k value	fitting loss	
90 degree bend R=1D	0.75	0.55 m	check formulae when inserting rows
200 / 300 taper	0.04	0.03 m	
		0.00 m	
		0.00 m	
		0.00 m	
<b>Total component losses</b>		<b>0.58 m</b>	
<b>Total dynamic loss in section</b>		<b>0.58 m</b>	
DYNAMIC LOSS CALCULATION			DN300 DI CL K12
Pump Discharge Pipework (DN300 sections)			
Flow rate	576.0 m <sup>3</sup> /hr	0.16 m <sup>3</sup> /s	<b>Flowrate</b> 160.0 L/s
Pipe internal diameter	313.0 mm	0.31 m	single pump flow
Surface area	0.077 m <sup>2</sup>	12 inch	
Water velocity	2.079 m/s	0.0006 m	
Reynolds Number	646,975.42		
Roughness coefficient	0.600 mm	1.01E-06 m <sup>2</sup> /s	
Equivalent length of pipe	5 m	length is an estimate only	
Temperature	20 deg. C		
Kinematic viscosity	1.006 m <sup>2</sup> /s		
Hydraulic gradient	16.51 m/km		
Pipe dynamic loss	0.08 m		
Component fitting losses:	k value	fitting loss	
90 degree bend R=1D	0.75	0.17 m	check formulae when inserting rows
check valve (John fig. 404)	0.63	0.14 m	
gate valve (John Fig 694)	0.11	0.02 m	
tee - line to branch - radiused	0.80	0.18 m	left side pump is hydraulically disadvantaged
tee - branch to line - radiused	0.80	0.18 m	
300 / 450 taper	0.04	0.01 m	
<b>Total component losses</b>		<b>0.69 m</b>	
<b>Total dynamic loss in section</b>		<b>0.77 m</b>	



DYNAMIC LOSS CALCULATION			OD450 PE100 PN12.5	
DN450 Rising Main Up to River Crossing				
Flow rate	576.0 m <sup>3</sup> /hr	0.16 m <sup>3</sup> /s	<b>Flowrate</b>	<b>160.0 L/s</b>
Pipe internal diameter	382.0 mm	0.38 m	single pump flow	
Surface area	0.115 m <sup>2</sup>	15 inch		
Water velocity	1.396 m/s	0.0002 m		
Reynolds Number	530,113.37			
Roughness coefficient	0.150 mm	1.01E-06 m <sup>2</sup> /s		
Equivalent length of pipe	616 m	from CMBK long sections 14/4/04		
Temperature	20 deg. C			
Kinematic viscosity	1.006 m <sup>2</sup> /s			
Hydraulic gradient	4.39 m/km			
Pipe dynamic loss	2.71 m			
Component fitting losses:	k value	fitting loss		
		0.00 m	check formulae when inserting rows	
		0.00 m		
		0.00 m		
		0.00 m	The proposed pigging pit is in this section but the enlarged section and fittings are not expected to increase the duty head - only decrease it slightly - therefore it is ignored in the calcs.	
		0.00 m		
Total component losses		0.00 m		
Total dynamic loss in section		2.71 m		
DYNAMIC LOSS CALCULATION			OD400 PE100 PN20	
DN400 River Crossing				
Flow rate	576.0 m <sup>3</sup> /hr	0.16 m <sup>3</sup> /s	<b>Flowrate</b>	<b>160.0 L/s</b>
Pipe internal diameter	307.0 mm	0.31 m	single pump flow	
Surface area	0.074 m <sup>2</sup>	12 inch		
Water velocity	2.161 m/s	0.0002 m		
Reynolds Number	659,619.89			
Roughness coefficient	0.150 mm	1.01E-06 m <sup>2</sup> /s		
Equivalent length of pipe	749 m	from CMBK long sections 14/4/04 (path length, not chainage)		
Temperature	20 deg. C			
Kinematic viscosity	1.006 m <sup>2</sup> /s			
Hydraulic gradient	13.48 m/km			
Pipe dynamic loss	10.09 m			
Component fitting losses:	k value	fitting loss		
		0.00 m	check formulae when inserting rows	
		0.00 m		
		0.00 m		
		0.00 m		
		0.00 m		
Total component losses		0.00 m		
Total dynamic loss in section		10.09 m		

DYNAMIC LOSS CALCULATION		OD450 PE100 PN12.5	
DN450 Rising Main From River Crossing to SP300			
Flow rate	576.0 m <sup>3</sup> /hr	0.16 m <sup>3</sup> /s	<b>Flowrate</b> 160.0 L/s
Pipe internal diameter	382.0 mm	0.38 m	single pump flow
Surface area	0.115 m <sup>2</sup>	15 inch	
Water velocity	1.396 m/s	0.0002 m	
Reynolds Number	530,113.37		
Roughness coefficient	0.150 mm	1.01E-06 m <sup>2</sup> /s	
Equivalent length of pipe	2,066 m	from CMBK long sections 14/4/04	
Temperature	20 deg. C		
Kinematic viscosity	1.006 m <sup>2</sup> /s		
Hydraulic gradient	4.39 m/km		
Pipe dynamic loss	9.08 m		
Component fitting losses:	k value	fitting loss	
open discharge	1.00	0.10 m	check formulae when inserting rows
		0.00 m	
		0.00 m	
		0.00 m	
		0.00 m	
Total component losses		0.10 m	
Total dynamic loss in section		9.18 m	
PUMP DUTY CALCULATION		SP298 Lytton Rd Lytton	
Middle of operating band	0.7 RL		
Normal TWL in SP300 Wet Well	2.3 RL		TWL in SP300 inlet structure
Static head	1.5 m		
Total dynamic loss in suction	0.0 m		submersible station
Total dynamic loss in discharge	23.3 m		
Safety margin on dynamic loss for unaccounted fittings	5%		
Pump duty head	26.0 m		
Pump efficiency	76 percent		
Pump shaft power	54 kW		
Selected pump	Hidrostral H08K / 68kW		

NPSH CALCULATION		SP298 Lytton Rd Lytton
NPSHr = Static head at the inlet + surface pressure head - the vapor pressure of your product - the friction losses in the suction piping, valves and fittings		
Pump centreline	(1.3) RL	nominally 100mm below Stop Duty A
Stop Duty A	(1.2) RL	
Surface pressure head	10.3 m	normal atmospheric pressure 10.34m
Temperature	20 deg. C	
Vapour pressure	0.2 m	
Loss in suction	0.0 m	
NPSH Available	10.2 m	check Hidrostat curves for NPSHr
NPSH Required	3.0 m	from pump curve at the operating point
Safety Margin	7.2 m	positive is OK (prefer >1)

### System Curve

Single Pump Flow L/s	Duty Head m
	26.0
1	1.5
10	1.7
20	2.0
30	2.5
40	3.2
50	4.1
60	5.2
80	7.9
100	11.4
120	15.5
140	20.4
160	26.0
180	32.4
200	39.5



Parsons Brinckerhoff - Brisbane Office

Client: Brisbane Water

Project: Australia Trade Coast Sewerage Project

PB Job Code: 2138110B

## PERFORMANCE CURVE DATA

### SP 298 - Lytton Rd


Pump Type	Hidrostal H08K-M
Curve No.	84-K3229c
Imp. Diameter.	
Rated Power	68 kW

#### 1 Hidrostal 50 Hz

L/s	Total Hd
20	47
40	45.5
60	43
80	39.5
100	36
120	32.5
140	29.8
160	27
180	24.8
200	22.3
220	20
240	18
260	16
280	13
300	10

#### Smooth Pipe System Curve

L/s	Total Hd
0	1.5 created by FLYPS
15.4725	1.67674
30.945	2.20697
46.4174	3.09069
61.8899	4.32789
77.3624	5.91857
92.8349	7.86274
108.307	10.1604
123.78	12.8115
139.252	15.8162
154.725	19.1743
170.197	22.8859
185.67	26.951
201.142	31.3695
216.615	36.1416
232.087	41.2671
247.56	46.7462
263.032	52.5787
278.505	58.7647
293.977	65.3042
309.45	72.1971

**SP 298 (Lytton Rd) - Performance Curves - One Hidrostat H08K / 68kW**

Parsons Brinckerhoff - Brisbane Office  
Client: Brisbane Water  
Project: Australia Trade Coast Sewerage Project  
PB Job Code: 2138110B

Properties for Water

Temperature C	Density kg/m3	Kin viscosity m^2/s	Vapour Press m H2O
0	999.84	1.787E-06	0.062
4	999.97	1.514E-06	0.083
10	999.7	1.304E-06	0.125
15	999.09	1.137E-06	0.174
20	998.2	1.002E-06	0.238
25	997.04	8.910E-07	0.323
30	995.65	7.980E-07	0.433
40	992.22	6.540E-07	0.752
50	977.77	5.480E-07	1.258

Ref GCD 332 - 1.1

Interpolator

x=	30	a=	0.433
y=	35	b=	0.5925
z=	40	c=	0.752

b=            a -  $\frac{(a-c)*(x-y)}{(x-z)}$


For fluids other than water, parameters need to be investigated. Figures for water should not be used for other fluids.

17-MAR-2004 07:58 FROM WEIR SERVICES

TO 0-0738314223

P.02

(VSD)  
SP 298 (Lytton Rd) - System Curve (Subm)



Ⓐ = H08K-M @ 14.60 RPM

Ⓑ = H08K-M @ 730 RPM


15/3/04



17-MAR-2004 07:58 FROM WEIR SERVICES

TO 0-0738314223

P.03









Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix D

---

### Odour and Septicity Study (In Progress)







Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix E

---

### Geotechnical Information

- E1. Coffeys Reports
- E2. PB Report



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## **E1. Coffeys Reports**

---



**Coffey Geosciences Pty Ltd** ACN 056 335 516

Geotechnical | Resources | Environmental | Technical | Project Management

53B Fairlawn Street Nathan  
QLD 4111 Australia  
PO Box 108 Salisbury  
QLD 4107 Australia  
Telephone +61 7 3274 4411  
Facsimile +61 7 3274 4977  
Email brisbane@coffey.com.au

**Facsimile Transmission**

To	PARSONS BRINCKERHOFF	From	DAN ABOOD
Attention	IAN CAMERON	Date	27 MAY 2004
Facsimile number	3831 4223	Our Reference	B17928/01-B
cc	Number of pages including this page 4		
Subject:	SETTLEMENT ASSESSMENT - AUSTRALIA TRADE COAST SEWER, LYTTON ROAD, SP298		

Note. If you do not receive any of the pages of this fax, please telephone COFFEY on the above number as soon as possible.  
The contents of this facsimile (including attachments) may be privileged and confidential. Any unauthorised use of the contents is expressly prohibited. If you have received the document in error, please advise us by telephone (reverse charges) immediately and then shred the document. Thank you.

Parsons Brinckerhoff engaged Coffey Geosciences Pty Ltd to conduct various assessments associated with consolidation settlements for the area around the proposed Lytton Road Pump Station. The scope of work commissioned comprised the following three elements:

1. Assessment of settlement magnitude and duration (primary and secondary consolidation) for a range of vertical stress increments for the area of the pump station.
2. Assessment of the impacts of the adjacent Port of Brisbane Corporation (POBC) fill bund and hydraulically placed fill upon the long term settlement of the pump station site.
3. Provision of recommendations with respect to a recommended buffer zone around the pump station for additional fill on the POBC land.

This letter presents the results of the first of the items above. The settlement assessment was based on:

- Ground models and settlement parameters developed by Coffey during our involvement with the Port of Brisbane Motorway, which is very close to the pump station location;
- Specific subsurface information for the pump station site presented in the City Design report of 7 November 2003.

Based on the City Design data, the subsurface conditions at the pump station site are considered to be generally consistent with those near the eastern extents of Stage 1 of the Port of Brisbane Motorway. A general ground model showing settlement analysis parameters is shown on Figure 1. The model considers 27m of Recent alluvium, mainly comprising soft and firm clay, overlying stiffer, older alluvium of uncertain age. It also shows influence factors for an embankment up to 15m wide.

Figure 2 shows time versus settlement curves over a range of vertical stress increase. The significantly greater settlement beyond 30 kPa is due to a preconsolidation pressure of about 35kPa in excess of effective in-situ vertical stress, which affects the majority of the soil profile. The settlement curves do not follow a classical shape because they have been derived by integrating curves from several different layers, which have differing rates of settlement.

Although the curves are based in a detailed data set, they should be used with caution. Analyses of the reliability of the settlement data using the method of Duncan (2000) provide an approximate guide to the likely accuracy of settlement calculations by examining the potential error in the main parameters. Results of the reliability calculations for the model

B:\BRISBANE\B17928-1\Correspondence\B17928.01-B.Doc



**Coffey Geosciences Pty Ltd** ACN 056 335 516

B17928/01-B  
27 MAY 2004

2

shown in Figure 1 are summarised in Table 1. The calculations show that there is about a 10% probability that the settlement may be 1.5 times greater than that predicted.

**TABLE 1: SUMMARY OF RELIABILITY OF SETTLEMENT CALCULATIONS**

Ratio of Actual Settlement to That Predicted	% Probability of Exceedance
1.1	33
1.25	23
1.5	11
2	3

Should you require further information, please contact the undersigned.

For and on behalf of


**COFFEY GEOSCIENCES PTY LTD**

**IAN SHIPWAY**


Manager, Brisbane

**Attachment:** Figure 1. Settlement Model  
Figure 2. Calculated Settlements

B:\BRISBANE\B17928-1\Correspondence\B17928.01-B.Doc



## ASSESSMENT OF PRIMARY &amp; SECONDARY SETTLEMENT OVER TIME



Coffey

**Coffey Geosciences Pty Ltd**

ACN 056 335 516

Geotechnical | Resources | Environmental | Technical | Project Management

Drawn	DA	<b>PARSONS BRINCKERHOFF</b> <b>TRADE COAST SEWER PROJECT</b> <b>LYTTON RD PUMP STATION</b> <b>CALCULATED SETTLEMENTS</b>	<b>FIGURE 2</b>  Job no: <b>B17928/1</b>
Approved			
Date	27/05/2004		
Scale	NTS		

B:\BRISBANE\B17928-1\Calculations\Spreadsheets\Settlement Analysis Refined.xls\A4 Portrait Figure

15-JUN-2004 17:38 FROM COFFEY

TO 038314223

P.01

**Coffey Geosciences Pty Ltd** ACN 056 335 516

Geotechnical | Resources | Environmental | Technical | Project Management

538 Fairlawn Street Nathan  
QLD 4111 Australia  
PO Box 108 Salisbury  
QLD 4107 Australia  
Telephone +61 7 3274 4411  
Facsimile +61 7 3274 4977  
Email brisbane@coffey.com.au

**Facsimile Transmission**

To	<b>PARSONS BRINCKERHOFF</b>	From	<b>DAN ABOOD</b>
Attention	<b>IAN CAMERON</b>	Date	<b>15 JUNE 2004</b>
Facsimile number	<b>3831 4223</b>	Our Reference	<b>B17928/1-C</b>
cc	Number of pages including this page <b>2</b>		
Subject:	<b>SETTLEMENT ASSESSMENT AUSTRALIA TRADE COAST SEWER LYTTON ROAD SP398</b>		

Note. If you do not receive any of the pages of this fax, please telephone COFFEY on the above number as soon as possible. The contents of this facsimile (including attachments) may be privileged and confidential. Any unauthorised use of the contents is expressly prohibited. If you have received the document in error, please advise us by telephone (reverse charges) immediately and then shred the document. Thank you.

Parsons Brinckerhoff (PB) engaged Coffey Geosciences Pty Ltd (Coffey) to conduct various assessments associated with consolidation settlements for the area around the proposed Lytton Road Pump Station. The scope of work commissioned comprised the following three elements:-

1. Assessment of settlement magnitude and duration (primary and secondary consolidation) for a range of vertical stress increments for the area of the pump station.
2. Assessment of the impacts of the adjacent Port of Brisbane Corporation (POBC) fill bund and hydraulically placed fill upon the long term settlement of the pump station site.
3. Provision of recommendations with respect to a recommended buffer zone around the pump station for additional fill on the POBC land.

The first of these items above was addressed in our facsimile (ref. B17928/1-B) dated 27 May 2004. This letter presents the results of items 2 and 3 above. The settlement assessment was based on:-

- Ground models and settlement parameters developed by Coffey during our involvement with the Port of Brisbane Motorway, which is very close to the pump station location; and
- Specific subsurface information for the pump station site presented in the City Design report of 7 November 2003.

Based on the City Design data, the subsurface conditions at the pump station site are considered to be generally consistent with those near the eastern extents of Stage 1 of the Port of Brisbane Motorway. The model considers 27m of recent alluvium, mainly comprising soft and firm clay, overlying stiffer, older alluvium of uncertain age.

Based on the plans provided to Coffey by PB (Brisbane Water drawing No 486/5/7 – WR 101\_023/P1 and POBC plan No 104727) the following assumptions have been made:-

- The natural ground level at the pump station site and surrounding area is approximately RL~2m;
- The finished level of the Hardstand area is to be RL~2.75m; and
- The current height of the adjacent Port of Brisbane Corporation hydraulically placed fill is RL~3.5m and it has

B:\BRISBANE\B17928-1\PARSONS (IS)\Correspondence\B17928-1-C.Doc

15-JUN-2004 17:38 FROM COFFEY

TO 038314223

P.02


**Coffey Geosciences Pty Ltd** ACN 056 335 518

 B17928/1-C  
 15 JUNE 2004

2

been in place for a minimum of 5 years.

Based on the above assumptions and adopted ground model, the following settlement assessments and recommendations have been made:-

- Assuming the existing hydraulically placed fill has been in place for a minimum of 5 years, then it is expected that over 95% of the expected primary consolidation at the pump station location will have already occurred. It is estimated that the remaining primary settlement resulting from the adjacent hydraulically placed fill will be minimal. Assuming a design life for the pump station of 40 years, then up to an additional 10mm of secondary creep settlement may occur over the life of the structure.
- Placement of the Hardstand fill (0.75m thick) will result in an estimated settlement of ~95mm primary settlement. It is predicted that 95% of the primary settlement will occur within 5 years of placement of the fill. Assuming a design life for the pump station of 40 years, then up to an additional 10mm of secondary creep settlement is predicted over the life of the structure.
- Should an additional 2m of fill be placed on the existing hydraulically placed fill area, then it is estimated 110mm of primary consolidation settlement (additional 15mm to that expected from hardstand fill) will occur at the pump station within 5 years of completion of filling, an additional secondary creep settlement of up to 10 mm will occur over the life of the structure.
- Placement of additional loads adjacent to the pump station will result in increased settlements. The extent of such settlement is dependant on the magnitude and extent of the load and on the proximity of the loaded area to the pump station; as such it is difficult to define a buffer zone around the pump station. It is predicted that provided any additional filling carried out on the adjacent POBC land is not greater than 2m in height and is set back a minimum of 10m from the crest of the existing fill bund then the resulting additional settlements at the pump station location should be less than 10mm. It is recommended that specific settlement analysis be carried out once proposed development details for the adjacent land are known.

The predicted settlements should be used with caution. As indicated in our previous facsimile there is about 10% probability that the actual settlement may be 1.5 times greater than that predicted.

Should you require further information, please contact Dan Abood or the undersigned.

For and on behalf of  
 COFFEY GEOSCIENCES PTY LTD

IAN SHIPWAY  
 Manager, Brisbane

B:\BRISBANE\B17928-1\PARSONS (IS)\Correspondance\B17928-1-C.Doc

TOTAL P.02

## Cameron, Ian

---

**From:** Cameron, Ian  
**Sent:** Wednesday, 16 June 2004 8:54 AM  
**To:** John Bower (ec1psbw@brisbane.qld.gov.au)  
**Subject:** FW: FAX From Coffey - 15/06/04

**Importance:** High



Floor 7 Fax  
received\_001.pdf (..  
John

Coffeys settlement report for SP298

---

Ian Cameron  
Executive - Water  
Parsons Brinckerhoff Australia Pty Limited  
12th floor, IBM Centre  
348 Edward Street  
GPO Box 2907  
Brisbane QLD 4001 Australia  
tel: +61(0)7 3218 2222  
direct: +61(0)7 3218 2644  
fax: +61(0)7 3831 4223  
mob + (61) 0401 148 142  
email: icameron@pb.com.au  
www.pb.com.au and www.pbworld.com

Parsons Brinckerhoff (PB), formerly PPK Environment & Infrastructure, is a leading transport, infrastructure and environment consultancy and has been providing this service in Australia for over 38 years.

-----Original Message-----

**From:** AU BNE, Reception  
**Sent:** Tuesday, 15 June 2004 5:32 PM  
**To:** Cameron, Ian  
**Subject:** FAX From Coffey - 15/06/04  
**Importance:** High

-----Original Message-----

**From:** Parsons Brinckerhoff [mailto:bnereception@pb.com.au]  
**Sent:** Tuesday, 15 June 2004 5:31 PM  
**To:** Brisbane Reception  
**Subject:** Incoming Fax Floor 7  
**Importance:** High

FROM=61732744977  
TO=+61 7 3831 4223  
DATE=15/06/2004  
TIME=17:30:47  
TIMEZONE=+10:00









Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## E2. PB Report

---



## MEMORANDUM

**Date:** 27 April 2004  
**To:** Ian Cameron  
**cc:** Malcolm Pound (Cardno MBK Qld Pty Ltd)  
**From:** Jason Williams  
**Job No:** 2138110B/1800  
**Re: Trade Coast Sewer Project, Geotechnical Advice**  
**FINAL**

### **Parsons Brinckerhoff**

12th floor, IBM Centre  
 348 Edward Street  
 Brisbane Qld 4000  
 GPO Box 2907  
 Brisbane QLD 4001  
 Australia  
 Telephone +61 7 3218 2222  
 Facsimile +61 7 3831 4223  
 Email brisbane@pb.com.au

**ABN 84 797 323 433**

NCSI Certified Quality System ISO 9001

This engineering assessment is based on supplied information, listed in the references section of this report. The information is limited and sometimes contradictory. Section 3 discusses the reliability of this assessment in more detail.

## BACKGROUND

Ian Cameron from Parsons Brinckerhoff (PB) requested on behalf of Cardno MBK (Qld) Pty Ltd (MBK) that the following issues be addressed regarding three pump stations relating to the Trade Coast Sewer Project, Brisbane. For the Viola Place, Lytton Road and Serpentine Road pump stations each of the following issues were required to be addressed:-

- Establish a ground model using existing data.
- Establish expected foundation pressures (MBK to supply).
- Provide advice on allowable bearing pressure and likely settlement beneath structures, considering possible tilt.
- Comment on foundation options.
- Provide advice on sheet piling in terms of construction sequence.
- Provide advice on ultimate shear at perimeter of pump station structures under uplift situation, for both long and short term situations.
- Consider effect on ground if dewatered.
- Comment on reliability of engineering assessment.

Previous work at the pump station sites was undertaken by Coffey Geosciences (CG) and Brisbane City Council (BCC).

### 1.0 GROUND MODELS

Ground model sketches are contained in Attachment A.

#### 1.1 Viola Place

The ground model is based on one CG borehole (BH 1) and may be summarised as follows:-

**Fill** Ground surface (about RL 3.9 m) to about RL 1.3 m. Consisting of hard Sandy CLAY. For the purposes of the ground model it is assumed that weaker areas are

*Over a Century of  
Engineering Excellence*

Parsons Brinckerhoff Australia Pty Limited ACN 078 004 798 and Parsons Brinckerhoff International (Australia) Pty Limited ACN 006 475 056 trading as Parsons Brinckerhoff ABN 84 797 323 433

present in the fill, as indicated by BCC bores 120 m south of the pump station where SPT N values of 2 were recorded.

**Recent Alluvium** About RL 1.3 m to about RL -2.1 m. Comprising CLAY of variable consistency, from soft through to stiff. Lenses or bands of generally discontinuous sand might reasonably be expected.

**Older Alluvium** Occurring from about RL -2.1 m to at least about RL -6.1 m (limit of testing) and consisting of stiff to very stiff CLAY interbedded with medium dense SAND. CG describe this layer as hard clay but give a design  $C_u$  of 150 kPa. For the ground model it will be assumed this layer is stiff to very stiff.

**Groundwater** Groundwater was noted by CG at about RL 2.8 m (1.1m bgl). Given the proximity of the site to tidal water it may be reasonable to assume that fluctuation in groundwater levels is possible. It is understood no monitoring data is available.

Assumptions in the ground model include that the horizons encountered in the single CG borehole are uniform across the site. The RL of the CG borehole was not measured and is assumed to be about RL 3.9 m. It is understood that no other additional test boreholes are proposed at this stage.

## 1.2 Lytton Road

The ground model is based on comparison of soil horizons between BH 27 situated adjacent to the site and CPT 6 and CPT 21 situated near to the site. It was not possible to ascertain the exact distances of the test positions relative to the proposed infrastructure given the lack of features on respective site plans for cross-referencing. Additionally, relative levels are not available for CPT 6 and CPT 21. The ground model may be summarised as follows:-

**Fill** Ground surface (about RL 3.1 m) to about RL 1.55 m. The nature of the fill is unknown and for the purposes of the ground model it is assumed that weak areas are present, given the lack of available test data. The presence of fill is largely assumed based on existing ground contours which show the ground surface at about RL 3.1 m.

**Recent Alluvium** About RL 1.55 m to about RL -25.0 m. Comprising soft CLAY grading to stiff to very stiff CLAY, with loose SAND lenses throughout. Horizons based on correlation between test locations are recognised approximately as follows:

RL 1.55 m to RL -6.8 m	<b>Very soft CLAY</b> with very loose SAND between RL -2.15 m and RL -5.0 m. Other thin sand bands possible.
RL -6.8 m to RL -17.8 m	<b>Soft to firm CLAY.</b> Loose SAND bands possible, particularly between RL -14.0 m and RL -17.8 m.
RL -17.8 m to RL -25.0 m	<b>Firm to stiff CLAY.</b> Loose SAND bands possible.

**Older Alluvium** About RL -25.0 m to at least about RL -31.1 m (limit of testing). Consisting of stiff to very stiff CLAY interbedded with medium dense SAND. Test refusal is recorded in CPT 21 at about RL -27.4 m.

**Groundwater** Groundwater was recorded in BCC BH 27 at about RL 1.25 m on 28 May 2003. Given the proximity of the site to tidal water it may be reasonable to

assume that fluctuation in groundwater levels is possible. It is understood no monitoring data is available.

Assumptions in the ground model include that the horizons encountered in BCC BH 27 are generally uniform across the site. It is understood that no other additional test boreholes are proposed at this stage.

### 1.3 Serpentine Road

The ground model is based on comparison of soil horizons in the following boreholes:-

- BCC (2002) - BH 1 situated at the proposed pump site and BH 2 situated 35 m north of the pump site
- BCC (1994) - BH 1 and BH 2, both situated near to the pump site. Exact test positions relative to pump station footprint unknown.

Ground level data was not available for the site, or for the boreholes. However, CG refer to a ground level of RL 2.0 m at the site in a fax to PB dated 16 June 2003 relating to sheet piling. Based on a ground surface level at the site of about RL 2.0 m, the ground model may be summarised as follows:-

**Fill** Occurring from ground surface (assumed RL 2.0 m) to between about RL -0.1 m and RL 1.5 m, and consisting of Gravelly Clayey SAND. For the purposes of the ground model it is assumed that weak areas are present, given the lack of available test data.

**Recent Alluvium** Occurring from between about RL -0.1 m and RL 1.5 m, to about RL -26.9 m. Horizons based on correlation between test locations are recognised approximately as follows:

RL -0.2 m to RL -9.2 m	<b>Very loose SAND, Silty SAND &amp; Clayey SAND.</b>
RL -9.2 m to RL -12.9 m	<b>Soft CLAY.</b> Loose SAND bands possible.
RL -12.9 m to RL -26.9 m	<b>Firm CLAY.</b> Loose SAND bands possible.

**Older Alluvium** Occurring from about RL -26.9 m to at least about RL -33.3 m (limit of testing) and consisting of stiff to very stiff CLAY interbedded with medium dense SAND.

**Groundwater** Groundwater inflow was recorded in BCC (2002) BH 1 at 1.7m bgl (about RL 0.3 m) and BH 2 at 2.1 m bgl (about RL -0.1 m). Additionally, given the proximity of the site to tidal water it may be reasonable to assume that fluctuation in groundwater levels is possible.

Assumptions in the ground model include that the horizons encountered in BCC (2002) BH 1 are generally uniform across the site. Site levels and borehole levels have been assumed. It is understood that no other additional test boreholes are proposed at this stage.

## 2.0 ENGINEERING COMMENTS

### 2.1 Applied Foundation Pressures

Information regarding expected pressure applied to the foundation soils for the Viola Place pump station has been supplied by MBK. It is understood applied pressures vary

linearly from 80 kPa under the outer edge of the pump well to 20 kPa under the outer edge of the valve pit. For the purposes of this report it is assumed that the applied pressures described above will also be the same for the Lytton Road and Serpentine Road pump stations. It is understood that Viola Place and Lytton Road are wet well pump stations and that Serpentine is a dry well pump station and that the applied pressures supplied by MBK are for both wet and dry conditions.

PB structural engineers indicate applied pressure for the Viola Place ferric chloride dosing area is 18 kPa and for the generator hardstand is 13 kPa.

## 2.2 Sheet Piling Advice

Sheet piling is considered necessary for Viola Place, Lytton Road and Serpentine Road pump stations. Sheet piling is suggested for the entire construction site. This is considered to be the most practical approach, rather than sheet piling around certain parts of the pump structure only. The construction sequence suggested is as follows:-

- Driven sheet piles surrounding entire construction site are to be driven from the surface.
- Sheet pile depths to be sufficient to maintain internal stability of unsupported sections where significant level differences are present.
- Install internal sumps with dewatering pumps.
- External partial dewatering around perimeter of sheet piles using close spaced spear points, providing resulting settlement is satisfactory in terms of nearby buildings, structures, services etc.
- Excavation to design levels.
- Construction of pump station inside steel sheet piling.
- Backfilling with select engineered fill as and when required during construction of various pump station sections.
- Backfill to comprise select engineered fill, clayey gravel mix (to give maximum adhesion with pump walls).
- All backfill to be compacted to recognised standards.

CG provided geotechnical parameters for sheet pile design for Viola Place (Table 1) in their 2004 site investigation report. PB can design sheet pile support for Viola Place, Lytton Road and Serpentine Road if required. It would be an advantage if MBK could advise if the sheet piles can be internally braced and/or ground anchored.

Table 1. Viola Place material properties supplied by CG for sheet pile design.

Material	Undrained Parameters (Short Term)		Drained Parameters (Long Term)		Bulk Density (t/m <sup>3</sup> )
	$C_u$ (kPa)	$\phi_u$ (°)	$C'$ (kPa)	$\phi'$ (°)	
Fill	40	0	2	25	1.7
Firm to Stiff Clay	40	0	2	25	1.6
Hard Clay	150	0	5	25	1.8
Medium Dense Sand	0	35	0	35	1.7

\* Extracted from CG 2004 Site Investigation Report for Viola Place.



## 2.3 Allowable Bearing Pressure and Settlement

Clay is the predominant soil type in the Viola Place and Lytton Road ground models and as such the allowable bearing pressure (ABP) is assessed based on the shear strength of the clays. As no triaxial data is available it was necessary to assume shear strengths based on pocket penetrometer data supplied on geotechnical bore logs. Additionally, no consolidation test data is available making it necessary to assume coefficient of volume compressibility ( $m_v$ ) parameters using standard  $m_v$  values based on clay type, found in soil mechanics texts. The ABP at Serpentine Road is assessed based on SPT N values. Values of allowable bearing pressure (ABP) and estimated settlements are provided in Table 2.

Table 2. Suggested allowable bearing pressure and estimated settlements.

	<b>ABP (kPa) of Natural Soils</b> <i>(based on 4m wide pad footings)</i>	<b>Settlement</b> <i>(exclusive to settlement due to dewatering)</i> <i>(values approximate &amp; based on limited data)</i>
<b>Viola Place</b>	<p>Greater than about 5 m depth, ABP = 80 kPa.</p> <p>Parts of the pump structure founded at depths shallower than 5 m, ABP = 35 kPa.</p> <p>The existing fill is considered unsuitable to found on.</p> <p>ABP in compacted select fill, to 98% standard compaction, is assessed at 100 kPa provided it is at least 1.5 m thick below the founding element.</p>	<p>&lt;30 mm beneath footings at about 5 m depth (supplied by CG).</p> <p>Potential is recognised for differential settlement between adjoined parts of the pump structure which are founded at varied levels, given the presence of a soil profile with variable strength character. Without restricting ABP to 35 kPa in the upper 5m of soil profile, potential exists for differential settlement of 25-35 mm and total settlement of 50-60 mm. It is not known what the pump structure tolerances are.</p>
<b>Lytton Road</b>	<p>Very soft clay from about RL 1.85 to RL -6.8, ABP = 5 kPa</p> <p>For the soft to firm clay beneath RL -6.8, an ABP of 15 kPa is suggested for design purposes.</p> <p>The existing fill is considered unsuitable to found on.</p>	<p>Not greater than 25-30 mm.</p> <p>Not greater than 25-30 mm.</p>
<b>Serpentine Road</b>	<p>Very loose sand from about RL -0.2 to RL -9.2, ABP = 10 kPa.</p> <p>Soft to firm clay below about RL -9.2, ABP = 15 kPa is suggested for design purposes.</p> <p>The existing fill is considered unsuitable to found on.</p>	<p>Not greater than 25-30 mm.</p> <p>Not greater than 25-30 mm.</p>



It is understood that the intention at tender design stage was to design buoyant pump station structures, thus minimising the applied stress at foundation level and avoiding the need for robust foundation solutions such as piling. It is understood piling had been discussed for each site and been considered not warranted. Since tender design stage various design levels have changed and new geotechnical information has been obtained. The outcome regarding foundation options for each of the pump stations is assessed as follows:- (providing groundwater levels are consistent with ground models)

#### Viola Place

A floating design is viable. However, it is suggested that foundations at less than about 5m depth be placed on >1.5 m thickness of compacted select fill to minimise total and differential settlement impacts.

#### Lytton Road

Assumptions at tender design stage include that the pump station structure would be lighter than the soil being replaced. Using current design levels and BCC BH 27 which was obtained after tender discussions, the net effective stress increase at foundation level is estimated to range from 20 kPa to 30 kPa, with groundwater at RL 1.25 m. The structure is therefore heavier than the soil it replaces and additionally exceeds the ABP of 5 kPa, with differential settlement and tilting a likely outcome. It is suggested that other foundation options be considered. Options include piling, lowering the level of the pump station if the design would allow, or possibly spreading the load over broader foundations. With broader foundations there are concerns about possible eccentric loads given the extra breadth of foundation required to comply with 5 kPa ABP.

In the consideration of piled foundations it is suggested that the sheet piling construction sequence allow for installation of piled foundations prior to sheet pile installation. Bored or driven piles could be considered however caution may be required with driven piles. The effects of vibration from driven piles on the soft clay founding soils are unknown and may be undesirable in terms of settlement. Further consideration of the effects of vibration would be recommended.

#### Serpentine Road

Current design levels (invert level about -3.9 m) are approximately 2.5m deeper than those shown at tender design stage. Based on a groundwater level of RL -0.1 m (BCC-2002 BH 2), the net effective stress change at foundation level is estimated to range between -30 kPa to -55 kPa (uplift), also possibly inducing tilt. If additional weight cannot be accommodated in the design to resist uplift then an anchor system may need to be considered. Anchor piles would be an option. Broader foundations or outstands (possibly buttressed) may also be suitable as anchors but would warrant further structural consideration.

## **2.4 Buoyancy and Uplift Resistance**

### **BUOYANCY**

Given that the proposed structures are generally lighter than the soil being replaced, and that foundations occur beneath groundwater levels there is potential for buoyancy of the pump structures. The magnitude of the buoyant forces will act differentially on the structures given that foundation levels vary within the sites. Complicating the buoyancy issue is the likelihood of the groundwater level to fluctuate above or below the measured level due to possible tidal effects. Groundwater monitoring has not been conducted and consequently for design purposes it may be applicable to consider the following:-

1. Flood conditions. Flood data should be obtained to verify flood heights, and therefore the likely uplifts due to buoyancy.

2. If groundwater occurs below the deepest founding level (i.e. should pumping be required to maintain the construction area, or groundwater levels drop due to other phenomenon).

#### ***TILTING DUE TO BUOYANCY***

There is potential for tilt due to buoyancy at each of the pump stations when groundwater levels are high given the likelihood of stronger buoyancy forces beneath the deeper pump sections. It is expected that the structures will be designed to be heavy enough to resist buoyancy. This is a design issue and it becomes a balancing exercise between providing enough weight to resist the buoyancy forces whilst not exceeding the ABP during times of possible lower groundwater. A solution to limit tilting impacts would be to design the pump station foundations to the same level.

#### ***UPLIFT RESISTANCE***

Provided sheet piling surrounds the entire construction the ultimate shear at the perimeter of the pump station depends primarily on the adhesion between the select backfill material and the pump station walls. For design purposes a value of zero for ultimate shear is suggested for assessment of uplift at the perimeter of the pump station elements.

### **2.5 Effect on Ground if Dewatered**

#### ***NEARBY GROUND***

Dewatering will increase the effective stresses acting on the soils which would result in settlement. CG quote in their 2004 site investigation report 75 mm consolidation settlement for Viola Place depending on the drawdown and this seems a reasonable estimate based on limited data. Soils are softer at Lytton Road and Serpentine Road pump stations and consolidation settlement at both stations could exceed about 150 mm, depending on the drawdown. The consolidation settlements stated above could be potentially damaging to nearby structures (roads, buildings, services, etc) requiring external dewatering to be reconsidered and suitable sheet piles designed. PB structural engineers indicate there are no structures or services at risk at the Viola, Lytton or Serpentine pump station sites.

Without any groundwater monitoring or consolidation data it is difficult to estimate the size of the area that may be influenced by settlement and the severity. Dewatering around the perimeter of sheet piling driven to about 4 to 5 m depth is likely to influence an area of about 35 m to 40 m out from the sheet piles, providing water levels are monitored and allowance for re-injection of the water is made.

#### ***FOUNDATION SOILS***

Settlements stated above due to drawdown also apply to the foundation soils. Foundation soils could settle about 75mm at Viola Place and about 150mm at Lytton Road and Serpentine Road, depending on the drawdown. If settlement is taking place when construction of the pump stations and associated infrastructure has commenced then there is a risk of differential settlement. In this regard tilting may be an issue during construction and allowance should be made in the pipe work to take account of differential movements.

### 3.0 GENERAL COMMENT ON RELIABILITY OF ENGINEERING ASSESSMENT

The reliability of this engineering assessment for the pump stations is subject to the following:

- There is no groundwater level monitoring data for any of the sites.
- The range of groundwater level fluctuations at each site due to tidal influences is unknown.
- RL data of the test boreholes and CPTs at the ground surface is mostly absent.
- Ground levels are absent for Serpentine Road.
- No triaxial (shear strength) or consolidation test data is available for any of the sites, which has resulted in our assumptions of this data. Dale Waters from BCC confirms there were no triaxial tests ever conducted and only one oedometer consolidation test conducted, which is located about 1.7km from the Lytton Road pump station.

No accountability can be taken for any of the assumptions made in this assessment or of their impact on the ultimate designs. Including the above, assumptions for the sites include:-

#### Viola Place

The ground model provided in this report is based on 1 borehole (CG BH 1) for which there is limited geotechnical test data and no measured RL. The borehole RL at the ground surface was assumed.

#### Lytton Road

The ground model provided in this report is based on 1 borehole (BCC BH 27) and two CPT tests (CPTs 6 & 21) for which there is limited geotechnical test data. It was necessary to assume the relative levels of the ground surface of the CPTs. Data is contradictory where some SPT N values are zero but pocket penetrometer values are between 10 kPa to 110 kPa.

#### Serpentine Road

The ground model provided in this report is based on four boreholes (BCC-1994 BHs 1 and 2, and BCC-2002 BHs 1 and 2) for which limited geotechnical test data is available. It was necessary to assume the relative levels of the site and of the ground surface at the test boreholes.

For each of the above sites, settlement limits the suggested ABP values. The settlement estimates are based on assumed  $m_v$  values which is not desirable given the sensitivity of settlement calculations to  $m_v$  values. The ABP values cannot be further refined without laboratory oedometer consolidation data. The ABP for Viola Place and Lytton Road is assessed based on pocket penetrometer derived estimates of shear strength whereas typically undrained triaxial or multi-stage triaxial laboratory test data would be relied on.

With alluvial strata found at each of the pump station sites, changes in ground profile could occur over short distances and there is a risk that the ground models on which the engineering assessment is based could be different than as modelled. Refer to attachment B regarding further limitations of geotechnical advice.

## 4.0 CONCLUSIONS

- The ground models are based on limited data.
- Laboratory test results would typically be relied on when assessing ABP, settlement and foundation options. However, laboratory test data is not available for any of the pump station sites under consideration.
- Ground conditions at Lytton Road consist of very soft clay and at Serpentine Road consist of very soft clay and very loose sand.
- Low ABPs apply for each of the pump station sites, more so for Lytton Road and Serpentine Road than Viola Place. The low ABPs are in order to limit total and differential settlements impacts and tilting.
- Sheet piling is suggested for construction of all pump station sites.
- At each pump station site there is potential for significant buoyancy effects due to high ground water levels, particularly at Serpentine Road.
- At each pump station a value of zero for ultimate shear is suggested for assessment of uplift at the perimeter of the pump station elements.
- Dewatering will induce settlement in foundation soils and in nearby ground.
- At Viola Place it is suggested that foundations at less than about 5m depth be placed on >1.5 m thickness of compacted select fill to minimise total and differential settlement impacts.
- Pile foundations are a suggested option for Lytton Road to accommodate the low ABP. More geotechnical data could further refine the assessment of the site and allow closer scrutiny of foundation options but the general view is that the soils at the site are softer than expected and the design needs to accommodate this.
- An anchor system is one solution for Serpentine Road pump station to counter buoyancy effects. Possible options requiring further consideration include additional weight in the structure, broader foundations or outstands (possibly buttressed) or anchor piles.
- The level of the ground water is assessed to play a crucial role in the design of a buoyant structure, and at each of the pump station sites no ground water level monitoring has been conducted.
- The pump stations will be constructed in an environment described in BCC reports as sometimes highly aggressive to steel and concrete due to the pH of the ground water and the sulphur content of the soils. Although no data is available specific to the pump station sites, the design should consider that these corrosive conditions are likely.
- The foundation soils may be sensitive to vibrations.

## 5.0 REFERENCES

### Viola Place

Coffey Geosciences Pty Ltd (2004). Australia Trade Coast Sewer Project. Viola Place Pump Station (SP299), Geotechnical Investigation for Parsons Brinckerhoff.

Brisbane City Council (1994). Brisbane Water Limited, Contaminated Land & Acid Sulphate Soil Assessment, ATC Sewerage (North) Viola Street to Serpentine Road, Pinkenba – Appendix B. Soil Bore Logs.

Drawings: Viola Place Pumping Station (Mar 2004): SP299 Sectional Plan, Dwg No 486/5/7-SQ700/010 Amend P2, and (Jan 2004) SP299 Sections, Dwg No 486/5/7-SQ700/011 Amend P2, and (Feb 2004) SP299 Locality & Site Plan Dwg No 486/5/7-SQ700/001 Amend P3.

### Lytton Road

City Design (2003). Geotechnical Data Report, Australia Trade Coast Sewerage Project, Lytton Road, Lytton to Serpentine Road, Pinkenba. March 2003. Ref: CD/T6-G10389095-PR001Bjsb

City Design (2003). Supplementary Geotechnical Data Report, Australia Trade Coast Sewerage Project, Lytton Road to Brisbane River, Lytton. November 2003. Ref: CDT6-G10389095-PR002Bjsb

Soil Surveys (2002). Port of Brisbane Corporation, Clunies Flat Industrial Subdivision, Lytton Road, Lytton. Project No 102-6514, August 2002.

Drawings: Lytton Road Pumping Station (Feb 2004): SP298 Sections, Dwg No 486/5/7-WR101\_031 Amend P1, and (Feb 2004) SP298 Site Plan, Dwg No 486/5/7-WR101\_022, Amend P1.

### Serpentine Road

Brisbane City Council (1994). Investigation Report 93038 - Appendix B. Borehole and CPT Locations & Records. Department of Water Supply & Sewerage Projects Design Section, Eagle Farm to Luggage Point Rising Main, Serpentine Road Structures. August 1994.

Brisbane City Council (2002). Attachment B. Soil Bore Logs. Australia Trade Coast North, Viola St to Serpentine Road. Project CD/T6 – G1/0389212.

Coffey Geosciences fax to Parsons Brinckerhoff. 16 June 2003. Ref B17625/1-D. Australia Trade Coast Sewer, Serpentine Road Pump Station Temporary Works.

Drawings: Serpentine Road Pumping Station (Jan 2004): SP300 Section, Dwg No 486/5/7-TR201\_031 Amend P1.

### Other Drawings

Tender Drawings – 20/062003: Australia Trade Coast Sewerage Project. Drawings PD201-204, PD301-304, PD101-104.

Australia Trade Coast Sewerage Project 3/06/03: Borehole Locations, Dwg No PD005, Amend A, and 3/06/03 Key Plan, Dwg PD003, Amend A.

## **Attachment B. Limitations of Geotechnical Advice**

### **Reliance on Data**

In preparing the report, PB has relied upon data, surveys, analyses, designs, plans and other information provided by the Client and other individuals and organisations, most of which are referred to in the report ("the data"). Except as otherwise stated in the report, PB has not verified the accuracy or completeness of the data. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations in the report ("conclusions") are based in whole or part on the data, those conclusions are contingent upon the accuracy and completeness of the data. PB will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to PB.

### **Geotechnical Investigation**

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared to meet the specific needs of individuals. A report prepared for a consulting civil engineer may not be adequate for a construction contractor or even some other consulting civil engineer. This report was prepared expressly for the Client and expressly for purposes indicated by the Client or his representative. Use by any other persons for any purpose, or by the Client for a different purpose, might result in problems. The Client should not use this report for other than its intended purpose without seeking additional geotechnical advice.

### **This Geotechnical Report is based on Project-specific Factors**

This geotechnical engineering report is based on a subsurface investigation, which was designed for project-specification factors, including the nature of any development, its size and configuration, the location of any development on the site and its orientation, and the location of access roads and parking areas. Unless further geotechnical advice is obtained this geotechnical engineering report cannot be used:

when the nature of any proposed development is changed; or

when the size, configuration location or orientation of any proposed development is modified.

This geotechnical engineering report cannot be applied to an adjacent site.

### **The Limitations of Site Investigation**

In making an assessment of a site from a limited number of boreholes or test pits there is the possibility that variations may occur between test locations. Site exploration identifies specific subsurface conditions only at those points from which samples have been taken. The risk that variations will not be detected can be reduced by increasing the frequency of test locations; however this often does not result in any overall cost savings for the project. The investigation programme undertaken is a professional estimate of the scope of investigation required to provide a general profile of the subsurface conditions. The data derived from the site investigation programme and subsequent laboratory testing are extrapolated across the site to form an inferred geological model and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour with regard to the proposed development. Despite investigation the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration programme, no matter how comprehensive, can reveal all subsurface details and anomalies.

The borehole logs are the subjective interpretation of subsurface conditions at a particular location, made by trained personnel. The interpretation may be limited by the method of investigation, and cannot always be definitive. For example, inspection of an excavation or test pit allows a greater area of the subsurface profile to be inspected than borehole investigation, however, such methods are limited by depth and site disturbance restrictions. In borehole investigation, the actual interface between materials may be more gradual or abrupt than a report indicates.

### **Subsurface Conditions are Time Dependent**

Subsurface conditions may be modified by changing natural forces or man-made influences. A geotechnical engineering report is based on conditions, which existed at the time of subsurface exploration.

Construction operations at or adjacent to the site, and natural events such as floods, or groundwater fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. The geotechnical engineer should be kept apprised of any such events, and should be consulted to determine if additional tests are necessary.

### **Avoid Misinterpretation**

A geotechnical engineer should be retained to work with other appropriate design professionals explaining relevant geotechnical findings and in reviewing the adequacy of their plans and specifications relative to geotechnical issues.

### **Bore/Profile Logs Should Not Be Separated from the Engineering Report**

Final bore/profile logs are developed by geotechnical engineers based upon their interpretation of field logs and laboratory evaluation of field samples. Customarily, only the final bore/profile logs are included in geotechnical engineering reports. These logs should not under any circumstances be redrawn for inclusion in architectural or other design drawings. To minimise the likelihood of bore/profile log misinterpretation, contractors should be given access to the complete geotechnical engineering report prepared or authorised for their use. Providing the best available information to contractors helps prevent costly construction problems. For further information on this matter reference should be made to "Guidelines for the Provision of Geotechnical Information

in Construction Contracts" published by the Institution of Engineers Australia, National Headquarters. Canberra 1987.

### **Geotechnical Involvement During Construction**

During construction, excavation is frequently undertaken which exposes the actual subsurface conditions. For this reason geotechnical consultants should be retained through the construction stage, to identify variations if they are exposed and to conduct additional tests, which may be required, and to deal quickly with geotechnical problems if they arise.

### **Report for Benefit of Client**

The report has been prepared for the benefit of the Client and no other party. PB assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of PB or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own enquiries and obtain independent advice in relation to such matters.

### **Other Limitations**

PB will not be liable to update or revise the report to take into account any events or emergent circumstances or facts occurring or becoming apparent after the date of the report.




## **Attachment A. Ground Model Sketches**




Job TRADE COAST SEWER Design JAW Office PB-BRIS  
VIOLA - PUMP STATION Date \_\_\_\_\_ Job No. 2138110B/1800  
 Checked \_\_\_\_\_ Page No. \_\_\_\_\_  
 Date 31/3/04


SCALE 1:100





RELEVANT INFO.  
BH 27, CPT 21, CPT 6













Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix F

---

### Dynamic Surge Analysis Information





**Parsons  
Brinckerhoff**

12th Floor, IBM Centre  
348 Edward Street  
Brisbane QLD 4000  
GPO Box 2907  
Brisbane QLD 4001  
Australia  
Telephone +61 7 3218 2222  
Facsimile +61 7 3831 4223  
Email brisbane@pb.com.au

Our Reference: 2138110B-LTR043Aic:rmk

ABN 84 797 323 433  
NCSI Certified Quality System ISO 9001

4 August 2004

Mr James Whybrow  
Project Manager — Australia Trade Coast Sewer Project  
Leighton Contractors Pty Limited  
C/- Level 3, 143 Coronation Drive  
MILTON QLD 4064

Dear James

## **Australia Trade Coast Sewer Project Additional Water Hammer Analysis SP298 to SP300 Rising Main**

Further to the Design Meeting held on 28 July 2004, we commissioned sub-consultant Design Detail and Development (Geoff Stone) to complete further water hammer analyses based upon the control philosophy outlined by PB Principal Engineer David Kent.

### **1. Scenario Modelling**

The preference of Brisbane Water (BW) not to have automatic air valves on the SP298 to SP300 rising main has been included in the scenarios modelled.

*provide* Additionally we have included an elevated inlet at RL 2.25 m AHD at SP300 in order to provide static head to ~~five~~ some resistance to fluid momentum upon pump stop. This is required to limit the volume drawn from SP298 after pump stop.

For the elevated inlet at SP300 we propose an air valve pit with a blanked tee mounted on an air valve tee with a 100 ND breather pipe connected to the SP300 wet well (which will be vented through an odour scrubber). (See attached sketch.)

The elevated inlet with venting to atmosphere will ensure that the hydraulic grade line remains at RL 2.25 m AHD at the break pressure pit immediately adjacent to SP300.

We understand that Leighton Contractors will locate the proposed elevated inlet valve pit on the southern side of the existing rising mains so that a directional drill can be constructed down to the inlet works which will reduce the cost of the proposed inlet works. (See attached sketch.)

**Over a Century of  
Engineering Excellence**

Parsons Brinckerhoff Australia Pty Limited ACN 078 004 798 and Parsons Brinckerhoff International (Australia) Pty Limited ACN 006 475 056 trading as Parsons Brinckerhoff ABN 84 797 323 433



2/...

2138110B-LTR043Aic:rmk

Flow banding has been adopted as follows:

- Duty A to 160 L/s RL 0.25
- Duty A to 90 L/s RL -0.18
- Stop Duty B RL -0.38
- Stop Duty A RL -0.98

The scenarios which were modelled were as follows:

- pump stop is normally from 90 L/s;
- pump stop is normally controlled from 160 L/s to 90 L/s;
- single pump trip at 90 L/s, due to loss of power; and
- single pump trip at 160 L/s, due to loss of power.

## 2. Modelling Results

A copy of the "Supplement to the Review of Unsteady State Hydraulic Design, SPS 298 Lytton Road to SPS 300 Serpentine Road" (2 August 2004) is attached as Appendix A.

The extra water hammer analysis may be summarised as follows:

Event	Integrated Volume (cu. m.)	Minimum Volume Available to BWL (cu. m.)
90 L/s Single Pump Trip Due to Loss of Power	1.85	3.3
160 L/s Single Pump Trip Due to Loss of Power	3.75	9.5

Note: 3.6 m diameter pump well has a cross-sectional area of 10.2 m<sup>2</sup>.

Conclusion: The SP298 wet well has sufficient capacity not to empty under normal stop or power failure mode provided the nominated set points are used with VSD control of the pumps.

On the basis of the successful water hammer modelling the following revised settings are recommended:

- Duty A to 160 L/s RL 0.15
- Duty A to 90 L/s RL -0.30
- Stop Duty B RL -0.60
- Stop Duty A RL -1.10

The final pump settings will be optimised during the commissioning of the SP298 pump station. This will allow minimisation of the volume of sewage in the wet well after a normal pumping cycle.

**Over a Century of  
Engineering Excellence**





3/...

2138110B-LTR043Aic:rmk

### 3. Brisbane Water Approval

On the basis of the additional water hammer modelling we now formally seek the approval of Brisbane Water for the proposed rising main arrangement so that the detailed design of SP298 and SP300 can now be finalised.

Should further information be required, please contact the undersigned on 3218 2644 or 0401 148 142.

Yours sincerely

A handwritten signature in black ink, appearing to read 'Ian Cameron'.


**Ian Cameron**

Design Manager

Parsons Brinckerhoff Australia Pty Limited

Encl. Supplement to the Review (2 August 2004)  
Rising Main Sketch

Cc. Andrew Bannink — BW  
John Bower — BW  
Greg Wright — BW











Supplement to the Review  
of  
Unsteady State Hydraulic Design  
  
Australian Trade Coast Sewerage Project  
  
SPS 298 Lytton Road  
to  
SPS 300 Serpentine Road

Commissioned by Parsons Brinkerhoff Australia  
Client : Brisbane Water  
Prepared by Geoffrey D Stone F I Mech E C. Eng; F I E Aust C.P. Eng  
Date 2<sup>nd</sup> August 2004  
Status Revision D1

*Design Detail & Development*      0402 35 2313

## TABLE OF CONTENTS

<b><u>PREAMBLE</u></b>	<b><u>3</u></b>
<b><u>SUMMARY</u></b>	<b><u>3</u></b>
<b><u>REVISIONS TO REPORT</u></b>	<b><u>3</u></b>
<b><u>SOFTWARE USED</u></b>	<b><u>3</u></b>
<b><u>SCENARIOS MODELLED</u></b>	<b><u>4</u></b>
<b><u>SYSTEM MODELLING</u></b>	<b><u>4</u></b>
<b>UNSTEADY STATE RESPONSE PIPELINES AND PUMPS</b>	<b>4</b>
<b>SPS 298 PUMPING STATION</b>	<b>4</b>
<b>SINGLE PUMP TRIP DUE TO LOSS OF POWER FROM 90 LS-1</b>	<b>4</b>
<b>FLOW RATE CHANGE FROM HIGH SPEED TO LOW SPEED</b>	<b>6</b>
<b>SINGLE PUMP TRIP DUE TO LOSS OF POWER FROM 90 LS-1</b>	<b>8</b>
<b>OUTCOMES OF THE MODELLING</b>	<b>10</b>
<b><u>CONCLUSIONS</u></b>	<b><u>11</u></b>

**Design Detail & Development 0402 35 2313****Preamble**

Parsons Brinckerhoff Australia (PBA) have undertaken a design for the Australia Trade Coast Sewerage Project for Brisbane Water. This Supplement covers the unsteady state analysis of the hydraulic design for the SPS 298 Lytton Road PS to SPS 300 Serpentine Road PS where the air valve option has been deleted but the elevated IL at SP300 is retained..

**Summary**

The following key points summarize the supplemental findings of the review of the systems design:-

- The analysis was carried out using the latest version of AFT Impulse
- The pressure transients in the system are within the design rating of the pipeline
- The steady state hydraulics are in general agreement with those used for pump selection however the pump is now speed control to a maximum of 160 Ls-1
- Two speed operation based upon wet well level is the proposed operating strategy
- The results are based upon Hidrostat pump curve modified to represent the desired speed
- The volume of fluid siphoned from the SP298 wet well is within the Capacity of the well
- Column separation doesn't occur in significant volumes

**Revisions to Report**

The following revisions have been undertaken:-

**Revision D1**

- SP300 inlet box was increased to RL 2.25m
- No double air valves are modelled in the line
- Pump stop is normally controlled from 160 Ls-1 to 90 Ls-1
- Pump stop is normally from 90 Ls-1

**Software Used**

The software used to undertake the system unsteady state hydraulics was AFT's Impulse vr 3.0. This software enables single or dual pump modelling using the HQ curve, moment of inertia and other criteria of the selected pumps. Details of the software and its verification are available from [www.aft.com](http://www.aft.com).

**Design Detail & Development 0402 35 2313****Scenarios Modelled**

This models developed were used to determine the following scenarios:-

- Loss of power for all modes of pumping


**System Modelling**



The modelling was undertaken to demonstrate that the 3.6m diameter wet well at SP298 would not be emptied on normal or emergency pump stop. The pump was modelled with a curve for each speed scenario based upon the maximum flow rate of 160 Ls-1 and for the low wet well level where the flow rate was reduced to 90 Ls-1. This replicates the advised form of two speed control using the VSD of the pumps..


**Unsteady State Response Pipelines and Pumps****SPS 298 Pumping Station****Single Pump Trip Due to Loss of Power from 90 Ls-1**

This scenario models the behaviour of the system when the duty pump trips due to loss of power or emergency stop action. The normal stopping under VSD control is considered to be even less of an issue and has not been modelled.

The maximum & minimum surge pressure is 550 kPag positive & -80 kPag respectively for the scenario of a single pump trip.



**Design Detail & Development 0402 35 2313**


**Design Detail & Development 0402 35 2313**



The above curve demonstrates the integrated volumetric flow into the pump upon pump trip. The momentum of the water column in the pipeline results in the volume siphoned reaching a plateau of less than 2m<sup>3</sup>.


**Flow Rate Change from High Speed to Low Speed**

This scenario models the behaviour of the system when the pump is operating at high speed and is changed to low speed using the VSD and flow meter control philosophy. Speed change is effected in 10 seconds.

The maximum & minimum surge pressure is 530 kPag positive & -30 kPag respectively for this scenario.




**Design Detail & Development 0402 35 2313**

**Design Detail & Development 0402 35 2313****Single Pump Trip Due to Loss of Power from 90 Ls-1**



This scenario models the behaviour of the system when a pump is tripped from 160 Ls-1 by electric power outage or emergency stop. Although the selected pump can deliver more than this flow rate, the flow rate is controlled by a controller from a signal from the magflowmeter.


The maximum & minimum surge pressure is predicted as 700 kPag positive & -100 kPag respectively for the scenario of the pump starting with the valve closed at the station valve pit. Examination of the vapour volumes revealed extremely low vapour boundary separation. This explains the low surge levels in this system.





Design Detail & Development      0402 35 2313



**Design Detail & Development 0402 35 2313**

The curve above demonstrates that the fluid volume siphoned from the SP298 wet well is less than the capacity available.

**Outcomes of the Modelling**

The transient pressures are within the design rating of the pipe for all the above scenarios. The design rating of the pipe class selected is 1250 kPa at 20°C. Should the station operate four times an hour the derating factor for a 50 year life would be 0.81 and for a 100 year life 0.74. The maximum derating would thus be to 1012.5 kPa bar for the latter case. Thus the selection complies with the requirements of WSA 01 Polyethylene Pipeline Code.

The check valves selected are suitable for this application and do not require counterweights. The use of counterweights can in some instance magnify a pressure transient in the case of a poorly maintained valve. Should the valve remain open and close swiftly upon reverse velocity of the fluid column, the counter weight increases the acceleration causing a higher valve slam. However it is suggested that the check valve spindle be extended in case devices are to be fitted at a later date.

The wet well at SP298 appears to have sufficient capacity to handle pump stop from all these scenarios.

Negative pressures at the pump discharge may be of concern to the pump manufacturer in terms of seal damage. This may become a maintenance issue over the longer term. The solution would be to install the Ventomat air valves as originally suggested.

***Design Detail & Development      0402 35 2313*****Conclusions**

The following conclusions are drawn from this supplemental review of the system of Lytton Road PS to SPS 300 Serpentine Road PS DN 450 PE100 PN 12.5 pipeline that crosses the Brisbane River: -

- Transient pressures are within the design rating of the pipe material
- Compliance with WSA 01 has been met
- Check valves do not require counterweights
- The use of variable speed drives for the pumps will further reduce any possible fatigue damage of pipeline components or the pumps
- Two speed operation overcomes the concern by Brisbane Water of using air valves on sewage systems.

oooOOOooo



Review  
of  
Unsteady State Hydraulic Design  
Australian Trade Coast Sewerage Project  
SPS 298 Lytton Road  
to  
SPS 300 Serpentine Road

Commissioned by Parsons Brinkerhoff Australia  
Client : Brisbane Water  
Prepared by Geoffrey D Stone F I Mech E C. Eng; F I E Aust C.P. Eng  
Date 22nd June 2004  
Status Revision D



***Design Detail & Development      0402 35 2313***

## **TABLE OF CONTENTS**

<b><u>PREAMBLE</u></b>	<b><u>3</u></b>
<b><u>SUMMARY</u></b>	<b><u>3</u></b>
<b><u>REVISIONS TO REPORT</u></b>	<b><u>3</u></b>
<b><u>SOFTWARE USED</u></b>	<b><u>3</u></b>
<b><u>SCENARIOS MODELLED</u></b>	<b><u>3</u></b>
<b><u>SYSTEM MODELLING</u></b>	<b><u>4</u></b>
<b>UNSTEADY STATE RESPONSE PIPELINES AND PUMPS</b>	<b>5</b>
<b>SPS 298 PUMPING STATION</b>	<b>5</b>
<b>SINGLE PUMP TRIP DUE TO LOSS OF POWER</b>	<b>5</b>
<b>SUDDEN VALVE CLOSURE ALONG THE LENGTH OF THE PIPELINE</b>	<b>9</b>
<b>PUMPS STARTING AGAINST A CLOSED VALVE</b>	<b>10</b>
<b>SINGLE PUMP FAILURE WHILST ANOTHER PUMP IS RUNNING</b>	<b>12</b>
<b>OUTCOMES OF THE MODELLING</b>	<b>13</b>
<b><u>CONCLUSIONS</u></b>	<b><u>13</u></b>

**Design Detail & Development 0402 35 2313****Preamble**

Parsons Brinckerhoff Australia (PBA) have undertaken a design for the Australia Trade Coast Sewerage Project for Brisbane Water. This Report covers the unsteady state analysis of the hydraulic design for the SPS 298 Lytton Road PS to SPS 300 Serpentine Road PS.

**Summary**

The following key points summarize the initial findings of the review of the systems design:-

- The analysis was carried out using the latest version of AFT Impulse
- The pressure transients in the system are within the design rating of the pipeline
- The steady state hydraulics are in general agreement with those used for pump selection
- The results are based upon Hidrostal pump
- The manual air vent at SP298 should be changed

**Revisions to Report**

The following revisions have been undertaken:-

**Revision D**

- SP300 inlet box was added increasing depth to 2.25m
- A DN25 air valve was modelled at SP298 valve pit to replicate the manual valve
- Investigation of larger double air valve at SP298 valve pit

**Software Used**

The software used to undertake the system unsteady state hydraulics was AFT's Impulse vr 3.0. This software enables single or dual pump modeling using the HQ curve, moment of inertia and other criteria of the selected pumps. Details of the software and its verification are available from [www.aft.com](http://www.aft.com).

**Scenarios Modelled**

This models developed were used to determine the following scenarios:-

- Loss of power for all modes of pumping
- Sudden valve closure along the length of the pipeline
- Pumps starting against a closed valve
- Single pump failure whilst another pump is running



## System Modelling

The maximum momentum of the water column arises when pumping from top water level upstream of the pump to bottom water level of the receiving structure. This is the basis of the modelling.

The pump trip is modelled as *stop on inertia with no backwards flow*. Pump moment of inertia (MOI) has been taken from the Hidrostal pump Curve 84-K3229c. The moment of inertia is given as  $0.955 \text{ kg-m}^2$ .

The characteristics of the non-return valves to be employed were not available from the manufacturer Tyco Water. They were modelled as swing check type valve using industry data<sup>1</sup>.

Pipe materials consist of

- DN 300 AS 2280 K12 DICL for the station piping
- DN400 & 450 PE 100 AS 4130 PN20 & PN12.5 for the main pipeline and river crossing respectively.

The properties used in establishing the wavespeed was the instantaneous modulus of PE 100 at 20°C. This is consistent with the engineering principle that a thermoplastic when exposed to rapid load will respond based upon its instantaneous properties.

The level of the inlet to SP300 has been raised to RL2.25 to prevent the the sump at SP298 emptying when the pumps are tripped and air enters the pipeline due to the negative pressure. The models have all been revised to predict the effects of this arrangement.

It was reported that a DN25 manual air valve was located at the SP298 valve pit to allow venting of the line. This was modelled. Further a DN100 air valve was modelled to investigate reducing the likelihood of emptying the station on pump trip.

---

<sup>1</sup> Fluid Transients in Pipeline Systems Prof. ARD Thorley

**Design Detail & Development 0402 35 2313****Unsteady State Response Pipelines and Pumps****SPS 298 Pumping Station**

The modelled pumps for this system are duty/standby configuration based upon a The Hidrosta H08K-M02R-HE5TA-XMSK-NDB6-10 pump for this service. This single stage vertical submersible unit model has a nominal duty of 160 L/s @ 25.6m fitted with a four pole speed motor 70 kW motors. Each pump operates with an efficiency of 77% at 160 L/s in single operation. This pump has a similar moment of inertia of 0.955 kg-m<sup>2</sup>.


In order for the scenario of *pump failure with a second pump continuing to run* to be considered it has been assumed that parallel pumping is a possible operating mode.

No valve or penstock is located at the discharge end of the pipeline (SP300 inlet) however this was modelled in case one is installed in the future or to represent a pipeline blockage.


**Single Pump Trip Due to Loss of Power**

This scenario models the behaviour of the system when the duty pump trips due to loss of power or emergency stop action. The normal stopping under VSD control is considered to be even less of an issue and has not been modelled. This is because the VSD can be characterised for slow stop/start. This will reduce the momentum change in the pipeline and result in lower pressure transients than for a pump trip.


The maximum & minimum surge pressure is 620 kPag positive & -100 kPag respectively for the scenario of a single pump trip.



**Design Detail & Development      0402 35 2313**





The column separation apparent in the model in this scenario is likely to be an artificial transient or it is of such small volume as to not impact on the pipeline as the graph below illustrates.



**Design Detail & Development 0402 35 2313**

The graphs below illustrate the time taken for the water column to come to rest. This duration is to be expected with a long pipeline of PE with near zero static head. This is because there is little friction or head to slow the pipeline fluid velocity and also the DN25 air vent is so small that critical velocity of the air is reached entering the pipeline. It was reported that the air vent is a manual valve and hence could not be operated in the event of a pump trip.

This of course only occurs in the rare case of pump trip due to loss of power or emergency stop activation. In the normal course of events the pumps can be slowed using the VSD. Then the water column would slow in a controlled fashion.





To reduce the water column velocity a DN100 double air valve was modelled at the valve pit. This would allow the ingress of sufficient air so that the SP298 well would not be drained when a pump tripped due to power failure.





**Design Detail & Development      0402 35 2313**

The graph below illustrates that the fluid in the pipe immediately downstream of the pump in line 1 comes to rest in 2 seconds whilst that downstream of the air valve in line 3 continues to travel along the pipe as there is little friction or static head to reduce its momentum. The graph of the air valve volume vs time illustrates that air is being drawn into the main when the pump trips.




*Design Detail & Development      0402 35 2313*

**Sudden Valve Closure along the Length of the Pipeline**


This scenario models the behaviour of the system when a station valve is closed in 10 seconds whilst the pump is operating. The normal stopping under VSD control and valve closing with a stopped pump is considered to be of no consequence for the reasons given in the above scenario.

The maximum & minimum surge pressure is 670 kPag positive & -100 kPag respectively for the scenario of a valve closing at the station in 10 seconds.



**Design Detail & Development      0402 35 2313**


A model was created to demonstrate the effect of a valve or penstock closing at SP300 inlet. The model was evolved to a point where the vlave was closed to 5% open in ten seconds and the balnce in a further 40 seconds in order to limit the pressure transient. The maximum & minimum surge pressure is 1060 kPag positive & 0 kPag respectively.



**Pumps starting against a closed valve**


This scenario models the behaviour of the system when a pump is started against a closed valve. Two scenarios were modelled with one using the station valve and another where a possible valve is installed or there is a blockage in the pipeline. This replicates a future installed valve or a potential blockage of some kind.

The maximum & minimum surge pressure is predicted as 820 kPag positive & -100 kPag respectively for the scenario of the pump starting with the valve closed at the station valve pit.






*Design Detail & Development      0402 35 2313*





The maximum & minimum surge pressure is predicted as 810 kPag positive & -20 kPag respectively for the scenario where a future valve or penstock is closed at the inlet to SP300 when the pump starts. No column separation was apparent in the model in this scenario.



**Design Detail & Development 0402 35 2313****Single Pump Failure Whilst Another Pump is Running**

This scenario models the behaviour of the system when two pumps are in operation and one fails. This operating scenario must be permissible under the normal or emergency control. Some pumping stations are inhibited to prevent some such operations whilst others adopt such practices. The normal stopping under VSD control and valve closing with a stopped pump is considered to be of no consequence.

The maximum & minimum surge pressure is 740 kPag positive & -30 kPag respectively. No column separation was apparent in the model in this scenario.



**Design Detail & Development 0402 35 2313****Outcomes of the Modelling**

The transient pressures are within the design rating of the pipe for all the above scenarios. The design rating of the pipe class selected is 1250 kPa at 20°C. Should the station operate four times an hour the derating factor for a 50 year life would be 0.81 and for a 100 year life 0.74. The maximum derating would thus be to 1012.5 kPa bar for the latter case. Thus the selection complies with the requirements of WSA 01 Polyethylene Pipeline Code.

The check valves selected are suitable for this application and do not require counterweights. The use of counterweights can in some instance magnify a pressure transient in the case of a poorly maintained valve. Should the valve remain open and close swiftly upon reverse velocity of the fluid column, the counter weight increases the acceleration causing a higher valve slam

The manual air vent at SP298 valve pit should be changed to an automatic DN100 double air valve to allow sufficient air to enter the pipeline so as to stop the SP298 well draining due to siphoning action. The Ventomat RGx is suggested for this application.

**Conclusions**

The following conclusions are drawn from this original review of the system analysis of the Lytton Road PS to SPS 300 Serpentine Road PS DN 450 PE100 PN 12.5 pipeline that crosses the Brisbane River: -

- Transient pressures are within the design rating of the pipe material
- Compliance with WSA 01 has been met
- Check valves do not require counterweights
- The use of variable speed drives for the pumps will further reduce any possible fatigue damage of pipeline components or the pumps
- The manual air vent should be changed to a larger automatic double acting air vent.

oooOOOooo









Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix G

---

### SUR Plan and RP Plan





## UR PLAN

ion of part of Lot 719 on SP110610.  
ion 3, Parish of Toombul.  
ity of Stanley.



Scale 1: 500

Drawn: PMW 05/10/2003

Search: 1789

CAD Ref: SUR040313-05

Instructions: J.Bower  
Brisbane Water

## CITY DESIGN TECHNICAL SERVICES

3rd Floor, T.C. Beirne Centre  
315 Brunswick St Mail, 4006.  
J.Dowling. ph.(07)34030489 fax.(07)34033035.

Project / Plan number	Amend
SUR040313-05	A

002/002









Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix H

---

### Control Philosophy



# **SEWAGE PUMP STATION SP 298 LYTTON ROAD LYTTON**

## **REVISED FUNCTIONAL SPECIFICATION**

**Revision: 2**

**Date of Issue: 6 August 2004**

### Document Approval

Signature

Date

Author M. Brand

Design Verifiers

Projects Engineering  
Manager

Project Manager

Team Leader – Projects  
Systems & Information  
Management

Principal Process  
Operations Engineer

### Document History and Status

Issue	Date of Issue		Date		Date		Date		Date
Rev 0	21/6/04	M B	21/6/04						
Rev 1	12/7/04	V B	12/7/04						
Rev 2	3/8/04	I C	3/8/04						

# Contents

<b>DOCUMENT APPROVAL</b>	<b>2</b>
<b>DOCUMENT HISTORY AND STATUS</b>	<b>2</b>
<b>1. INTRODUCTION</b>	<b>4</b>
1.1 SCOPE OF DOCUMENT	4
1.2 ORGANISATIONS INVOLVED	4
1.3 GENERAL DESCRIPTION OF SP298	4
<b>2. FUNCTIONAL REQUIREMENTS</b>	<b>5</b>
2.1 PUMP STATION DUTY	5
2.2 EQUIPMENT INSTALLED	5
2.2.1 Pumps	5
2.2.2 Pump Protection Equipment	5
2.2.3 Starters	5
2.2.4 Flowmeters	5
2.2.5 Level Sensors	5
2.2.6 Pressure Transmitters	6
2.2.7 Actuated Valves	6
2.2.8 Dosing Pumps	7
2.2.9 Activated Carbon Scrubber	7
2.2.10 Emergency Generator	7
2.2.11 Pump Station PLC	7
2.2.12 Telemetry Equipment	7
2.3 PUMP STATION OPERATING STATES	7
2.3.1 Remote State	7
2.3.2 Local State	7
2.4 PUMP START/STOP SEQUENCE	8
2.5 PUMP AVAILABILITY	9
2.5.1 Pump VFD Ready and in Auto Mode	9
2.6 RUNNING PHILOSOPHY	10
2.7 SITE ALARMS	13
2.7.1 Alarm Definition	13
2.7.2 Pump Station Alarms	13
2.7.3 Priority 2 Alarms	16
2.7.4 Alarm Suppression	16
2.8 PLC FUNCTIONALITY	17
2.8.1 PLC Calculations	17
2.8.2 Site Attention Indicator	20
2.8.3 Local Indication Lamp	22
2.8.4 Pump Hours Run	22
<b>3. MITS SCADA SYSTEM – OPERATOR INTERFACE</b>	<b>23</b>
3.1 PLC INPUT/OUTPUT LISTING	23

## ATTACHMENTS:

SP298 Design Calculations  
SP298 Electrical Drawings

## **1. INTRODUCTION**

### **1.1 Scope of Document**

This document outlines the functional requirements for control, monitoring and telemetry at sewage pump station SP298 at Lytton Road Lytton.

### **1.2 Organisations Involved**

The design, construction and commissioning of SP298 were components of Brisbane Water's *Australia Trade Coast Sewer Project*. The project was awarded to Leighton Contractors Pty Ltd (LCPL) in late 2003.

SP298 was designed by Parsons Brinckerhoff — LCPL's design consultant — and was constructed by LCPL in the second half of 2004.

### **1.3 General Description of SP298**

SP298 is a 3.6 m diameter reinforced concrete pump station incorporating two variable speed 68 kW submersible pumps operating in a duty/standby arrangement. SP298 is located on the northwest side of Lytton Road Lytton, approximately 300 m southwest of Freight Street.

SP300 discharges a maximum of 160 L/s of raw sewage through an OD450 PE100 and OD400 PE100 rising main to the inlet structure at SP300 at Serpentine Road Pinkenba, approximately 2.6 km to the northwest. The rising main includes a horizontal directional drilled (HDD) section under the Brisbane River at approximately RL-50mAHD.

## **2. FUNCTIONAL REQUIREMENTS**

### **2.1 Pump Station Duty**

SP298 is required to deliver a maximum of 160 L/s into SP300 at Serpentine Road Pinkenba. The rising main consists of approximately 2700 m of OD450 PN12.5 PE100 pipe installed by "cut and cover" and around 750 m of OD400 PN20 PE100 pipe installed by HDD under the river.

Immediately upstream of SP300 is an elevated valve pit at RL2.25 m AHD on the southern side of the existing rising mains. It has been included in the design to reduce the impact of the momentum associated with pump stop and pump trip events and to prevent the rising main from draining on shutdown.

The pumping station has two duties, 90 L/s and 160 L/s. The duty will be selected depending on water level in the wet well.

System curves, pump performance curves and duty calculations for SP298 are presented in the Attachments.

### **2.2 Equipment Installed**

#### **2.2.1 Pumps**

Two Hidrosta H08K submersible pumps with 68 kW four pole electric motors are installed in the wet well.

#### **2.2.2 Pump Protection Equipment**

Each pump is fitted with moisture probes in the oil chamber and thermistors in the stator windings.

#### **2.2.3 Starters**

Two Danfoss VLT8000 Variable Frequency Drives (VFDs) are installed in the pump station switchboard. VFDs were installed to allow two duty points and for flexibility of operations in the future. The VFDs will also provide soft starting functionality.

#### **2.2.4 Flowmeters**

One direct buried DN450 ABB Magmaster electromagnetic flowmeter is installed in the DN450 PE100 discharge main downstream of the valve chamber. The flowmeter will be used to control the flow set points of 90 L/s and 160 L/s.

#### **2.2.5 Level Sensors**

One Vega hydrostatic level transmitter and one Multitrode level probe are installed in the wet well.




## 2.2.6 Pressure Transmitters

One Vega D84 pressure transmitter is installed on the discharge pipework in the valve chamber.

## 2.2.7 Actuated Valves

Normally flow from Prichard Street Pumping Station (PS085) and Kianawah Road Pumping Station (PS049) will deliver flow to the Lytton Road Pumping Station (PS 298). The incoming rising mains to PS 298 shall be fitted with actuated valves to allow flow from PS085 and PS049 to bypass PS 298 (flows from PS085 will be diverted to the PS049 rising main) or to allow each incoming pipeline to be isolated in the event of a pressure main burst.

Two actuated DN300 Keystone Figure 951 knifegate valves shall be installed at the inlet valve pit. These valves will be located on the rising main from PS 049 (V1) and on the common main to PS298 (V2). The actuated valve will be required to operate during an electrical outage. To ensure reliable operation the valves shall be fitted with a 24 VDC electric actuator connected to the grid/ generator and backed by a battery power supply. A manually operated DN300 Keystone Figure 951 knifegate valve would be installed on the rising main from PS 085 (V3). The sketch below shows the proposed arrangement.



The above valve arrangement will have the following modes of operation:

1. Normal Operation Mode 1 – V1, V2 and V3 Open.  
Allows Flow from PS085 and PS049 to discharge to PS298.
2. Normal Operation Mode 2 – V1 Closed, V2 and V3 Open.  
Allows only flow from PS PS085 to discharge to PS298.
3. Failure Mode 1 – V1 Open, V2 Closed and V3 Open.  
Allows from PS 085 to be diverted to Gibson Island WWTP.
4. Failure Mode 2 – V1 and V2 Open, V3 Closed.  
Isolates PS 085 rising main in the event of the PS085 main failing.
5. Failure Mode 3 – V1 Closed, V2 and V3 Open.  
Isolates PS 049 rising main in the event of the PS049 main failing.

### 2.2.8 Dosing Pumps

Provision was made for two chemical dosing pumps (nominally Alldos 0.09 kW) to be installed adjacent to the dosing slab. Provision was made for VFDs for these pumps to be installed in a dedicated control panel adjacent to the pumps. These will need to be flow paced to allow for the two flow duties.

### 2.2.9 Activated Carbon Scrubber

Provision was made for one activated carbon odour scrubber (nominally RKR Engineering Airclenz) to be installed adjacent to the wet well. Provision was made for the starter and controls for the activated carbon unit to be installed in a dedicated control panel adjacent to the scrubber.

### 2.2.10 Emergency Generator

One 150 kVA diesel powered backup generator is installed on a slab adjacent to the valve chamber. The generator includes its own GE FANUC PLC mounted in a dedicated control panel inside the generator housing.

### 2.2.11 Pump Station PLC

One GE FANUC PLC is installed in the pump station switchboard.

### 2.2.12 Telemetry Equipment

One MITS RTU is installed in the pump station switchboard.

## 2.3 Pump Station Operating States

SP298 has two operating states:

- Remote
- Local

The Local/Remote selector switch dictates the mode of operation. This switch is located in the door of the main switchboard.

### 2.3.1 Remote State

This is the normal operating state. Pump functionality is directed by the PLC based on automatic stop/start control of the wet well level.

### 2.3.2 Local State

In Local mode, no automatic control is performed. The PLC controls the pumps based on the manual initiation of the pumps individual start and stop pushbuttons. Once started in manual, the pumps will run until they are requested to stop manually. The operator or electrician is fully responsible for the consequences of running the station in this mode.

**THE VFD KEYPADS WILL BE DISABLED AFTER COMMISSIONING TO AVOID OPERATION BY UNTRAINED PERSONNEL.**

Electricians with proper training will be able to enable the keypad and allow the pumps to be operational in an emergency situation.

## **2.4 Pump Start/Stop Sequence**

A pump will start if both the following conditions are true:

1. the pump is available for PLC control; and
2. the pump is requested to run.

A pump will stop if either of the following conditions are true:

1. the pump is no longer available for PLC control; or
2. the pump is requested to stop.

Once a start request is accepted by the PLC, the pump is started using the following sequence:

- VFD run/stop relay output shall close;
- a low flow inhibit timer set to 60 seconds inhibits the low flow cut-out (based on the magnetic flowmeter signal) while the pump starts;
- if the magnetic flowmeter has registered a flow of at least 20 L/s after the time delay has expired, then the run/stop relay remains energised; and
- the status indicator lights turns on.

If the pump is unable to match the duty flow with the motor frequency within a set band, then the pump will stop, an alarm will be activated and the standby pump will become the duty pump. (These acceptable frequency bands will be set during commissioning.)

Upon a stop request being reset, the pump is stopped using the following sequence:

- VFD run pump relay output shall open;
- VFD frequency reaches 0 Hz, the drive running light on the panel is de-energised; and
- the status indicator light turns off.

The emergency stop sequence for a pump will be executed in the following manner:

- main switchboard or VFD panel emergency stop pushbutton is pressed;
- the isolating contactor opens;
- VFD run/stop relay is de-energised; and
- run light on VFD panel is de-energised.

## 2.5 Pump Availability

A pump must be available before it can be started. Any one of the following onsite fault conditions will make the pump unavailable:

Fault Condition	Description	Set Criteria	Reset Criteria
Pump Control Power NOT on	Pump or Control Circuit breaker switched to the "OFF" or "Tripped" position	Physical input inactive	Physical input active
Pump Emergency Stop	Pump Emergency Stop pushbutton pressed	Physical input inactive	Physical input active
Pump VFD NOT Ready	VFD faulted due to any of the conditions listed in 2.5.1	Physical input active	Physical input inactive
Pump VFD Not Ready Count Exceeded	More than 3 VFD Not Ready faults in eight hours	Counter > 2	Local or Remote Reset
Pump Contactor fail to operate (open or close)	Any pump contactor fails to operate. Fail to open or fail to close)	Output command $\neq$ Input Feedback for two seconds	Local or Remote Reset

In Remote mode, under normal operating conditions (not surcharge pumping), a pump motor restart request is locked out for six minutes to protect the motor starting equipment from thermal failure. This lockout is bypassed by the remote start command from the MITS SCADA system.

A pump cannot be stopped (except emergency stop) once the wet well level is above surcharge imminent.

The emergency stop button is a latched button. The physical button has to be reset before the emergency stop condition is reset.

Local mode prevents the CRO from controlling the site and the pump unavailable alarm is suppressed in this mode. Critical alarms as surcharge imminent and surcharge occurring are sent back to the CRO regardless of his control status.

### 2.5.1 Pump VFD Ready and in Auto Mode

The local control keypad for the VFD is mounted in the door of the pump compartment. The following control functions are available on the keypad:

"VFD Ready" PLC digital input signal. This signal will be on when the VFD is powered up and the following conditions are not present:

- one of the VFD essential faults has not been detected. The VFD essential faults are:
  - earth fault;
  - switch mode fault;
  - short circuit;
  - auto-optimisation not OK;

- heat sink temperature too high;
- motor phase failure; and
- inverter fault.

If any of these essential faults is detected, the VFD will stop the pump and the “VFD Ready” PLC input signal will be off.

- “VFD Auto Mode selected” this signal will be on , if the drive is selected to Auto on the keypad and is ready for remote control.
- “VFD Running” this signal will be on when the drive is running.
- “VFD Running Speed” PLC analogue input signal will provide 4–20 mA VFD running Hz to the PLC.
- When selected to Auto mode with the pump station mode selector switch in Remote, each VFD speed will be controlled via an analogue output from the PLC. The pump operating speed will be set by the PLC.
- When the VFD is in Auto mode with the pump station mode selector switch in Local, each VFD speed will be controlled via a potentiometer mounted on the pump starter panel part of the main switchboard.

The pumps will be available for PLC control if the “VFD Ready” and “VFD Auto Selected” signals are on.

The pump “VFD Not Ready” fault will be unlatched and the pump will become available for PLC control if any of the following conditions are true:

1. The pump VFD Not Ready fault condition is reset (VFD Ready PLC input signal active) and the local reset pushbutton is pressed.
2. The pump VFD Not Ready fault condition is reset (VFD Ready PLC input signal active) and a reset is issued from the operator workstation.
3. The pump VFD Not Ready reset delay timer times out. This will be indicated by the pump VFD Ready auto reset flag being active.

When the pump VFD faults, the VFD Auto reset timer will start. The VFD Ready delay reset timer is used to allow a preset time to pass before unlatching the fault.

## 2.6 Running Philosophy

The incoming sewage at SP298 is pumped from SP049 at Kianawah Rd Lindum and SP085 at Pritchard St Lytton. A branch was constructed on the SP049 rising main to allow flow into SP298 from the existing SP049, which originally pumped to Gibson Island WWTP. SP049 is still capable of pumping directly to Gibson Island WWTP when the new branch is isolated at the inlet to SP298. An actuated knifegate valve is installed at the end of the branch to allow this diversion to be triggered remotely.

The Kianawah Road branch and Pritchard Street rising main are connected in a valve chamber upstream of SP298 and discharge through a common pipe into the SP298 grit collector maintenance hole (GCMH). From the GCMH, the sewage flows directly into the wet well through a submerged pipe.

SP298 is designed to discharge through its own dedicated rising main to the inlet structure at SP300. A pressure transmitter and flow transmitter are installed in the discharge pipework. Only the flow setpoints will be used to control the station.

During normal operation, SP298 operates in “fill and drain” mode based on the measurement from the hydrostatic level transmitter. The proposed level control philosophy is described below.

Two flow “banded” set points are proposed for 90 L/s and 160 L/s in the lower and upper well respectively.

At the start of an operating cycle, the level in the wet well will be at *Stop Duty A* and the pumps will be off. As sewage enters the station, the level will rise. When the level reaches the *Duty A* to 90 L/s level, the duty pump will start at 90 L/s. Once the pump starts, the level will fall and the pump will stop at the *Stop Duty A* level. The operating volume between *Duty A* to 90 L/s and *Stop Duty A* is sized for a maximum of ten starts per hour.

If the inflow is greater than the maximum pump discharge rate, the level in the wet well will continue to rise after the *Duty A* pump starts. If the level reaches *Duty A* to 160 L/s, the pump will increase in speed to achieve that required flow. If the level reaches *Start Duty B*, the second pump will start to assist the first pump. The *Duty B* pump will cut out when the level is drawn down to the *Stop Duty B* level.

Under normal circumstances, all control functions will be initiated in response to an analogue signal from the hydrostatic level transmitter. The Multitrode level switches will be used to indicate Surcharge Imminent.

In the event of a failure of the hydrostatic level transmitter, all pumps will immediately stop and control of the pump station will be based on the surcharge imminent digital input alarm. When this alarm is received, the *Duty A* pump will start and run for a predefined time (120 seconds).

When the level reaches the surcharge imminent level, as per the physical surcharge imminent electrode, the station will initiate the surcharge pumping mode. In surcharge pumping mode, all starting interlocks, pump inhibits and wet well level duty setpoints are ignored. All available pumps will be commanded to run.

Surcharge pumping mode is active while surcharge pumping conditions are true and for a set period of time (site specific) after the level falls below the surcharge imminent condition. Once surcharge-pumping mode is deactivated, the station will revert to normal level of operation.

The MITS operator can inhibit one or both station pumps. A single pump can be inhibited if it is not operating in the pump curve. This will remove it from the duty cycle allowing the other pumps to operate as duty pumps until the inhibit is removed.


When the whole pump station is inhibited, it is desirable to minimise the volume pumped. This is achieved by utilising the wet well storage capacity to a safe maximum level. The duty start levels are raised to 200 mm below surcharge imminent. At this level, the pumps will run for a minimum of two minutes until the pump lockout time expires. After this period, the pumps will stop at 400 mm below surcharge imminent. While both pumps are inhibited, the wet well high alarm will be suppressed.

SP298 may communicate by telemetry with SP049, SP085 and SP300 through BW's Cullen Avenue Control Centre. This would enable the system to be controlled as a whole, thus minimising the chance of sewage overflows in the event of a breakdown or malfunction. The nature of this system control interconnectivity is to be determined by Brisbane Water.

### Operational Diagram

The following diagram shows the station structure levels and operating levels.

#### Station Levels (NTS)



Note: BW may alter settings during commissioning to provide the best performance for the pump station.

## 2.7 Site Alarms

### 2.7.1 Alarm Definition

When alarms are triggered, the PLC immediately transmits them to the MITS master station. These are unsolicited transmissions and, to preserve radio network capacity, these transmissions are kept to a minimum.

The alarm definitions are:

Priority 1: Immediate action

Priority 2: Action next calendar day

Priority 3: Action next working day

Priority 4: No action required, not an "alarm", log as an event for future reference.

Priority 1 alarms need immediate action and are therefore placed in the PLC trigger queue.

The alarm priority class is shown by colour in the CRO's alarm picture on the MITS. The MITS SCADA allows alarm filtering of alarms.

### 2.7.2 Pump Station Alarms

The following alarms are labelled Pump Station Alarms and cause the PLC to send and immediate alarm to the control room.

MITS SCADA Details		Alarm Description
Plant	Quantity	
Sewage_pumping_station	Local_Remote	Station in Local mode
Sewer_pump	Available	Sewer pump unavailable
PLC	Isagraph_stopped	PLC software stopped
PLC	Isagraph_failed	PLC software faulted
Sewage_pumping_station	Mains_fail	Site Main Power Fails
PLC	Battery	PLC power failure battery
PLC	Mains_fail	PLC power failure (mains)
Wet_well	Level_invalid	Wet well measuring instrument faulted
Wet_well	Surcharge_imminent	Wet well level reaches the surcharge imminent level
Wet_well	Surcharge_occurring	Wet well level reaches the surcharge occurring level
Wet_well	High	Wet well level rises above a high alarm level



MITS SCADA Details		Alarm Description
Plant	Quantity	
PLC	Abnormal_operation	Abnormal operation of PLC – PLC has restarted
Wet_well	Low	Wet well level is low
Sewer_pump	Pump_hours_excessive	Pump run hours are excessive
Sewer_pump	Low_run_hours	Pump station run hours are below normal
Pressure_gauge	High	RM Pressure is high
Pressure_gauge	Low	RM Pressure is low
Pressure_gauge	Invalid	RM Pressure is invalid
Sewer_pump	VFD frequency low	Main burst
Sewer_pump	VFD frequency high	Pump or pipe blockage or excessive pump wear
Sewer_pump	Motor_power_high	Pump motor power high
Sewer_pump	Motor_power_low	Pump motor power low
Sewer_pump	Motor_power_invalid	Pump motor power invalid
Sewer_pump	Motor_current_high	Pump motor current high
Sewer_pump	Motor_current_low	Pump motor current low
Sewer_pump	Motor_current_invalid	Pump motor current invalid
Sewer_pump	VFD_Fault	Pump VFD Faulted, signal provided by VFD Not Ready
Sewer_pump	VFD_count_check	Pump VFD has faulted more than 3 times in 8 hrs period
Sewer_pump	Mains_power	Pump has lost mains power
Sewer_pump	Running	Pump running indication
Sewer_pump	Contactor_Fail_to_Close	Pump contactor fail to close
Sewer_pump	Emergency_stop_fault	Pump emergency stop button is active
Sewer_pump	Moisture_In_Oil Chamber	Pump Oil Chamber - Moisture detected
Attention	Automatic_reset	Site attention indication has automatically reset

The pump performance degradation and pump blockage variables have the following values.

Index	DPBkSP (mAHD)	VSDDSP (Hz)	FlwDSP (L/s)	VSDBSP (Hz)	FlwBSP (L/s)
0		Set in code	Set in code	Set in code	Set in code
1	0	TBA	TBA	TBA	TBA
2	TBA	TBA	TBA	TBA	TBA
3	TBA	TBA	TBA	TBA	TBA

The PID loop variables have the following values.

Index	PidIN	PidSP	PidK	pidKd	PidKi	pidInt	pidDb	pidOUT
0	Set in code	Set in code	TBA	0	TBA	0	0.2	Set in code
1	Set in code	Set in code	TBA	0	TBA	0	0.2	Set in code
2	Set in code	Set in code	TBA	0	TBA	0	0.2	Set in code

#### Pump Performance Degradation (Monitoring Only)

The pump performance degradation alarm flag will be latched if the pump has been running, the VFD speed is valid, the flow rate is valid, the delivery pressure is valid and either of these following alarm conditions becomes active.

- During PID minimum flow control, the VFD speed is above the performance degradation minimum flow rate VFD speed setpoint for that delivery pressure for longer than the time period determined by the performance degradation minimum flow rate VFD speed timer.
- Flow rate less than the performance degradation flow rate setpoint for that delivery pressure and the VFD speed is above the performance degradation flow rate VFD speed setpoint for that delivery pressure for longer than the time period determined by the performance degradation flow rate VFD speed timer.

The alarm flag will be reset when the pump performance degradation conditions no longer exist and either of the following conditions occur:

- local reset (PnLRst) via the pump local reset pushbutton being pressed; and
- remote reset via an operator.

#### 2.7.2.1 Pump Blockage

The pump blockage flag, which inhibits the pump from being available if another pump is available to run, will be latched if the pump station doesn't have a surcharge imminent alarm active, the pump has been running, the VFD speed is valid, the flow rate is valid and either of these following alarm condition becomes active.

While being in PID flow control, the VFD speed is above the upper speed setpoint for the requested duty flow for longer than the time period determined by the pump blockage minimum flow rate VFD speed timer.

The alarm flag will be reset when the pump blockage conditions no longer exist and any of the following conditions occur:

- local reset (PnLRst) via the pump local reset pushbutton being pressed;
- remote reset via an operator; and
- surcharge imminent alarm becomes active.

#### 2.7.2.2 Pump Availability

The pump available flag will only be set when all of the “available” conditions occur and any of the following conditions occur:

- NOT Pump no.n blockage;
- pump no.n blockage and another pump is NOT available to run; and
- pump no.n blockage and surcharge imminent alarm becomes active.

If any of the available conditions are not met then the pump is unavailable for PLC control and will not be able to be run automatically or locally via the local start pushbutton.

### 2.7.3 Priority 2 Alarms

Priority 2 alarms are stored in the PLC buffer and transmitted when the buffer is full or when the MITS master station polls the PLC. The CRO will be notified of these alarms once they are transmitted.

Since these alarms are non-critical, this delay is acceptable.

No priority 2 alarms are used for this site.

### 2.7.4 Alarm Suppression

To avoid consequential alarming that is one fault condition triggering multiple alarms at the MITS SCADA system, alarm suppression is used on secondary alarms.

The main consequential alarm condition is Site Power Fail.


If site power fails, the following secondary alarms are suppressed:

- pump unavailable;
- PLC power fail;
- motor current invalid;
- motor power invalid;
- site pressure invalid; and
- motor speed out of allowable operating bands.

When the station is switched to Local mode, the site is under the control of the on site technician. An alarm is triggered at the SCADA system to indicate the station is in local control. All pump alarms are suppressed as the on site technician has assumed responsibility for the station.

Note: Wet well and PLC alarms are not suppressed.

### Alarm Suppression Tree



### No Suppression

#### Wet well

- ◆ Level invalid
- ◆ Wet well high
- ◆ Surge imminent
- ◆ Surge occurring

#### PLC

- ◆ PLC stopped
- ◆ PLC failed
- ◆ PLC Battery low

## 2.8 PLC Functionality

### 2.8.1 PLC Calculations

The following calculations are performed by the pump station PLC:

1. Wet Well Level Calculations
2. Wet Well Volume
3. Station Inflow
4. Station Volume Pumped
5. Station Surge Duration
6. Station Pressure mAHd

7. Pump Hour Run per day
8. Pump Flow (kL) per day
9. Pump Starts per day
10. Pump kW hours per day

A brief description of the listed items are given below.

#### 2.8.1.1 Wet Well Level Calculations

The onsite wet well level indicator mounted on the switchboard shows well level in percentage (%) of full range. This value is transmitted to control room for ease of comparison with the on site technician.

The operator requires the wet well level in mAHD to be able to do a meaningful comparison between different sites.

The following formulas are used to calculate these values.

$$WWL \text{ (mAHD)} = WWL \text{ (meters)} + WWLZero \text{ Level (mAHD)}$$

$$WWL \text{ (%) } = \frac{[WWL(mAHD) - WWLZero(mAHD)]}{WWLRange(m)}$$

#### 2.8.1.2 Wet Well Volume

The wet well level is calculated using a wet well levels versus volume look up table. The look up table has a maximum of 32 point specification of the non-linear relationship of the wells "Level versus Volume". Volume in wet well is an interpolation of the well versus volume look up table values.

		Water Height (mAHD)	Stored Volume (m³)	Remaining Storage Capacity [m³]	Comments	% Level	% Volume
1	Wet Well Low	-1.31	0.0	32.5	BWL	0%	0%
2	Incoming Sewer	-1.31	0.0	32.5		0%	0%
3	Stop Duty A	-1.10	2.1	30.4		7%	7%
4	Stop Duty B	-0.60	7.2	25.3		22%	22%
5	Duty A to 90 L/s	-0.30	10.3	22.2		32%	32%
6	Duty A to 160 L/s	0.15	14.8	17.7		45%	45%
7	Start Duty B	0.40	17.4	15.1		53%	53%

		Water Height (mAHD)	Stored Volume (m³)	Remaining Storage Capacity [m³]	Comments	% Level	% Volume
8	High Level Alarm	0.65	19.9	12.6	TWL	61%	61%
9	Station Inhibited Stop	1.19	25.4	7.1		78%	78%
10	Station Inhibited Start	1.39	27.4	5.1		84%	84%
11	Surcharge Imminent Alarm	1.59	29.5	3.0		90%	90%
12	Surcharge Occurring Alarm	1.87	32.3	0.2		99%	99%
13	Overflow Level	1.89	32.5	0.0		100%	100%

### 2.8.1.3 Total Inflow

The total volume pumped in kilolitres since the start of the year is updated in two seconds increment calculated by integrating the inflow, if the wet well level and flow are valid, using the following calculation algorithm:

$$\text{Total Inflow} = (\text{Inflow} \times 2) / 1000 + \text{Total Inflow}$$

The Inflow rate is the change in volume plus the volume pumped out of the well and is updated in two second increments calculated, if the wet well level and flow are valid, using the following calculation algorithm.

$$\text{Inflow} = ((\text{Volume Now} - \text{Volume Old}) + (\text{Flow} \times 2)) / 2$$

Volume now = Current wet well level volume

Volume old = Previous (2 seconds ago) wet well level volume

Flow = Flow in engineering units

The wet well volume is calculated, if the wet well level is valid, using the wet well level as a reference and interpolation of a level vs. volume vs. surcharge flow lookup table.

### 2.8.1.4 Total Volume Pumped

The total volume pumped in Kilolitres since the start of the year is updated in two second increments calculated by integrating the inflow if the wet well level and flow are valid.

### 2.8.1.5 Station Surge Duration

While the surcharge occurring alarm is active, a timer is accumulated to measure the duration of the surcharge event. This figure is stored until a new surcharge occurring alarm is triggered, at which time the timer is reset to zero.

### 2.8.1.6 Station Pressure (mAHD)

The pressure probe measures the pressure in kPA. This allows the CRO to compare different sewerage sites. The pressure, in mAHD, is calculated and sent back to the MITS SCADA system.

$$\text{Pressure (mAHD)} = \text{Pressure} \frac{(kPA)}{k} + \text{Pressure Elevation (mAHD)}$$

$$k = 9.803 \quad (\text{Pressure constant to convert from kPA to metres})$$

$$\text{Pressure Elevation} = \text{Site Specific Pressure Elevation of Pressure Gauge}$$

### 2.8.1.7 Pump Hrs Run/day

The VFD of each pump has a Modbus communication card connected to the PLC.

This card provides the PLC with information regarding Current, Speed, kW hours per day and Hours run per day.

### 2.8.1.8 Pump kL/day

The station magnetic flowmeter will provide flow readings via an analogue 4–20 mA signal connected to the PLC.

### 2.8.1.9 Pump Starts/day

The number for starts per day counter is incremented every time a pump starts. This counter is reset at midnight.

### 2.8.1.10 Pump kW hrs/day

The VFD of each pump has a Modbus communication card connected to the PLC.

This card provides the PLC with information regarding Current, Speed, kW hours per day and Hours run per day.

## 2.8.2 Site Attention Indicator

The operator will be able to initiate and cancel the site attention indicator. When a site attention indication is generated, officers on site will be required to acknowledge the attention indicator and then contact the operator.

The site attention indicator digital output is latched by an operator generating a site attention indicator flag.

The output is unlatched if any of the following occurs:

- site attention indicator reset by the operator;
- site attention indicator reset pushbutton digital input being pressed; and
- site attention alarm timer expires.

The site attention alarm timer is enabled by the site attention alarm indicator digital output.

The site attention alarm flag is latched if the site attention alarm expires. The alarm is unlatched when the next site attention indicator output is set.



### 2.8.3 Local Indication Lamp

The local indication lamp output displays the status of the pump.

**Lamp Off** Pump stopped but available

**Lamp On** Pump running

**Lamp Flashing** Pump Fault

### 2.8.4 Pump Hours Run

An hours run counter shall be kept for all pumps in the PLC.

A cyclometer type hours run meter has also been mounted on the front door of each pump starter Panel.

An electronic hours run meter also exists in the VFD for the Pumps, these totalise the pump hours run time during its operation.

### 3. MITS SCADA SYSTEM – OPERATOR INTERFACE

The SCADA Screen shall follow the format and standards of the existing Screens.

#### Live points from PLC fed back to picture

- Wet well level in metres AHD and % full.
- Pump duty A start level (in metres AHD and % full), pump duty A stop level, and wet well high level
- Status of each pump (available, running)
- Delivery pressure in metres AHD
- Delivery Flow
- Site power status
- Local/ Remote control status
- Station inflow (when pumps are not running)
- Wet well volume
- Time (in minutes) to surcharge (when pumps are unavailable)

#### MITS database points in the picture

The Inlet level (metres AHD), Overflow Control Level (metres AHD) and the Site Level (metres AHD) are stored in the MITS database and not in the PLC. These values are displayed in the main station picture.

#### 3.1 PLC Input/Output Listing

Refer to electrical drawings.





## **ATTACHMENTS**



Australia Trade Coast Sewer Project  
Contract No. BW30137-02.03  
Revised Developed Design Report  
Separable Portion No. 2  
Lytton Road Pump Station SP298

## Appendix I

---

### Cardno MBK Structural Report

## Lytton Road Pump Station Design Report

### 1.0 Introduction

Cardno MBK were responsible for the structural design of the Lytton Road Pump Station, Number SP298.

The structures comprising the pump station include the wet well, valve pit, grit collector manhole, ferric chloride dosing area slab, odour scrubber pad, transformer base, switchboard base, generator pad, pig launcher pit and unlet valve pit.

### 2.0 Geotechnical Assessment

The pump station is located in the weak recent sediments of the lower Brisbane River and understating the difficult foundation conditions was critical to developing a design for a pump station that would have adequate structural performance.

#### 2.1 Available Geotechnical Information

The geotechnical conditions at the sites of the above two pump stations, are illustrated by the following materials, supplied to Cardno MBK by Parsons Brinckerhoff:

Borehole 2, Project No. CD/S3-G1/0185661 dated 31 January 2001  
 Borehole 51, Project No. CD/S3-G1/0185661 dated 14 May 2001.  
 Borehole 07, Project No. CD/T6-G1/0389629 dated 29 November 2002.  
 Brisbane City Council, City Design, Geotechnical & Environmental Engineering.

*BH2 is adjacent to the proposed pump station.*

Supplementary Geotechnical Data Report, Australia Trade Coast Sewerage Project, Lytton Road to Brisbane River, Lytton. 7 November 2003.  
 Brisbane City Council, City Design, Geotechnical & Environmental Engineering.

*This report included BH27 that is adjacent to the proposed pump station.*

The location of the pump station is shown on Drawing No. PD003

#### 2.2 Assessment by Parsons Brinckerhoff

Geotechnical engineers from Parsons Brinckerhoff initially reviewed the available geotechnical information. This review confirmed the weak nature of the underlying soils and showed that settlements were likely under any additional loading. It was determined that the additional allowable bearing pressure should be limited to 15 kPa at a depth below RL-6.8m to limit settlement to 25-30 mm.

### 2.3 Assessment by Coffey Geosciences

A further assessment of the site was undertaken by Coffey Geosciences to indicate the likely settlements of the site under the additional loading to be applied to the site by the construction of the pump station.

A total settlement of 80 mm is predicted after 50 years for an applied loading of 10 kPa, with a possibility of 33% that this settlement will be exceeded by more than 10%.

## 3.0 Design Construction Requirements

### 3.1 Settlement

It was realised that settlement of the pump station structures was inevitable as the minimum depth of fill applied to the site for the construction of the required pavements would apply significant loading and result in consolidation of the underlying soil. As a result, design was directed towards the design of structures with uniform foundation bearing pressures to ensure that structures would settle uniformly, rather than tilting. The performance of the pump station would not be affected by uniform settlement provided sufficient flexibility was allowed in connecting pipework to allow for differential movement between adjacent structures. Similarly, any pipelines leading to or from the pump station would be not affected by the consolidation as the settlement bowl would extent out from the pump station due to the depth of compressible material.

### 3.2 Construction Issues

The tender method of construction for the pump station was developed by Coffey Geosciences Pty Ltd (Reference facsimile dated 16 June 2003 to Parsons Brinckerhoff). This method comprised the use of an open excavation above the water table and a steel sheet pile supported excavation for the structures below the water table.

Leighton Contractors developed an alternative method of construction for the pump station that eliminated the requirement for steel sheet piling. This alternative method recognised the strength of the near surface soils and the ability for open excavations to remain stable for a limited period of hours. The excavation would be made and stabilised with a rapidly placed internal lining of mass concrete.

The near surface soils have been observed to have a low permeability, indicating that ground water seeping into the open excavations will be unlikely to be a major issue and can be readily managed using small drainage sumps and dewatering pumps during the work.

### 3.3 Design Issues

There are two design cases for the in-ground pump stations:

- Provision of sufficient mass in the structure to overcome buoyancy forces under high water table conditions. It is considered that the design should allow for the water table to be located at the ground surface. The weak



soil conditions also indicate that no allowance should be made for friction on the surrounding soil assisting to hold down the structures.

- Limiting the additional bearing pressure to the underlying soils during dry conditions when the ground water level is low.

In both cases, the centre of buoyancy and the centre of mass should correspond to limit tilting.

## 4.0 Design Outcomes

### 4.1 General Arrangement

The design process considered several arrangements of the valve pit, pump well and grit collector manhole to develop a layout acceptable to Brisbane Water that would address the geotechnical issues of the site.

The design development arrangements considered were:

- A standard arrangement of valve pit and wet well combined in a single structure was considered. It was found that uniform foundation bearing pressures could not be achieved to ensure uniform settlement. The use of fly ash as backfill to the structures to control settlement was considered but was not viable due to the overall settlement of the pump station.
- The use of separate valve pit and wet well structures was considered as each structure would have uniform foundation bearing pressures and hence would settle uniformly. The use of extended foundation slabs to limit non-uniform settlement was considered. Brisbane Water rejected this arrangement.
- It was found that an acceptable bearing pressure distribution could be obtained by combining the valve pit, wet well and grit collector manhole into a single structure as the valve pit would balance the grit collector manhole opposite from the valve pit.

The final solution comprises the valve pit and grit collector balancing each other on opposite sides of the wet well. The grit collector manhole is attached to the wet well by twin reinforced concrete walls.

It was preferable to locate the grit collector manhole adjacent to the pump well to minimise the requirements for the structural members joining the wet well and grit collector manhole. Brisbane Water required the grit collector to be located further from the wet well and this resulted in a significant increase in the size of the connecting members.

The other structures, including the ferric chloride dosing area slab, odour scrubber pad, transformer base, generator slab, pig launcher pit and inlet valve pit were designed with uniform foundation bearing pressures. The majority of these structures were sized to limit the maximum additional bearing pressure applied to the subgrade.

## 4.2 Structural Details

All structures were detailed in reinforced concrete. All significant structures were founded on a compacted clean sand-bedding layer placed on the soft subsoils on completion of excavation to provide a sound-bearing surface. Blinding concrete was specified to provide a firm surface for construction of the structures.

Sand was also specified to be used for the backfilling of excavations as this material can be readily placed and compacted using light equipment.

A jointed reinforced concrete pavement was designed for the access roadway to the pump station to provide a stable base for maintenance vehicle parked at the pump station. The pavement consists of a 200 mm concrete slab and 200 mm sub-base of CBR 25 material overlying the natural subgrade or construction fill.

The foundation for the substation comprises a ground slab at depth supporting a standard Energex unculvert precast transformer base and substation plinth.

## 4.3 Corrosion

The pump station is located in recent alluvium identified as having significant potential acid sulphate soil conditions and groundwater very aggressive towards concrete structures. The concrete structures should be protected against groundwater attack.

However, the general soil permeability is low and little groundwater movement is expected once equilibrium conditions develop following the completion of construction. An appropriate treatment to protect the concrete structures against attack include a double layer of polyethylene sheeting either laid under the structures prior to the pouring of concrete and placed on completed concrete surfaces prior to backfilling. This protection should extend under all foundations and walls located below RL 2.2 m.

An exposure classification of B2 is considered appropriate for concrete protected against the corrosive groundwater as described above.






## BRISBANE STRUCTURES CALCULATION COVER SHEET

<b>PROJECT:</b>	AUSTRALIA TRADE COAST SEWER PROJECT
<b>PROJECT NUMBER:</b>	5219/02-3
<b>DATE:</b>	15-7-4

LYTTON RD PUMP STATION

ACTIVITY	SHT. No.	DESIGN	DATE	CHECKED	DATE
Design of pump well structure	1	AdeC	1-5-4	MAP	14-7-4
Connection to grit Collector	1	MAP	28-6-4	MAP	14-7-4
Review for Gravelled Pump Well /					
Grit Collector Springs	1	MAP	14-7-4	MAP	15-7-4
Review Aboult Drive System	1	MAP	13-5-1	MAP	14-7-4
Rig Launcher	1	MAP	26-6-4	MAP	14-7-4

PROJECT	Trade Coast	PROJECT NO.	7591/02
	Lytton Road P/S	Designed	
		Date	Sheet 1 of



$I = 1.9 \text{ E}12$	$3.0 \text{ E}13$	$1.7 \text{ E}12$	$3.0 \text{ E}12$
$b = 3900$	$3900$	$5000$	$2700$
$d = 1800$	$4500$	$1500$	$2400$

→ equivalent rectangular sections with same bearing area.

<b>PROJECT</b>	<b>PROJECT NO.</b> 7591/2 <b>Designed</b> _____ <b>Date</b> _____ <b>Sheet</b> 2 of _____
----------------	---

Valve pit

Walls  $(3.95 + \frac{4.25}{2} \times 2) \times 0.25 \times 24 = 75 \text{ kN}$   
 $\downarrow$  24 kN      11.9 kN/m  
 $\swarrow$  8.5m  
 $\hookrightarrow$  6 kN/m for 1-28

Slab

$0.3 \times 4.2 \times 24 = 30 \text{ kN/m} \quad (1-10) \quad 90$   
 $1.25^2 \times 0.3 \times 24 = 12 \text{ kN} \quad 12$   
 $\hline 102$

Total = 177 kN

Pump well

Wall  $3.9 \times \pi \times 4.8 \times 0.3 \times 24 = 423 \text{ kN}$

Slab  $\frac{4.8^2 \times \pi}{4} \times 0.45 \times 24 = 200 \text{ kN}$   
 $\frac{4.2}{4} \quad 0.6$

Lid  $4.2^2 \times \frac{\pi}{4} \times 0.35 \times 24 - 1.35 \times 2.6 \times 0.35 \times 24 = 118 \text{ kN}$   
 $\frac{25 \text{ kN/m}}{4}$

Total  $\hline 742$

Switch board

Walls  $0.25 \times 32 \times 24 \times 2 = 19.2 \text{ kN/m} \times 2.75 = 53 \text{ kN}$

Slab  $4.2 \times \frac{0.25^2}{0.35} \times 24 = 25.2 \times 2.3 = 58.1 \text{ kN}$   
 $\frac{35.2}{0.35}$

Total  $\hline 111 \text{ kN}$   
 134

Grit collector

Wall  $\pi \times 2.55 \times 0.15 \times 24 = 28$

Slab  $\pi \times \frac{2.9^2}{4} \times 0.25 \times 24 = 34$   
 $\frac{7.4}{4}$

Lid  $2.9^2 \times 0.35 \times 24 = 61 \text{ kN}$   
 $\frac{123}{112}$

PROJECT

PROJECT NO. ....

Designed .....

Date .....

Sheet 3 of .....

Stability check

Total dead load

$$G = 177 + 742 + 134 + 123 = 1176$$

Water pressure (Taking w.T. at natural G.L.)

$$P = 4.2^2 \times \frac{\pi}{4} \times 38 = 526$$

$$+ 4.2 \times 2.5 \times 10 = 105$$

$$+ \pi \times \frac{2.7^2}{4} \times 15 = 86$$

$$= 717$$

$$0.9 G = 1058$$

$$1.2 P = 860 < 0.9 G.$$

∴ uplift stability is satisfactory.

<b>PROJECT</b>	<b>PROJECT NO.</b> ..... <b>Designed</b> ..... <b>Date</b> ..... <b>Sheet 4 of</b> .....
----------------	--

Loading input for BPT

Elements 1 - 10      36 kN/m

Elements 11 - ~~15~~ 15

$$\frac{70.3 + 6}{3.9} = 186 \text{ kN/m}$$

Elements ~~16~~ 16 - 23      = 180

Elements 24 - 33      46

Elements 33 - 41      46

$$\text{Total} = 36 \times 3 + 186 \times 5 + 180 \times 8 + 46 \times 18$$

= 1067      close enough.

Use 2 methods of analysis and design for the worst case

1) Elastic half space


$$E_s = 15000$$

$$\nu = 0.25$$

2) Winkler  $fd^4$

$$k_s = 1000$$

5




Elastic half spur  
 $E_s = 15000$






6




Elastic half space  
 $E = 15000$

7




Elastic half span  
 $E = 15000$

8



Elastic half space  
 $E_s = 15000$


9



Winkler  $f_{d^h}$

$$k_s = 1000$$


10



Winkler  $fd^4$

$k_s = 1000$

1)



Elastic ~~half~~ <sup>wrinkle</sup> span for  
 $R_s = \frac{15000}{1000} = 15$

PROJECT

PROJECT NO. ....

Designed .....

Date .....

Sheet .....

of .....

Valve pit wall to  $M_s = 550$

$$M^* = 550 \times 1.5 = 825$$

for each wall

$$M^* = 413$$

$$\frac{M}{b d^2} = 0.34 \text{ very small}$$

$$A_s = \frac{412 \times 10^6}{0.8 \times 500 \times 0.7 \times 2400}$$

$$= 613 \text{ mm}^2$$

4N16 Rf T&B.

shear forces to be transferred  
at CTS

$$= 270 \times \frac{2}{2} = 270 \text{ kN ult}$$

$$\text{shear stress} = 0.5 \text{ MPa OK.}$$



PROJECT

PROJECT NO. ....

Designed .....

Date .....

Sheet .....

of .....

Valve pit bottom slab

3m x 4m

benign pressure = 80 kPa (say)  
(Ref BPT Es=15k  
analysis)

$$q/b = 1.3$$

$$G_b = \beta \cdot q \frac{b^2}{x^2} = 0.45 \times 80 \times \frac{3^2}{0.35^2}$$

$$M_b = 0.45 \times 80 \times \frac{3.0^2}{0.35^2} \times \frac{1}{6} \times 0.35^2$$

$$= 0.075 \times 80 \times 3^2 = 54 \text{ kNm/m}$$

Provide


N16 - 150 top (so cover)


$$M_{\text{long span}} = 0.056 \times 80 \times 3^2 = 40 \text{ kNm/m}$$

N16 - 150 ~~top~~ Top

Provide

N16 - 150 b/w





### Calculation of service stress in steel bars and Crack width estimation

Cover to links,  $c = 50$  mm  
 Overall depth,  $h = 300$  mm =  $a'$   
 Main bar size = 16 mm  
 Tension rf. ratio  $\rho = 0.00593$   
 $f_{cu} = 32$   $f_y = 500$   
 Distance between bars,  $s = 150$  mm  
 Stirrup (or lower rf. ) size = 16 mm  
 Reinforcement available =  $A_s = 1340$   $A_s' = 0$   
 Compression rf. ratio  $\rho' = 0$   
 $E_c(\text{instant}) = 26.4$  kN/mm<sup>2</sup>

Service Moment,  $M_s = 40.0$  Balancing Moment,  $M_p = 0$

Axial tensile stress  $= T / A = 0.00$   
 Bonded (+ve) ps strands area,  $A_{ps} = 0$   
 Strain due to axial tension,  $\epsilon_t = 0.0000$   
 Depth of p/s steel,  $d_p = 0$

Number of tensile stress layers = 1

M	bf	d	d'	$\alpha_a$	x/d	z/d	$f_s$	$\epsilon_s$	$\epsilon_m$
40.0	1000	226	74	15.15	0.34	0.89	149	0.0011	0.0007

At the soffit of the member,  $a = 97$

Design surface crack width =  $0.240$  mm  $= \epsilon_m / (1 + (2(a_{cr} - C_{min}) / (h - x)))$

**Calculation of service stress in steel bars and Crack width estimation**

Cover to links,  $c = 50 \text{ mm}$       Distance between bars,  $s = 150 \text{ mm}$   
 Overall depth,  $h = 300 \text{ mm} = a'$       Stirrup (or lower rf. ) size = 0 mm  
 Main bar size = 16 mm      Reinforcement available =  $\frac{A_s}{A_s'} = 0$   
 Tension rf. ratio  $\rho = 0.00554$       Compression rf. ratio  $\rho' = 0$   
 $f_{cu} = 32$        $f_y = 500$        $E_c(\text{instant}) = 26.4 \text{ kN/mm}^2$

Service Moment,  $M_s = 54.0$       Balancing Moment,  $M_p = 0$

Axial tensile stress  $= T / A = 0.00$       Strain due to axial tension,  $\epsilon_t = 0.0000$

Bonded (+ve) ps strands area,  $A_{ps} = 0$       Depth of p/s steel,  $d_p = 0$

Number of tensile stress layers = 1

M	bf	d	d'	$\alpha$	$x/d$	$z/d$	$f_s$	$\epsilon_s$	$\epsilon_m$
54.0	1000	242	58	15.15	0.33	0.89	187	0.0013	0.0009

At the soffit of the member,  $a = 87$

Design surface crack width =  $0.264 \text{ mm} = \epsilon_m / (1 + (2(a_{cr} - C_{min}) / (h - x)))$

**Calculation of service stress in steel bars and Crack width estimation**

Cover to links,  $c_{min} = 50 \text{ mm}$       Distance between bars,  $s = 150 \text{ mm}$   
 Overall depth,  $h = 250 \text{ mm} = a'$       Stirrup (or lower rf. ) size = 0 mm  
 Main bar size = 12 mm      Reinforcement available =  $\begin{matrix} A_s & A_s' \\ 754 & 0 \end{matrix}$   
 Tension rf. ratio  $\rho = 0.00389$       Compression rf. ratio  $\rho' = 0$   
 $f_{cu} = 32$        $f_y = 500$        $E_c(\text{instant}) = 26.4 \text{ kN/mm}^2$

Service Moment,  $M_s = 20.0$       Balancing Moment,  $M_p = 0$   
 Axial tensile stress  $= T / A = 0.00$       Strain due to axial tension,  $\epsilon_t = 0.0000$   
 Bonded (+ve) ps strands area,  $A_{ps} = 0$       Depth of p/s steel,  $d_p = 0$

Number of tensile stress layers = 1

M	b <sub>f</sub>	d	d'	$\alpha_e$	x/d	z/d	$f_s$	$\epsilon_s$	$\epsilon_m$
20.0	1000	194	56	15.15	0.29	0.90	151	0.0011	0.0005

At the soffit of the member,  $a = 88$

Design surface crack width =  $0.131 \text{ mm} = \epsilon_m / (1 + (2(a_{cr} - C_{min}) / (h - x)))$

PROJECT

PROJECT NO.

Designed

Date

Sheet of

Design of Link beams and SW board slabs

walls

$M_{max} = 400 \text{ kNm}$ 

service

Mult

$= 1000 \text{ kNm}$ 

say

$b = 500$   
 $\phi = 2000$   
 $A_s = 1600 \text{ (8 N16)}$

slab

$M = 25 \times 1.25^2 = 20$   

provide N12 - 200 T & B b/w

200

N12-200 T & B

4N16

N12-200 T & B

N12-200

250

N12-200 E/F

100

2N16

2N16

4N16

PROJECT

PROJECT NO. ....

Designed .....

Date .....

Sheet .....

of .....

Top slabs for Grit collector

2.6  $\phi$  .

$$M = 25 \times \frac{2.6^2}{16}$$

$$= 10.5$$

nominal of .

Provide N12-200 b/w

Base of Pumpwell

4m  $\phi$ 

Circular Plate .

Pressure = 100 kPa (say)


$$\text{ie } \frac{1}{4} \times 4.2^2 \times 100 = 1385$$

Can take  
total load .

$$M = 100 \times 4.0^2 \times \frac{1}{4} \times \frac{(3+0.2)}{16}$$

$$= 80$$

Provide N16-200 b/w T & B .



PROJECT

PROJECT NO. ....

Designed .....

Date .....


Sheet .. of ..

Bot Slab for gnt collector.

$$M = 80 \times \frac{2.7^2}{64} \times 3.2 = 29$$

N16-200 T & B OK.

$$f_s = 142 \quad c/w = 0.176 \text{ max.}$$



Top Slab for pump well

$$M = 25 \times \frac{4.0^2}{20} \text{ without openings} = 20$$

From SLABS analysis

$$M_{ut} = 23 \text{ (generally)}$$

with

$$M = 155 \text{ as highest in a 200 wide strip}$$

for the strip


$$\frac{m}{b \cdot d^2} = 4.2$$

$$A_s = 900$$

$$M = 76$$

(3N20 additional)






add 3N20 B

2 N16  
Trimmer  
bars  
T&B (1.5m long)

LAYOUT PLAN

1:25



**SLABS 3.00, Analysis and Design of Reinforced Concrete Slabs**

Company: Cardno MBK


File: c:\slabs\data\4.5diaslab .dat, 28/05/2004, 10:14

Job:

Project:

Location:

Client:



Bending Mx

Bending Mx [kNm/m]
min:
-64.28
-34.86
-5.44
23.98
53.40
max:
82.82

**SLABS 3.00, Analysis and Design of Reinforced Concrete Slabs**

Company: Cardno MBK


File: c:\slabs\data\4.5diaslab.dal, 28/05/2004, 10:16

Job:

Project:

Location:


Client:

**Bending My**

<b>Bending My</b>	
<b>[kNm/m]</b>	
<b>min:</b>	<b>-57.99</b>
	<b>-15.22</b>
	<b>27.66</b>
	<b>70.32</b>
<b>max:</b>	<b>113.09</b>
	<b>158.86</b>



PROJECT	Lytton Road PS	PROJECT NO.	7519/02-3
	Connection to pit Collector	Designed	
		Date	28-6-4



$M_A =$	top slab	$2.9 \times 2.9 \times .35 \times 25 \times 3.9$	287
	interlock slab	$2.5 \times 4.2 \times .35 \times 25 \times 1.25$	115
	pit collector wall	$(2.3^2 - 1.8^2) \frac{\pi}{4} \times 2.8 \times 25 \times 3.9$	439
	" " floor	$2.3^2 \frac{\pi}{4} \times .3 \times 25 \times 3.9$	122
	" " contents	$1.8^2 \frac{\pi}{4} \times 2.8 \times 10 \times 3.9$	278
	interlock (3t)	$3 \times 9.81 \times 1.35$	40
	walls	$.25 \times .95 \times 2 \times 3.15 \times 1.55 \times 25$	58
			<u>1339</u>

Roof load	top slab	$2.9 \times 2.9 \times 3.9 \times 5$	164
	interlock slab	$2.5 \times 4.2 \times 1.25 \times 5$	66
			<u>230</u>

$$\therefore M_U = 1339 \times 1.25 + 230 \times 1.5 = 2019$$


PROJECT

PROJECT NO. ....

Designed .....

Date .....

Sheet 2 of



$$f'_c = 40 \text{ MPa}$$

$$\frac{M_u}{bd^2} = \frac{2019 \times 10^6}{500 \times 1000^2}$$

$$= 4.038$$

$$\therefore \frac{A_s}{bd} = 0.0137$$

$$A_s = 0.0137 \times 500 \times 1000 = 6850 \text{ mm}^2$$

N24 - 452

 $\therefore 15 - N24$  $\therefore 11 - N28$ 

N28 - 615



assume that ground supports will ~~also~~ always carry 50% load

$$\therefore \text{max } M_u = 1010 \text{ kNm}$$

$$\therefore \frac{M_u}{bd^2} = 2.019$$


$$\therefore \frac{A_s}{bd} = 0.0067$$

$$A_s = 3350 = 8 N24 / 6 N28$$



PROJECT	PROJECT NO. ....
	Designed .....
	Date ..... Sheet <u>3</u> of .....

adps 8 N 24 T v B



**ULTIMATE SLABS**

D	300 mm
cover	50 mm
cross reo dia	0 mm
main dia	16 mm
main reo spacing	200 mm
fsy	400 Mpa
fc	40 MPa
d	242 mm

Area steel	1005 mm/m
------------	-----------

---

p	0.0042
---	--------

q	0.0415
---	--------

phi	0.8
-----	-----


Ku	1.30
----	------

Mu	75.9 nNm/m
----	------------



PROJECT	Lytton Rd PS	PROJECT NO.	7519/02-3
	Link Wet Well - Jib Collector	Designed	MP
		Date	14-7-0
		Sheet	1 of

Spacing increased by Brisbane Water



$$\sum M_A = -179 \times 3.57 + 217 \times 2.12 + 128 \times 7.55 - F_B \times 7.55$$

$$\therefore F_B = 104.3 \quad \Rightarrow 37.2 \text{ kN/m}$$

$$\therefore F_A = \frac{522.7}{739.7} \quad \Rightarrow \frac{124.5}{176} \text{ kN/m}$$



PROJECT

PROJECT NO.


7519/2-3

Designed

Date

Sheet 2 of

Sewer Collector Manhole


 $4.43$   
 $2.70$ 

$$= \left[ \frac{(2.3^2 - 1.8^2) \pi}{4} \cdot 2.75 + \frac{2.3^2 \pi}{4} \cdot 65 \right] 25$$

$$= 178 \text{ kN}$$

$$+ .5 \times 3.4 \times 2.3 \times 25$$

$$- .5 \times 2.75 \times 1.8 \times 25$$

$$= 178 + 98 - 62$$

$$= 214 \text{ kN}$$

$$\text{uplift} = 2.3^2 \times \frac{\pi}{4} \times 1.64 \times 9.81$$

$$+ 2.3 \times .5 \times 1.64 \times 9.81$$

$$= 67 + 19$$

$$= 86 \text{ kN}$$

$$\text{slab} \left( 4.2 \times .35 \times 4.05 + 2 \times .25 \times 1.35 \times 4.05 \right) 25$$

$$= 217 \text{ kN}$$

3

## LYTTON ROAD PUMP STATION GEOMETRICAL DESIGN

No Footing allowed

Ground water 1m below ground level

Pump well diameter	3.60 m
Pump well wall thickness	0.30 m
Valve pit length	2.65 m
Valve pit width	3.70 m
Valve pit wall thickness	0.25 m
Dividing wall thickness	0.30 m
Switchboard slab length	4.05 m
Pump well floor thickness	0.60 m
Valve pit floor thickness	0.30 m
Footing length	0.00 m
Footing thickness	0.00 m
Pump well hatch location	1.00 m
Pump well hatch length	1.10 m
Pump well hatch width	2.30 m
Pump well roof thickness	0.35 m

Top level	2.75 m
Ground level	2.45 m
Water table level	1.45 m
Pump well floor level	-1.91 m
Valve pit floor level	0.71 m

Concrete density	25.00 kN/m <sup>3</sup>
Ground density	19.00 kN/m <sup>3</sup>
Water density	9.81 kN/m <sup>3</sup>
Top surcharge	5.00 kPa

Side shear	5.00 kN/m <sup>2</sup>
------------	------------------------

### Pump station mass

Pump well floor	6.11 m <sup>3</sup>	5.00 m	Inside wall
Pump well wall	18.05 m <sup>3</sup>	5.00 m	Foundation to U/S of roof
solid block	0.00	6.05	
wet well cutout	0.00	5.89	
Wet well footing	0.00 m <sup>3</sup>	0.00 m	
solid block	49.14	2.50	to C/L of pump well
valve pit hole	20.00	1.58	
pump well hole	16.21	4.11	
valve pit hole	12.93 m <sup>3</sup>	1.91 m	
square slab	8.60	7.93	
pump well half	2.42	4.11	
pump well hatch	0.89	4.75	
Pump well roof	10.14 m <sup>3</sup>	7.29 m	
Total concrete	47.22 m <sup>3</sup>	4.65 m	
	1181 kN		

Moment on Centreline	417 kNm
----------------------	---------

### Buoyancy

Assumes water level is above underside of valve pit

Pump well lower	40.45 m <sup>3</sup>	5.00 m
Pump well upper	14.41 m <sup>3</sup>	5.00 m
valve pit solid	21.84	2.50
pump well hole	7.20	3.86
Pump pit	14.64 m <sup>3</sup>	1.83 m
Total buoyancy	69.50 m <sup>3</sup>	4.33 m
	-682 kN	

Moment on Centreline	-455 kNm
----------------------	----------

### Soil on Footing

solid block	0.00	6.05
-------------	------	------

4

wet well cutout	0.00	5.89
Soil on footing	0.00 m <sup>3</sup>	0.00 m
	0 kN	
Moment on centreline		0.00 kNm

**Side Shear**

Neglect side friction on top equivalent to depth of slab

Pump well lower	38.53 m <sup>2</sup>	5.00 m
Pump well upper	15.83 m <sup>2</sup>	6.34 m
Valve pit sides	48.10 m <sup>2</sup>	2.50 m
Valve pit end	8.36 m <sup>2</sup>	0.00 m
Total shear	108.82 m <sup>2</sup>	3.75 m
	544 kN	

Moment on Centreline		679 kNm
----------------------	--	---------

**Buoyancy Calculations**

	With shear	No shear
Down force factored	1552 kN	1062 kN
Up force factored	-818 kN	-818 kN
Ratio	-0.53	-0.77

OK

**Roof Loading**

Roof area	45.57 m <sup>2</sup>	
Roof live load	447 kN	5.43 m
Moment on centreline		-190 kNm

**Equipment Loading**

Valve pit pipework	45 kN	2.50 m	assumption
Pump well pumps	120 kN	5.60 m	assumption
Benching	66 kN	5.00 m	estimate
Pump well contents	220 kN	6.25 m	estimate
Total equipment	451 kN	5.52 m	
Moment on centreline		-235 kNm	

Maximum loading	1397 kN	-462 kNm	e	Base A	13.85 m <sup>2</sup>
Minimum loading	499 kN	-38 kNm		Base Z	7.27 m <sup>3</sup>
Normal case	950 kN	-272 kNm			

**Stresses on Pump Well Base**

	Compression	Bending	Max	Min	
Maximum loading	101 kPa	-64 kPa	37	164 kPa	
Minimum loading	36 kPa	-5 kPa	31	41 kPa	
Normal loading	69 kPa	-37 kPa	31	108 kPa	No go

**Stresses on Pump Well Base + Valve Pit Base**

	Bending	e	New e	New M	Total L	7.10 m
Maximum loading	-462 kNm	-0.33	-1.99	-2779	Pit width	4.20 m
Minimum loading	-38 kNm	-0.08	-1.73	-865	Pit length	5.00 m
Normal loading	-272 kNm	-0.29	-1.95	-1848	Well dia	4.20 m
					Centroid	3.34 m
						78.05 m <sup>4</sup>
					c1	3.34
					c2	3.76
					Z1	23.36 m <sup>3</sup>
					Z2	20.77 m <sup>3</sup>
					Area	27.93 m <sup>2</sup>

	Compression	Bending	Max	Min	
		C1	C2	C1	C2
Maximum loading	50 kPa	-119	134	-69	184 kPa
Minimum loading	18 kPa	-37	42	-19	60 kPa
Normal loading	34 kPa	-79	89	-45	128 kPa

**Effective Ground Stress**

Pump well floor	45.58 kPa
Valve pit floor	18.75 kPa


PROJECT

PROJECT NO. ....

Designed .....

Date .....

Sheet 5 of .....



OK for curved walls.

Assumes that load is shared between pump wet well and gub collector based on static.

Likely in view of 14 m length of the structure.

Space capacity in connection of foundations under gub collector is softer than under pump well.



PROJECT

Lytton Rd PS

PROJECT NO.

7519/2

Designed

HP


Date

13-5-01

Sheet

1 of

Femie Alondo Dosing System



Beam pressure under slab

$$= \frac{7.13 \times 7.13 \times 2 \times 25 + 27.72 \times 7 \times 2 \times 25}{7.13^2} + 32 \times 9.81$$

= 13.1 kPa

PROJECT


PROJECT NO. ....

Designed .....

Date .....

Sheet 2 of .....

Slab Moment



$$W = \frac{32 \times 9.81}{6.73^2} = 6.93 \text{ kPa}$$

$$M = 6.93 \times \frac{4.493^2}{2} \times \frac{3.177}{3} = 74.1 \text{ kNm}$$

$$L = 6.354$$

$$\therefore M_u = \frac{74.1}{6.354} \times 1.5 = 17.5 \text{ kNm/m}$$

$$D = 200$$

$$d = 126$$

$$N16 @ 150$$

$$A_s = 1340$$

$$F_c = 32$$

more than adequate.

$\therefore$  same design as Viro's Place.




PROJECT Lytton Road PS  
Pip Launcher


PROJECT NO. 7519/02-3  
Designed MP  
Date 26-6-04 Sheet 1 of 1

largest wall


$$\frac{b}{a} = \frac{6510}{2530} = 2.57$$



$q = 20 \text{ kN/m}^3$   
 $h_0 = .5$   
 $q_1 = 253 \text{ kN/m}^2$



Case 4



$T = 10$

$$\begin{aligned} M_V &= 65 \quad 25.3 \quad 2.53^2 \quad \frac{1}{1000} = 10.6 \text{ kNm/m} \\ M_H &= 37 \quad " \quad " \quad " = 6.0 \text{ kNm/m} \end{aligned}$$

assume restrained

12mm req  $\rho_s = 0.48\%$

wall 250 thick =  $1200 \text{ mm}^2$

N12 @ 113mm

$\therefore 2 \text{ layers / } \forall 12 @ 188$

$\rightarrow \forall 12 @ 150 = 753 \text{ mm}^2/\text{m}$

base 300 thick =  $1440 \text{ mm}^2 \therefore \text{also } \forall 12 @ 150$



## Concrete Serviceability analysis

Case	Hor		Ver		
	1		2	3	4
D	250 mm		250		
Cover	50 mm		50		
Outer Reo Dia	0 mm		12		
Stress Reo Dia	12 mm		12		
Stress Reo Spacing	150 mm		150		
Concrete strength	40 MPa		40		
Concrete mass	2500 kg/m <sup>3</sup>		2500		
Reinforcement strength	500 MPa		500		
Moment	6 kNm/m		10.6		
d	194 mm		182	0	0
Area of reinforcement	754 mm <sup>2</sup>		754	#DIV/0!	#DIV/0!
p	0.0039		0.0041	#DIV/0!	#DIV/0!
E concrete	33994 MPa		33994	0	0
E reinforcement	2.00E+05 MPa		2.00E+05	2.00E+05	2.00E+05
n	5.9		5.9	#DIV/0!	#DIV/0!
pn	0.023		0.024	#DIV/0!	#DIV/0!
k	0.192		0.198	#DIV/0!	#DIV/0!
j	0.936		0.934	#DIV/0!	#DIV/0!
Allowable concrete stress	16.0 MPa		16.0	0.0	0.0
Allowable reo stress	150.0 MPa		150.0		
Mc	54.2 kNm/m		48.9	#DIV/0!	#DIV/0!
Ms	20.5 kNm/m		19.2	#DIV/0!	#DIV/0!
	OK		OK	OK	OK

<b>PROJECT</b>	<b>PROJECT NO.</b> ..... <b>Designed</b> ..... <b>Date</b> ..... <b>Sheet</b> 3 <b>of</b> .....
----------------	---

" walls + floor OK.

Roof 5 kPa

slab 1.5m wide, supports 2.9m width, span 4.7m


DL 3<sup>rd</sup> slab  $M = \frac{3 \times 25 \times 2.9}{1.5} \times \frac{4.7^2}{8} \times 1.25$

$= 14.5 \times 2.76 \times 1.25$

$M_{DL} = 50 \text{ kNm/m}$

$D = 300$        $d = 300 - 50 - 8$

$= 240 \text{ mm}$  (M6)



Transverse req =  $6 b D \times 10^{-3} = 1800 \text{ mm}^2/\text{m}$  | excessive ∴ not retained

min req =  $\frac{A_{st}}{bD} = .002$

$A_{st} = .002 \times 1000 \times 300 = 600 \text{ mm}^2/\text{m}$





<b>PROJECT</b>	<b>PROJECT NO.</b> ..... <b>Designed</b> ..... <b>Date</b> ..... <b>Sheet 4</b> of .....
----------------	--

$$DL = 5 \text{ kN/m}^2$$

$$M_{ULL} = 5 \times \frac{2.9}{1.5} \times \frac{4.7^2}{8} \times 1.5$$

$$= 40 \text{ kNm}$$

$$\therefore M_U = 90 \text{ kNm/m}$$

$$A_s = 1260 \text{ mm}^2/\text{m}$$

$$N16 @ 150 = 1340 \text{ mm}^2/\text{m} \quad \underline{OK}$$


PROJECT

PROJECT NO. ....


Designed

Date

Sheet 5 of





4-N12






PROJECT

PROJECT NO. \_\_\_\_\_  
Designed \_\_\_\_\_  
Date \_\_\_\_\_ Sheet 5 of \_\_\_\_\_







Home

MACHOVEC

## 3-Strand Tuck Splice

Rope

Rescue Gear

Mustang

Secure Screen

Life Jackets

Quest Meters

Catalog Index

Request Info



Contact Us

**Class 1 3-strand ropes are made from any or all of the following**

Although the 3-strand splice is the most common splice, and simple to perform, tech Take care that the tucks lie neatly; rope strength can be lost if the strands are twisted

**Tools Required:** Fid; tape or whipping twine; marking pen, scissors or a sharp knife;

**Getting Started:** From one end of the rope, count back 16 crowns. Tape this section end of each strand. Form the eye and tape the standing part of the rope. To avoid a the rope one-half turn between the pieces of tape.



### STEP 1 ... TUCKING THE FIRST STRAND


With a fid or your finger, raise a strand the rope and insert the middle work through. Mark the first tucked strand with a double hash mark. Working strands will help you keep track

### STEP 2 ... TUCKING THE SECOND STRAND

Using the fid to separate strands, tuck the next working strand over the strand you just tucked under and under the strand just below it. Mark this strand with a double hash mark.


### STEP 3 ... TUCKING THE THIRD STRAND

Turn the entire piece over. There is one working strand left to tuck and there is one strand left in the standing part of the rope that does not have





a working strand under it. Insert the fid to separate the strands and make this tuck, cc the rope. Mark this strand with a triple hash mark.





The first round of tucks is complete. Tighten if necessary by pulling on the strand ends

When you tuck, take care to use all three strands in each round and that you tuck up and not under one of your working strands.




## STEP 4 ... FINISHING THE SPLICE

Perform four more complete tucks. Tighten tucks if necessary. Both the front and illustrations shown.



*\*Splicing information is provided by SAMSON Rope Technologies*





© 2004 MACHOVEC - A

Site questions should |

Please take a moment to view our



# MACHOVEC

## 3-Strand Tapered Eye Splice

***Class 1 3-strand ropes are made from any or all of the following fibers: Olefin, Polyester, Nylon***

Home

Rope

Rescue Gear

Mustang

Secure Screen

Life Jackets

Quest Meters


Catalog Index

Request Info

Contact Us

Although the 3-strand splice is the most common splice, and simple to perform, technique is important to preserve splice strength. Take care that the tucks lie neatly; rope strength can be lost if the strands are twisted incorrectly.

**Tools Required:** Fid; tape or whipping twine; marking pen, scissors or a sharp knife; hot knife or heat source ☺; ruler.




### STEP 1 ... FORMING THE EYE


From one end of the rope, count back 14 crowns. Tape this section. Form the eye and tape the standing part of the rope. To avoid a twist in the eye of the finished splice, untwist the rope one-half turn between the pieces of tape.

### STEP 2 ... TUCKING THE FIRST STRAND

Unlay the three strands to the first tape and either tape or seal the individual ends.



Form the eye from right to left by bringing the two tape marks together. Tuck the center unlaid strand toward you under the top strand in the main body of the line. Pull tight.




### **STEP 3 ... TUCKING THE SECOND STRAND**

Turn the entire piece over. Insert the fid to separate the strands and tuck the left-hand unlaid strand under the next strand in line and pull towards you. Keep the strands pulled tight.


### **STEP 4 ... TUCKING THE THIRD STRAND**

Turn the entire piece over. There is one working strand left to tuck and there is one strand left in the standing part of the rope that does not have a working strand under it. Insert the fid to separate the strands and make this tuck, continuing to work counter to the lay or twist of the rope..

The first round of tucks is



complete. Tighten if necessary by pulling on the strand ends.




### STEP 5 ... CONTINUING ON


Take one of the unlayed strands and pass it over, around and under the strand next to it. Pull the end of the strand through toward you. Repeat this process with all unlayed strands for a minimum of five tucks each. You will find that each unlayed strand will be forming a twist around one of the strands in the body of the line.

When you tuck, take care to use all three strands in each round and that you tuck under a strand in the standing part of the rope and not under one of your working strands.

### STEP 6 ... TAPERING THE SPLICE

To taper the splice into the line, make two additional tucks with one strand and one additional tucks with a second strand leaving the third strand as it is. This will leave a strand between each unlayed strand.





### STEP 7 ... FINISHING THE SPLICE

Cut off the remaining unlayed strands about 3/8" from the last tuck. Heat seal the ends to prevent fraying, if desired. Smooth the splice by rolling it between your hands or under foot for large diameter lines.


*These splicing instructions were brought to you by [www.machovec.com](http://www.machovec.com).*

*\*Splicing information is provided by New England Ropes*



---

© 2004 MACHOVEC - All Rights Reserved

Site questions should be directed to 

Please take a moment to view our Terms of Use and our Privacy Policy.

