

# KALBAR S.T.P. HYPOCHLORITE TANK REPLACEMENT CONTRACT No. SOA C1011-045

### **OPERATION & MAINTENAINCE MANUAL**

### Developed by:



J & P RICHARDSON INDUSTRIES CAMPBELL AVENUE WACOL QLD 4076

> ABN 23 001 952 325 ACN 001 952 325

Ph. (07) 3271 2911 Fax. (07) 3271 3623

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 1 of 44

## KALBAR S.T.P.

# HYPOCHLORITE TANK REPLACEMENT

# CONTRACT No. SOA C1011-045

## DOCUMENT CHANGE HISTORY

### **Revision Control**

Version	Author	Issue Purpose	Signature	Date
0	Paul Houston / Rob Miotti	Original Issue	Rob Miołti	29-3-16

### Reviewed by

Version	Author	Position	Signature	Date
0	Darren Wedley	Project Manager	Darren Wedley	29-3-16

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 2 of 44

# **CONTENTS**

- 1 Introduction
- 2 Product Data Sheets
  - 2.1 HDPE Tank & Bund
  - 2.2 Dosing Pump Instructions
- 3 Certification Forms
- 4 Test Reports
- 5 "As Constructed" Drawings

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 3 of 44

# 1 INTRODUCTION

The site of these works is located at the Kalbar Sewerage Treatment Plant, Heit Road, Kalbar. The purpose of this project was to:

- 1. Upgrade the Sodium Hyplochlorite Tank & dosing system by installing a 1,500L Tank, to suit the anticipated duty expected over the next 25 years.
- 2. Bring the storage & dosing facilities into compliance with the current Australian Standards & Codes of Practice.

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 4 of 44

Contract Number: SOA C1011-045

 ${\it Kalbar\,S.T.P.\, Hypochlorite\, Tank\, Replacement}$ 

# 2 PRODUCT DATA SHEETS

### 2.1 HDPE TANK & BUND


Kalbar Manual Rev. 0 29 March 2016


Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 5 of 44


# **Tank Specification**

Working Capacity	1,500 L		
Documentation	Design documentation, as-built Drawings up to revision C.		
Engineering standard	DVS 2205, BS EN 12573		
Design criteria	Sodium Hypochlor	ite at 30°C	
Specific Gravity	1.2		
Dimensions	Tank ID = 1200 mm, Apex Height = 1800 mm, O/A Cylinder Height = 1500 mm Flat Base		
Material	Black HDPE		
Tank Connections	Inlet	DN50 PN16 PE Stub/ BR Galv. Steel AS4087 PN 16	
	Outlet	DN50 PN16 PE Stub/ BR Galv. Steel AS4087 PN 16	
	Overflow	DN80 PN16 PE Stub/ BR Galv. Steel AS4087 PN 16	
	Vent	DN25 PN16 PE Stub/ BR Galv. Steel AS4087 PN 16	
	Sight Glass	DN25 Clear PVC with GF Ball Valve	
Tank Identification Plaque		Plaque	
Testing	Hydrostatic		

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 6 of 44







Contract Number: SOA C1011-045

 ${\it Kalbar\,S.T.P.\, Hypochlorite\, Tank\, Replacement}$ 

## 2.2 DOSING PUMP INSTRUCTIONS

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 10 of 44

# **Grundfos DDA Dosing Pump**

- 1. From the main operating screen, rotate the dial until the "Setup" icon is selected and press the dial.
- 2. From the setup screen, rotate the dial until "Analogue Scaling" is selected and press the dial.
- In this section the operator can modify the analogue scaling values.Basic settings that are required for the system to operate correctly are,
  - Analogue range = 4 20 mA (<u>Do not modify</u>).
  - Analogue Zero (4mA = 0% Dose rate in L/H) = 0L/Hr (<u>Do not modify</u>).
  - Analogue Maximum (20mA = 100% Dose rate in L/H) = Operator adjustable dosing rate.
- 4. After the required changes are made, rotate the dial until the "Home" icon is selected and press the dial. Now you should be back at the main operating display.

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 11 of 44

# **Grundfos DDI Dosing Pump**



"Start/Stop"

- Use this button to start or stop the pump.
- Error signals can be acknowledged by pressing the "Start/Stop" button.



Use the "Menu/Info" button to switch between the operating modes.





Use the "Down" and "Up" buttons to change values in the display.

1. From the main operating screen, press and hold the "Menu" button for 3 Seconds

Now Code C:111 will be displayed on the screen, press "Menu" button to accept password.

2. From the setup screen, keep pressing the Menu button until the "Weighting o Current" input is displayed.

From the "Weighting of Current" screen, press the "Start/Stop" button to select the value minimum analogue input value (this value should always be 4 mA - <u>Do not modify</u>).

Press the Stop/Start button to progress through the parameter.

4. This screen sets the minimum flow rate in L/Hr for the minimum analogue value set in the previous step (this value should always be 0 L/H - <u>Do not modify</u>). Press the Stop/Start button to progress through the parameter.


5. This screen sets the maximum analogue input value (this value should always be 20 mA - <u>Do</u> not modify). Press the Stop/Start button to progress through the parameter.

6. This screen sets the maximum flow rate in L/Hr for the maximum analogue value (20mA) which was set in the previous step, this set point is the operator adjustable dosing rate.

By pressing the "Down" and "Up" buttons the dosing rate can be changed to the required concentration.

Press the Stop/Start button to confirm the setting and close the second function level and to return to the main operating display.

Q-Pulse Id: TMS1600 Active: 27/04/2016 Page 12 of 44



0.219661017 L/Hr

Dose Rate

### Grundfos DDA Pump Parameter Setup

Site	Kalbar STP				
Pump	Hypo Dosing				
Serial No.					
Product No.	97722862				
Туре Кеу	DDA 7.5-16 FCM-PV/T/	C-F-31U2U2IG			
Menu		Setting		Intial	Date
SETUP	1				
Language	English	✓			
			<u> </u>		
Operation m	Manual				
	Pulse				
	Analog	✓	4-20mA		
	Batch				
	Dosing Timer Cycle				
	Dosing Timer Week				

Analog scaling		Input value [mA]	Dosing flow	
		≤ 4.0	0	
		≥ 20.0	1.016945085	
FlowConti	rol active*	✓		
FlowConti	rol Delay	Short		
	<u> </u>	Medium	✓	
		Long		
	Sensitivity	Short		
	,	Medium	✓	
		Long		
Pressure r	monitoring*	<b>√</b>		
	Min Pressure	1		
	Max Pressure	1	7 Bar	
Display	Units	Met.	✓	
-17		US gallons		
	Contrast	58%		
	Additional Display	Default Display		
		Dosed Volume		
		Actual Flow		
		Backpressure	✓	
Inputs/Ou	itnuts	Вискрі сэзиге	•	
puts, ot	Relay 1	Alarm	✓	
	,	Warning		
		Stroke signal		
		Pump Dosing		
		Pulse Input		
		Bus Control		
		Contact Type	NC	
	Relay 2	Alarm	IVC	
	neldy 2	Warning		
		Stroke signal		
		Pump Dosing	✓	
		Pulse Input	,	
		Bus Control		
		Contact Type	NO	
	External stop	NO NO	NO ✓	
	ехтеппат 200р	NC NC	*	
	Empty signal		·	
	Empty signal	NO NC	*	<del>                                     </del>
	Laurela dan al		<b>√</b>	
	Low-level signal	NO	<b>-</b> ✓	
		NC		1 1

Pump Speed L/hr = (Required Dose Rate 'mg/L' \* Water Flow 'L/s' \* 3600)/(Batch Concentration '%'\* Specific Gravity (1.16) \*10 000)

		_		Linear Chec	k	_	
Required Dose Rate	5	mg/L	%	mA	Rate		
Max Flow Rate	8.3333	L/s	0	4	0.000	L/Hr	0
Batch Concentration	12.5	% Weight/Volume	25	8	0.254	L/Hr	0.243
Specific Gravity	1.18		50	12	0.508	L/Hr	0.499
Max Pump Cap	7.5	L/Hr	75	16	0.763	L/Hr	0.754
Pump Speed L/hr	1.016945085	@20mA	100	20	1.017	L/Hr	1.01
Max Pump Percent	13.5592678	@20mA					
Flow Dose Rate Check		_					
Current Flow Meter	1.8	L/s					

0.22

Contract Number: SOA C1011-045

 ${\it Kalbar\,S.T.P.\, Hypochlorite\, Tank\, Replacement}$ 

# 3 CERTIFICATION FORMS

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 15 of 44

Version 3 – March 2013

# Form 15—Compliance Certificate for building Design or Specification

NOTE	This is to be used for the purposes of section 10 Building Regulation 2006.	of the Building Act 1975 and/or section 46 of the
		only give a compliance certificate about whether ion of the QDC. A building certifier (Class B) can earance and site cover provisions.
Property description     This section need only be completed if details of street address and property description are applicable.	Street address <i>(include no., street, suburb / locality &amp; po</i> Waste Water Treatment Plant, Treatment Plant Ro  GATTON QLD	
EG. In the case of (standard/generic) pool design/shell manufacture and/or patio and carport systems this section may not be applicable.	Lot & plan details (attach list if necessary)  In which local government area is the land situated?	
The description must identify all land the subject of the application.	Gatton Shire Council	
The lot & plan details (eg. SP / RP) are shown on title documents or a rates notice.		
If the plan is not registered by title, provide previous lot and plan details.		
2. Description of component/s certified Clearly describe the extent of work covered by this certificate, e.g. all structural aspects of the steel roof beams.	Footings & Slab	
3. Basis of certification Detail the basis for giving the certificate and the	Current Australian Standards	
extent to which tests, specifications, rules, standards, codes of practice and other	Engineering Principles	
publications, were relied upon.	Building Code of Australia	

Active: 27/04/2016



Q-Pulse Id: TMS 1600

4. Reference documentation Clearly identify any relevant documentation, e.g. numbered structural engineering plans.	Structural Engineering Plans by Icon Consulting Engineers P/L Ref No 1505-03 sheets 01 to 03 Issue B
5. Building certifier reference number	Building certifier reference number
6. Competent person details A competent person for building work, means a person who is assessed by the building certifier for the work as competent to practise in an aspect of the building and specification design, of the building work because of the individual's skill, experience and qualifications in the aspect. The competent person must also be registered or licensed under a law applying in the State to practice the aspect.  If no relevant law requires the individual to be licensed or registered to be able to give the help, the certifier must assess the individual as having appropriate experience, qualifications or skills to be able to give the help.  If the chief executive issues any guidelines for assessing a competent person, the building certifier must use the guidelines when assessing the person.	Name (in full)  Scott Duncan Wilson Fairley  Company name (if applicable)  Icon Consulting Engineers Pty. Ltd.  Phone no. business hours (07) 5559 2445  Email address info@i-con.com.au  Postal address PO Box 196 West Burleigh Qld  Licence or registration number (if applicable)  RPEQ – 8423
7. Signature of competent person This certificate must be signed by the individual assessed by the building certifier as competent.	Signature Date  24/08/2015

The *Building Act 1975* is administered by the Department of Housing and Public Works



Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 17 of 44

Version 4 – March 2013

# Form 16—Inspection Certificate / Aspect Certificate / QBSA Licensee Aspect Certificate

NOTE	This form is to be used for the purposes of section 10(c) and 239 of the <i>Building Act 1975</i> and/or sections 32, 35B, 43, 44 and 47 of the <i>Building Regulation 2006</i> .		
Indicate the type of certificate	Inspection Certificate for		
The stages of assessable building work are listed in section 24 of the <i>Building Regulation 2006</i> or as conditioned by the building certifier.  An aspect of building work is part of a stage (e.g. waterproofing).	Stage of building work (for single detached class 1a or class 10 building or structure) (indicate the stage)  Aspect of building work (indicate the aspect) Piers, Footings & Slab  QBSA Licensee Aspect Certificate Scope of the work Scope of the work Scope of the work covered by the licence class under the Queensland Building Services Authority Regulation 2003 for the aspect being certified, e.g. scope of work for a waterproofing licence is "installing waterproofing materials or systems for preventing moisture penetration". An aspect being certified may include "wet area sealing to showers".		
2. Property description  The description must identify all land the subject of the application.  The lot & plan details (eg. SP / RP) are shown on title documents or a rates notice. If the plan is not registered by title, provide previous lot and plan details.  3. Building/structure description	Street address (Include no., street, suburb / locality & postcode)  Heit Road  Kalbar QLD 4309  Lot & plan details (Attach list if necessary)  In which local government area is the land situated?  Scenic Rim Regional Council  Building/structure description  Class of building / structure  Water Tank Slab  10a		
LOCAL GOVERNMENT USE ONLY  DATE RECEIVED	REFERENCE NUMBER/S		

The *Building Act 1975* is administered by the Department of Housing and Public Works



Q-Pulse Id: TMS1600 Active: 27/04/2016 Page 18 of 44

4. Description of component/s certified Clearly describe the extent of work covered by this certificate, e.g. all structural aspects of the steel roof beams.	Piers, Footings & Slab (excavation & reinforcement) 08/10/2015		
5. Basis of certification	Visual Inspection		
Detail the basis for giving the certificate and the extent to which tests, specifications, rules, standards, codes of practice and other publications, were relied upon.	Building Code of Australia  Current Australian Standards  Engineering Principles		
Reference documentation     Clearly identify any relevant documentation, e.g. numbered structural engineering plans.	Structural Engineering Plans by Queensland Urban Utilities – Kalbar S.T.P. Heit Road Hypochlorite Tank Installation Dwg. No.: 486/5/5-0304-205 (Amendment O – 11/15) Dwg. No.: 486/5/5-0304-206 (Amendment O – 11/15) Dwg. No.: 486/5/5-0304-207 (Amendment O – 11/15)		
7. Building certifier reference number and development approval number	Building certifier reference number  Development approval number		
8. Building Certifier, competent person or QBSA licensee details A competent person must be assessed as competent before carrying out the inspection. The builder for the work cannot give a stage certificate of inspection. A competent person is assessed by the building certifier for the work as competent to practice in an aspect of the building and specification design, because of the individual's skill, experience and qualifications. The competent person must be registered or licensed under a law applying in the State to practice the aspect.  If no relevant law requires the individual to be licensed or registered, the certifier must assess the individual as having appropriate experience, qualifications or skills to be able to give the help.  If the chief executive issues any guidelines for assessing a competent person, the building certifier must use the guidelines when assessing the person.	Name (in full)  Scott Duncan Wilson Fairley  Company name (if applicable)  Icon Consulting Engineers Pty. Ltd.  Phone no. business hours (07) 5559 2445  Email address info@i-con.com.au  Postal address  PO Box 196  West Burleigh Qld  Licence or registration number (if applicable)  RPEQ – 8423		
Signature of building certifier, competent person or QBSA licensee  Note: A building certifier must sign this form for	Signature Date		
temporary swimming pool fencing under	30/11/2015		

The *Building Act 1975* is administered by the Department of Housing and Public Works



Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 19 of 44

Version 3 - March 2013

# Form 15—Compliance Certificate for building Design or Specification

NOTE	This is to be used for the purposes of section 10 of the Building Act 1975 and/or section 46 of the Building Regulation 2006.		
	RESTRICTION: A building certifier (class B) can only give a compliance certificate about whether building work complies with the BCA or a provision of the QDC. A building certifier (Class B) can not give a certificate regarding QDC boundary clearance and site cover provisions.		
Property description     This section need only be completed if	Street address (include no., street, suburb / locality & postcode)		
details of street address and property description are applicable.	Postcode		
EG. In the case of (standard/generic) pool design/shell manufacture and/or	Lot & plan details (attach list if necessary)		
patio and carport systems this section			
may not be applicable.	In which local government area is the land situated?		
The description must identify all land the subject of the application.			
The lot & plan details (eg. SP / RP) are shown on title documents or a rates notice.			
If the plan is not registered by title, provide previous lot and plan details.			
2. Description of component/s certified Clearly describe the extent of work covered by	Totalspan/Spanbild standard cold formed steel single flat roof carport		
this certificate, e.g. all structural aspects of the steel roof beams.	3 x 6 m, up to 4.2 m high.		
	Wind loading: Region: A (VR = 45 m/s), B (VR = 51 m/s), C (VR = Fc * 66)		
	Terrain cat. 2 or 3, Cpn = -1.0/-0.8, Importance level 2		
	Standard cladding tested for BCA LHL requirements		
	Footings/slab designed for class S & M and 100kPa bearing capacity		
3. Basis of certification  Detail the basis for giving the certificate and the	Current Australian Standards and Regulations:		
extent to which tests, specifications, rules,	BCA 2014 including close 3.10.1 & 3.11.		
standards, codes of practice and other publications, were relied upon.	AS 1170.0, 1 & 2: 2002/2011 (loading)		
	AS/NZS 4600:2005 (cold formed steel design), AS 4100 (steel structures)		
	AS 3600 (concrete structures), AS2870 (footings), AS 3566.1 (Screws)		
4. Reference documentation			
Clearly identify any relevant documentation, e.g. numbered structural engineering plans.	Totalspan/Spanbild standard drawing No. 1 TSFCP-AUS reviewed by  Stan T Olech		
,	Staff T Olecti		
LOCAL GOVERNMENT USE ONLY			
Date received	Reference Number/s		

Active: 27/04/2016

The *Building Act 1975* is administered by the Department of Housing and Public Works



5. Building certifier reference number	Building certifier reference number	
6. Competent person details  A competent person for building work, means a person who is assessed by the building certifier for the work as competent to practise in an aspect of the building and specification design, of the building work because of the individual's skill, experience and qualifications in the aspect. The competent person must also be registered or licensed under a law applying in the State to practice the aspect.  If no relevant law requires the individual to be licensed or registered to be able to give the	Name (in full)  Stan Theodore Olech  Company name (if applicable)  Vermont Consultants  Phone no. business hours  Mobile no.	Contact person S T Olech Fax no.
	(07) 3264 8409  Email address  vermont7@bigpond.com	FAX 110.
help, the certifier must assess the individual as having appropriate experience, qualifications or skills to be able to give the help.	P O Box 533	
If the chief executive issues any guidelines for assessing a competent person, the building certifier must use the guidelines when assessing the person.	Albany Creek  Licence or registration number (if applicable)  RPEQ 2426	Postcode 4035
7. Signature of competent person This certificate must be signed by the individual assessed by the building certifier as competent.	Signature	Date  1/07/2014  (This certificate is valid to 30/06/2015)

Active: 27/04/2016

Contract Number: SOA C1011-045

 ${\it Kalbar\,S.T.P.\, Hypochlorite\, Tank\, Replacement}$ 

# 4 TEST REPORTS

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 22 of 44

1876 DOCKET No. ELECTRICAL CONTRACTORS and ENGINEERS TELEPHONE: 3271 2911 (All hours) 114 CAMPBELL AVENUE - WACOL, BRISBANE Q 4076 CUSTOMER: JOB NUMBER Н 0 M S WORK START TIME EMP. No. NORMAL FIRE ANT INSPECTION CONDUCTED 
SOIL MOVED FROM JOB SITE TO: I have carried out the work listed & I confirm it complies with Good Work Practices, Our Quality Goals & to Customer's Satisfaction. m REPORT PROMPTLY ANY CONDITION LIABLE TO CAUSE AN ACCIDENT REMEMBER YOU ARE - RESPONSIBLE FOR YOUR SAFETY TIME CLOCK 48m 2m10 WNITS PER HR. 42m 18m Customer's Authorisation for live work: 24m 30m Customer's Signature Employee Signature: ENT BY: Refer to Customer Copy for General Terms and Conditions of Supply HRS. MIN UNITS WORK То To Tο Т TRAVEL Tο To To SERVICE CALL -APP BY -ENDORSEE -SERVICE CALL OUT -COST SECTION -SS **FOLLOW UP** CERTIFICATE OF TESTING & SAFETY I certify that the electrical work listed has been tested in accordance with the prescribed procedure and that such work complies in every respect with the Have you driven a truck over 12t GVM today? requirements of the Electrical Safety Regulation 2013. The electrical equipment Yes I Fill out your Driver Fatigue Form listed to the extent that it is affected by the above electrical work, is electrically safe. Electrical Licence No: Signature of Electrical Worker: Form No. F1024/4 November 15 Copyright 2006



## J. & P. RICHARDSON INDUSTRIES PTY LTD

Electrical Contractors & Engineers

# **Queensland Urban Utilities**

# Lockyer Valley STPs and Kalbar STP Hypo Tanks Replacement

C1011-045

**Commissioning Report** 

**Location: Kalbar STP** 

Date: <u>10,02 2016</u>

Job: C89875

J. & P. Richardson Industries Pty Ltd 114 Campbell Avenue, Wacol Qld 4076 Phone: (07) 3271 2911 Fax: (07) 3271 3623 Email: jpr@jpr.com.au

Printed: 2016-02-09 7:41:49 AM

Page 1 of 3

File: C:\Users\des\_rm\Documents\QUU C89875 Site Test Docs\Kalbar\Kalbar STP Commissioning test sheet.doc

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 24 of 44



# J. & P. RICHARDSON INDUSTRIES PTY LTD

Electrical Contractors & Engineers

# Site Detail

Site Name	KALBAR	STF
Site Name Site Identifier(s)		

# 2 Hardware

Equipment	Туре	Serial No.	Comments Pass/Fail
Flowmeter	Frankly SO	FC027C20000	
Dosing Pump	,		
Hypochlorite Tank	FUSION	PW2150C	
DDA 7.5-16 FCM - 1	PV/T/C-F-31U2U21G		
SECIAL NO.	1 497722862100003941	11209	

# **Bund Test**

Description	Start Time/Date	End Time/Date	Check	Comments Pass/Fail
Fill bund to high level and record level and time/date. (Bund must remain full for 24hrs)	16.11.15	18.11.15	PSmiTH	x
Bund remained at full mark.	1611.15	18.11.15	P-SMITH	

# 4 Hardware Setup

### 4.1 Flowmeter

Description	Setting	Comments Pass/Fail	
4-20mA Zero Setting	0L/s	_	
4-20mA Span Setting	0.3555 L/s		
	4-20mA Zero Setting	4-20mA Zero Setting 0L/s	

# 4.2 Dosing Pump

Parameter	Description	Setting	Comments Pass/Fail	
Zero	4-20mA Zero Setting	OL/hr	/	
Span	4-20mA Span Setting	, <u>t</u> ,01 _L/hr	1	
	Required Dose Rate	SMA L		

J. & P. Richardson Industries Pty Ltd 114 Campbell Avenue, Wacol Qld 4076 Phone: (07) 3271 2911 Fax: (07) 3271 3623

Email: jpr@jpr.com.au

Printed: 2016-02-09 7:41:49 AM

Page 2 of 3

File: C:\Users\des\_rm\Documents\QUU C89875 Site Test Docs\Kalbar\Kalbar STP Commissioning test sheet.doc

Q-Pulse Id: TMS1600 Active: 27/04/2016 Page 25 of 44



# J. & P. RICHARDSON INDUSTRIES PTY LTD

Electrical Contractors & Engineers

# 5 Functional Test

Step	Description	Check / Value	Comments Pass/Fail
1	Simulate flow to 0L/s – Dosing pump at 0L/hr	۵	/
2	Simulate flow to 25% of span – Dosing pump at 25% of L/hr	0.243	
3	Simulate flow to 50% of span – Dosing pump at 50% of L/hr	0.499	/
4	Simulate flow to 75% of span – Dosing pump at 75% of L/hr	0.754	
5	Simulate flow to 100% of span – Dosing pump at 100% of L/hr	1.01	/
6	Remove simulation and confirm flow rate to dosing pump ratio correct.	1.86/SEC FOOW -22 LANK DOSE	/
7	Confirm effluent chlorine residual is correct.	1.01 1.86/SER FOUN -22 YHK DOSE 0.25mg/2	1

Site commissioned by (JPR)	Test Sheet checked by NCS Project Officer
Name: Ben wan den Ende	Name:
Signature: Bran der Knobe	Signature:
Date: 10/2/16	Date:10: 2.1.b.
	By operator

J. & P. Richardson Industries Pty Ltd 114 Campbell Avenue, Wacol Qld 4076 Phone: (07) 3271 2911 Fax: (07) 3271 3623 Email: jpr@jpr.com.au

Printed: 2016-02-09 7:41:49 AM

Page 3 of 3

File: C:\Users\des\_rm\Documents\QUU C89875 Site Test Docs\Kalbar\Kalbar STP Commissioning test sheet.doc

Contract Number: SOA C1011-045

 ${\it Kalbar\,S.T.P.\, Hypochlorite\, Tank\, Replacement}$ 

# 5 "AS CONSTRUCTED" DRAWINGS

Kalbar Manual Rev. 0 29 March 2016

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 27 of 44



# KALBAR S.T.P. HEIT ROAD HYPOCHLORITE TANK INSTALLATION

SITE COVER SHEET - CIVIL / STRUCTURAL

DRAWING No.	Rev	DRAWING TITLE	Remarks
486/5/5-0304-201	A	DRAWING INDEX	AS CONSTRUCTED
486/5/5-0304-202	A	OVERALL SITE WORKS LAYOUT	AS CONSTRUCTED
486/5/5-0304-203	A	SITE LAYOUT	AS CONSTRUCTED
486/5/5-0304-204	A	TOTALSPAN CARPORT DETAILS	AS CONSTRUCTED
486/5/5-0304-205	A	CONCRETE SLAB DETAILS	AS CONSTRUCTED
486/5/5-0304-206	А	CONCRETE SLAB DETAILS	AS CONSTRUCTED
486/5/5-0304-207	A	CONCRETE SLAB DETAILS	AS CONSTRUCTED
486/5/5-0304-208	A	MISCELLANEOUS COMPONENTS	AS CONSTRUCTED
486/5/5-0304-209			
486/5/5-0304-210			
486/5/5-0304-211			
486/5/5-0304-212			
486/5/5-0304-213			
486/5/5-0304-214			
486/5/5-0304-215			

AS CONSTRUCTED DETAILS

I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE A TRUE AND ACCURATE RECORD OF THE WORKS.

SIGNED: DATE: 17-2-16

NAME OF SIGNATORY: ROBERT MIOTTI

RPEQ No. or LICENCE: C19972

COMPANY NAME: J & P. RICHARDSON Ind.

START DATE: JUNE 2015 FINISH DATE: FEBRUARY 2016

J. & P. RICHARDSON IND.

START DATE: JUNE 2015 FINISH DATE: FEBRUARY 2016

J. & P. RICHARDSON INDUSTRIES PTY LID

INDUSTRIES PTY LID

LICENCAL CONTRACTORS AND ENGINEERS

ABM. 23 001 952 325

114 CAMPBELL ARE WACOL CLD 4078

HE (27) 3271 2011

FAX. (07) 3271 2011

FAX.

AS CONSTRUCTED

FLINDING DRAFTED P. HOUSTON P. HOUSTON 20-7-15 A 2.16 AS CONSTRUCTED DESIGN W.O. No. P.H. DRAFTING CHECK P. HOUSTON DESIGN R.P.E.Q. No. DATE APPROVED BY SIGNATURE DATE O 11.15 ISSUED FOR CONSTRUCTION CONSTRUCTION W.O. N ORIGINAL SIGNED BY PRAFTED DESIGNED FREQ NO. APPROVED FUNDED BY Q.U.U. (\*) EXTERNAL () Q.U.U. FILE No.


ASSET,PROJECT KALBAR S.T.P.
HEIT ROAD
HYPOCHLORITE
TANK INSTALLATION


DRAWING INDEX


SHEET No. 1 OF 8

QUEENSLAND URBAN UTILITIES DRAWING No. AMEND.

486/5/5-0304-201







# ENGINEERING DOCUMENTS FOR PROPOSED WASTE WATER TREATMENT PLANT - TANK SLABS KALBAR

CLIENT: J & P RICHARDSON INDUSTRIES PTY LTD

### GENERAL NOTES:

- 1. ALL STRUCTURAL DRAWINGS ARE PRELIMINARY UNLESS SIGNED IN TITLE BLOCK.
- 2. ALL STRUCTURAL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ARCHITECT/DESIGNER'S AND OTHER CONSULTANTS DRAWINGS. ANY DISCREPANCIES TO BE REFERRED TO THE ENGINEER IN WRITING.
- 3. ALL SITE INSPECTIONS TO BE PERFORMED BY THE ENGINEER MUST BE BOOKED 24 HOURS PRIOR TO INSPECTION TIME.
- 4. ALL DIMENSIONS SHALL BE VERIFIED BY THE CONTRACTOR BEFORE CONSTRUCTION AND/OR FABRICATION.
- 5. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE STRUCTURAL DRAWINGS.
- 6. DURING CONSTRUCTION THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE STRUCTURE IN A STABLE CONDITION AND ENSURING THAT NO CONSTRUCTION LOADS OVER STRESS ANY ELEMENTS OF THE STRUCTURE. IF UNSURE CONTACT ENGINEER FOR ADVICE.
- 7. THE STRUCTURAL ELEMENTS HAVE BEEN DESIGNED TO CARRY THE FOLLOWING LIVE LOADS:

INTERNAL FLOORS - BALCONIES LESS THAN 1000mm ABOVE GROUND -

1.5kN/m ALONG EDGE

BALCONY FLOORS 1000mm OR GREATER ABOVE GROUND -

2.0kPa / 1.8kN / 1.5kN/m ALONG EDGE 0.5kPa / 1.4kN

- STAIRS AND LANDINGS NON HABITABLE ROOF SPACES -
- 8. ALL WORKMANSHIP AND MATERIALS TO BE IN ACCORDANCE WITH THE RELEVANT (URRENT AUSTRALIAN STANDARD CODES, BCA AND LOCAL STATUTORY AUTHORITY REQUIREMENTS.
- 9. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE. (U.N.O)
- ). OTHER THAN FOR THE PURPOSES AND SUBJECT TO THE CONDITIONS OF COPYRIGHT ACT, NO PART OF THESE DRAWINGS MAY BE REPRODUCED OR COPIED IN ANY FORM WITH PRIOR WRITTEN APPROVAL.

### CONCRETE BLOCK MASONRY NOTES:

- 1. ALL CONCRETE BLOCK MASONRY WORKMANSHIP AND MATERIALS TO BE IN ACCORDANCE WITH THE RELEVANT CURRENT AUSTRALIAN STANDARD CODES AS3700 & OTHERS INCLUDED THEREIN.
- 2. ALL CONCRETE MASONRY UNITS SHALL HAVE MINIMUM CHARACTERISTIC UNCONFINED COMPRESSIVE STRENGTH OF
- 3. MORTAR SHALL BE MIXED IN THE PROPORTIONS 1:16 CEMENT-HYDRATED LIME-MORTAR SAND BY VOLUME OR M3. MORTAR WITH HIGHER EXPOSURES SUCH AS WITHIN 1km OF A COASTLINE OR IN AGGRESSIVE SOILS SHALL BE MIXED IN THE PROPORTIONS 1:0.25:3 ADDITIVES SHALL NOT BE USED WITHOUT APPROVAL BY ENGINEER.
- 4. GROUT FOR CORE FILLING SHALL BE IN ACCORDANCE WITH AS1379. STRENGTH=20MPa. MAXIMUM AGGREGATE SIZE IS 7mm, MAXIMUM SLUMP 200mm AND RODDED INTO PLACE WHERE NECESSARY TO ACHIEVE COMPACTION.
- 5. ALL CORE FILLED MASONRY SHALL BE LAID WITH A BASE COURSE OF 'CLEAN-OUT' BLOCKS TO FACILITATE CLEANING OF EXCESS MORTAR. THE MAXIMUM HEIGHT OF CORE FILL PLACED AT ANY ONE TIME IS 2400mm
- 6. CONTROL JOINTS TO BE PLACED AT 6000mm MAXIMUM CENTRES (U.N.O), USING CONTROL TYPE BLOCKS. REFER TO MANUFACTURES SPECIFICATIONS
- 7. REINFORCING IS TO BE PLACED CENTRALLY (U.N.O. IE RETAINING WALL SITUATIONS).

### FOUNDATION AND FOOTING/SLAB NOTES:

- REFER TO GEOTECHNICAL REPORT PREPARED REFERENCED ON FOOTING / SLAB PLANS FOR GEOTECHNICAL
- RETAIN AN EXPERIENCED ENGINEER TO INSPECT THE FOOTINGS/FOUNDATIONS TO CONFIRM ADEQUACY PRIOR TO PLACEMENT OF REINFORCING AND CONCRETE.
- ALL EARTHWORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH AS3798-2007. ALL TOP SOIL INCLUDING ORGANIC MATERIAL TO BE CLEARED FROM BUILDING AREA BEFORE CONSTRUCTION STARTS. FILL PLACED AFTER THE ISSUE OF THE GEOTECHNICAL REPORT SHOULD BE CERTIFIED TO A LEVEL 1, IN ACCORDANCE WITH (AS3798-2007), AND BE DEEMED CONTROLLED FILL IN ACCORDANCE WITH (AS2870-1996) BY A RECOGNISED GEOTECHNICAL ENGINEER. FILL TO BE NON REACTIVE AND COMPACTED IN 150mm LAYERS AND COMPACTED TO ACHIEVE A MINIMUM OF 95% MAXIMUM DRY DENSITY. BASED ON STANDARD COMPACTION TESTS.
- THE FOOTING RECOMMENDATIONS GIVEN ARE IN ACCORDANCE WITH AS2870 (INCLUDING AMENDMENTS) AND AR BASED ON THE GEOTECHNICAL REPORT. THE RECOMMENDATIONS HAVE PROVEN SATISFACTORY IN PERFORMANCE UNDER NORMAL CONDITIONS' ON SIMILAR SOILS. REFER AS2870 SECTION 1.3.3 FOR THE DEFINITION OF 'ABNORMAL CONDITIONS'. ALTERNATIVE FOOTING TYPES MAY BE SUITABLE AND DETAILS WILL BE PROVIDED IF REQUESTED. DETAILS OF OTHER PROPOSED ON EXISTING STRUCTURES NOT EVIDENT ON THE PLANS SUPPLIED (E.G. POOLS, RETAINING WALLS, SEWERS MAINS, TREES ETC.) AND CLOSE TO THE PROPOSED DWELLING WILL NEED TO BROUGHT TO OUR ATTENTION SO THAT THE DESIGN CAN ADDRESS THE LIMITING FACTORS ASSOCIATED WITH THE PROXIMITY OF THE OTHER STRUCTURES.
- SITE DRAINAGE PROTECTING THE SOIL FROM EXCESSIVE WETTING IS VERY IMPORTANT AND ALL STORM WATER RUNOFF MUST BE DIRECTED AWAY FROM THE FOOTINGS. SLOPING CONCRETE OR BITUMEN PAVING AWAY FROM THE HOUSE IS ALSO RECOMMENDED. GARDENS, LARGE TREES AND SHRUBS MUST BE KEPT AWAY FROM THE FOOTINGS. SEEPAGE WATER OCCURRING ON SLOPING OR EXCAVATED SITES MUST BE PREVENTED FROM REACHING FOOTINGS BY THE CONSTRUCTION OF CUTOFF DRAIN(S). REFER AS2870 APPENDIX B FOR FURTHER INFORMATION REGARDING MAINTENANCE.
- MINOR CRACKING MAY OCCUR AS A RESULT OF FACTORS NOT ASSOCIATED WITH SOIL MOVEMENTS. CONTROL JOINTS IN BRICKWORK AND BETWEEN DIFFERENT EXTERNAL MATERIALS ARE OF SIGNIFICANT ADVANTAGE IN REDUCING CRACKING AND MUST BE INCORPORATED WHEREVER POSSIBLE.
- ALL DRAINAGE TRENCHES MUST BE CONSTRUCTED A MINIMUM OF 1200mm FROM THE OUTSIDE EDGE OF THE FOOTING. IF SITE RESTRICTIONS MAKE THIS IMPOSSIBLE, ADDITIONAL DEPTH BY WAY OF PIERS WILL BE REQUIRED UNDER THE FOOTINGS WITHIN 1200mm OF DRAINAGE TRENCHES.
- AREAS OF MODERATLEY, HIGHLY AND EXTREMELY REACTIVE SOILS, IM, H AND E CLASS SITE CLASSIFICATIONS) IT IS RECOMMENDED THAT FLEXIBLE SEWER JOINTING IS USED.
- FOOTING CONCRETE STRENGTH TO BE 25MPQ. COVER TO FOOTING REINFORCING STEEL IS 40mm. REINFORCING STEEL IS TO BE SUPPORTED IN ITS CORRECT POSITION BY APPROVED PLASTIC CHAIRS AND/OR SPACERS. THE LAP LENGTH OF BAR SPLICES SHALL BE NOT LESS THAN 500mm. AT I AND L INTERSECTIONS THE BARS SHALL BE CONTINUED ACROSS THE FULL WIDTH OF THE INTERSECTION. AT L INTERSECTIONS, ONE OUTER BAR SHALL BE BENT AND CONTINUED FOR SOME AS A BENT CORNER BAR 500mm LONG EACH LEG SHALL BE PROVIDED AT ALL LEVELS OF FOOTING
- CONCRETE MUST BE POURED AS CLOSE AS POSSIBLE TO ITS FINAL POSITION, PENCIL VIBRATED AND CURED FOR AT LEAST SEVEN DAYS BY CONTINUOUS WETTING OR BY A SUITABLE CURING COMPOUND.
- SLAB CONCRETE STRENGTH TO BE 25 MPa AND TO BE REINFORCED WITH 1 LAYER OF MESH PLACED 30mm FROM TOP FACE AND SUPPORTED ON BAR CHAIRS AT 1000mm CENTRES IN BOTH DIRECTIONS. IN AREAS WHERE CERAMIC FLOOR TILES ARE USED WE RECOMMEND THE USE OF A FLEXIBLE BEDDING COMPOUND UNDER THE TILES. VAPOUR BARRIER IS 10.00 MPACED LANDER ENTIRE STAR TO BE PLACED UNDER ENTIRE SLAB

AS CONSTRUCTED DETAILS I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE A TRUE AND ACCURATI DATE: 17-2-NAME of SIGNATORY: ROBERT MIOTI RPEQ No. or LICENCE: C19972 COMPANY NAME: J & P RICHARDSON Ind. START DATE: JUNE 2015 FINISH DATE: FEBRUARY 201 J. & P. RICHARDSON DUSTRIES PTY LID ELECTRICAL CONTRACTORS AND ENGINEERS ARM 23 001 552 325 114 CAMPRELL ME MACOL OLD 4076 JPR Project No.: P15-C89875 QUEENSLAND URBAN UTILITIES DELEGATE **Urban** Utilities

boott Fairly 8423 24-8-15 P HOUSTON AS CONSTRUCTED DESIGN W.O. No. DRAFTING CHECK R.P.E.Q. No. DATE P HOUSTON APPROVED BY SIGNATURE DATE CONSTRUCTION W.O. No. 11.15 ISSUED FOR CONSTRUCTION P.H. P.H. CAD FILE 550304205-A.DWG ORIGINAL SIGNED BY No. DATE DRAFTED DESIGNED RPEQ N Q.U.U. FILE No. DESIGN CHECK R.P.E.Q. No. DATE CONSTRUCTION MANAGER SIGNATURE DATE

ASSET/PROJECT KALBAR S.T.P. HEIT ROAD **HYPOCHLORITE** TANK INSTALLATION


CONCRETE SLAB DETAILS

AS CONSTRUCTED

QUEENSLAND URBAN UTILITIES DRAWING No. AMEND

486/5/5-0304-205

Q-Pulse Id: TMS1600 Active: 27/04/2016 Page 32 of 44



# FOOTING/SLAB PLAN - KALBAR

SCALE 1:50 (A3)

REFER TO SITE

INVESTIGATION BY: DOUGLAS PARTNERS PROJECT No. 79887.00

FOUNDATION NOTE:

FOUNDING MATERIAL - STIFF NATURAL SILTY CLAY ALLOWABLE BEARING CAPACITY - 100kPa LEGEND

MARK	DESCRIPTION
BP1	450 Ø BORED PIER FOUNDED MIN. 200 INTO STIFF NATURAL GROUND. REINFORCE WITH 5-N12 BARS, R6 SPIRAL LIG, 200 PITCH WHERE PIER DEPTH EXCEEDS 1800. OMIT PIERS WHERE FOOTINGS ARE ALREADY FOUNDED INTO STIFF NATURAL GROUND.
BP2	300 Ø BORED PIER FOUNDED MIN. 200 INTO STIFF NATURAL GROUND. REINFORCE WITH 4-N12 BARS, R6 SPIRAL LIG, 200 PITCH WHERE PIER DEPTH EXCEEDS 1500. OMIT PIERS WHERE FOOTINGS ARE ALREADY FOUNDED INTO STIFF NATURAL GROUND.
150	DENOTES SLAB THICKNESS (I.E. 150mm)

#### NOTE:

- 1) THIS DESIGN DOES NOT TAKE INTO ACCOUNT TREES, OVERLAND FLOWS, POTENTIAL FLOODING, ANY UNDERGROUND INFRASTRUCTURE (UNLESS SHOWN). IF ANY OF THESE AFFECT THIS SITE, PLEASE CONTACT ENGINEER FOR AN ALTERNATE DESIGN.
- BUILDER TO CONFIRM DEPTHS AND LOCATIONS OF ALL EXISTING SERVICES PRIOR TO CONSTRUCTION.
- IF NEW STRUCTURE UNDERMINES OR SURCHARGES ANY EXISTING FOOTINGS OR STRUCTURES, BUILDER TO CONTACT ENGINEER FOR ADVICE

I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE A TRUE AND ACCURATE RECORD CE. THE WORKS.

SIGNED: DATE: 17-2-16

NAME of SIGNATORY: ROBERT MIOTTI

RPEQ No. or LICENCE: C19972

COMPANY NAME: J & P RICHARDSON Ind.

START DATE: JUNE 2015 FINISH DATE: FEBRUARY 2016

J. & P. RICHARDSON

INDUSTRIES PTY LTD

ELECTRICAL CONTRACTORS AND ENGINEERS

ABM. 23 001 852 325

ABM. 23 001 852 325

AS CONSTRUCTED DETAILS

A.B.M. 23 001 952 3; 114 CAMPBELL AVE W PH. (07) 3271 2911 FIX. (07) 3271 3623 EMML jpr@pr.com.su

JPR Project No.: P15-C89875

ME SIGNATURE

QUEENSLAND URBAN UTILITIES DELEGATE
(AUTHORISED FOR 12 MONTHS FROM DATE SHOWN)

**OUTENSLAND** Utilities

SCALE 150 0.5 1.0
(A1 SHEET U.N.O.) 0.25 0.25 0.75
SCALE 0F METERS

AS CONSTRUCTED

CONCRETE SLAB

SHEET No. 8 OF 8
QUEENSLAND URBAN UTILITIES DRA

486/5/5-0304-206 AMEND.

P.H. DESIGN W.O. No. DRAFTING CHECK P. HOUSTON A 2 16 AS CONSTRUCTED DESIGN R.P.E.Q. No. DATE APPROVED BY SIGNATURE DATE 0 11.15 ISSUED FOR CONSTRUCTION P.H. P.H. P.H. CONSTRUCTION W.O. No CAD FILE 550304206-A.DWG ORIGINAL SIGNED BY AMENDMENT DRAFTED DESCRED RPEQ NO. APPROVED FUNDED BY Q.U.U. (1) EXTERNAL ( ) DESIGN CHECK R.P.E.Q. No. DATE CONSTRUCTION MANAGER SIGNATURE DATE

P. HOUSTON

Scott Fairly

8423 24-8-15


Active: 27/04/2016


DRAFTED

ASSET/PROJECT KALBAR S.T.P.
HEIT ROAD
HYPOCHLORITE
TANK INSTALLATION

DETAILS

Q-Pulse Id: TM\$1600







# KALBAR S.T.P. HEIT ROAD HYPOCHLORITE TANK INSTALLATION

SITE COVER SHEET - MECHANICAL

DRAWING No.	Rev	DRAWING TITLE	Remarks
486/5/5-0304-230	А	DRAWING INDEX	AS CONSTRUCTED
486/5/5-0304-231	Α	1,500L TANK & BUND PIPEWORK LAYOUT	AS CONSTRUCTED
486/5/5-0304-232	A	1,500L TANK & BUND PIPEWORK LAYOUT	AS CONSTRUCTED
486/5/5-0304-233	A	1,500L TANK DETAILS	AS CONSTRUCTED
486/5/5-0304-234	A	MATERIAL LIST	AS CONSTRUCTED
486/5/5-0304-235			
486/5/5-0304-236			
486/5/5-0304-237			
486/5/5-0304-238			
486/5/5-0304-239			
486/5/5-0304-240			
486/5/5-0304-241			
486/5/5-0304-242			
486/5/5-0304-243			
486/5/5-0304-244			
486/5/5-0304-245			

AS CONSTRUCTED DETAILS I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS RPEQ No. or LICENCE: C19972 COMPANY NAME: J & P RICHARDSON Ind. START DATE: JUNE 2015 FINISH DATE: FEBRUARY 20 INDUSTRIES PTY LTD ELECTRICAL CONTRACTORS AND ENGINEERS JPR Project No.: P15-C89875 QUEENSLAND URBAN UTILITIES DELEGATE

AS CONSTRUCTED FUNDING DRAFTED P HOUSTON P. HOUSTON


P.H. DESIGN W.O. No. 2.16 AS CONSTRUCTED DRAFTING CHECK P. HOUSTON DESIGN R.P.E.Q. No. DATE SIGNATURE DATE CONSTRUCTION W.O. N ORIGINAL SIGNED BY DRAFTED DESCREEN PEGINO, APPROVED FUNDED BY Q.U.U. (1) EXTERNAL () DESIGN CHECK


ASSET/PROJECT KALBAR S.T.P. HEIT ROAD HYPOCHLORITE TANK INSTALLATION

DRAWING INDEX

**Urban**Utilities QUEENSLAND URBAN UTILITIES DRAWING No. | AMEND.

486/5/5-0304-230







	TANK FITTINGS						
NOZZLE	SIZE	SERVICE	DESCRIPTION	DRIENTATION	RADIUS FROM CENTRE OR HEIGHT (mm)		
N1	DN50 (63mm)	INLET	63mm PE STUB FLANGE W/ GALV STEEL B/RING TABLE D	90º	R=450		
N2	DN50 (63mm)	DUTLET	63mm PE STUB FLANGE w/ GALV STEEL B/RING TABLE D	45º	H=150		
N3	DN80 (90mm)	OVERFLOW	90mm PE STUB FLANGE W/ GALV STEEL B/RING TABLE D	315º	H=1385		
N4	DN50 (63mm)	VENT	63mm PE STUB FLANGE W/ GALV STEEL B/RING TABLE D	CENTRE	R=0		
N5	250mm	INSPECTION HATCH	250 THREADED INSPECTION HATCH	180º	R=450		
NP	220×160	NAME PLATE	STANDARD FUSION NAMEPLATE	115º	H=1000		
N6	DN25	SIGHT GLASS	2x 20mm ADAPTORS, CLEAR PVC WITH GF BALL VALVE	135º	H=120, H=1375		


NOZZLE SIZE	PROJECTION (mm)	
DN15-DN50 (20mm - 63mm)	80mm	
DN65 - DN100 (75 - 110mm)	100mm	
DN125 - DN200 (140 - 225mm)	150mm	
DN250 (250mm) AND ABOVE	200mm	

TANK DES	SIGN DETAILS	
DATE OF MANUFACTURE	AUGUST 2015	
MATERIAL OF CONSTRUCTION	HDPE	
TANK No.	PW2150 C	
DESIGN STANDARD	DVS 2205	
DESIGN PRESSURE	ATMOSPHERIC	
DESIGN TEMPERATURE	30° C	
DESIGN DENSITY OF LIQUIDS	1,2	
CHEMICAL REDUCTION FACTOR	1.9	
TANK DESIGN CAPACITY	1,500 L	
DESIGN CONTENTS	SODIUM HYPOCHLORITE 12.5% w/v	
DESIGN LOCATION	KALBAR, QLD	



TANK LIFTING LUG MATERIAL: 10mm THICK HOPE QTY: 4





AS CONSTRUCTED DETAILS I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS SHOWN ON THIS PLAN ARE A TRUE AND ACCURATE CORD OF THE WORKS. NAME of SIGNATORY: ROBERT MIOTT RPEQ No. or LICENCE: C19972 COMPANY NAME: J & P RICHARDSON Ind. START DATE: JUNE 2015 FINISH DATE: FEBRUARY 2016

J. & P. RICHARDSON J. CX. 1 . 110 . 111 . 112 . 111 . 112 . 111 . 112 . 1

JPR Project No.: P15-C89875

SIGNATURE QUEENSLAND URBAN UTILITIES DELEGATE (AUTHORISED FOR 12 MONTHS FROM DATE SHOWN)

**Urban** Utilities

SCALE 120 U.N.O. 0.2 0 0.2 0,6 0,6 0,8 1,0 DRAFTED FUNDING P. HOUSTON P, HOUSTON 20-7-15 P.H. DESIGN W.O. No. 2.16 AS CONSTRUCTED DRAFTING CHECK P. HOUSTON DESIGN R.P.E.Q. No. DATE SIGNATURE DATE P.H. CONSTRUCTION W.O. No. CAD FILE ORIGINAL SIGNED BY DRAFTED DESCREEN PEGINO. APPROVED. FUNDED BY Q.U.U. (/) EXTERNAL () DESIGN CHECK R.P.E.Q. No. DATE CONSTRUCTION MANAGER SIGNATURE DATE

SCALE 15 0.05 0 0.05 0.1 0.15 0.2 0.25 (A1 SHEET) SCALE OF METERS ASSET/PROJECT KALBAR S.T.P. HEIT ROAD HYPOCHLORITE TANK INSTALLATION

1,500L TANK DETAILS

AS CONSTRUCTED

QUEENSLAND URBAN UTILITIES DRAWING No. | AMEND. 486/5/5-0304-233

#### SAFETY SHOWER Item No. **Qty** Make & Number 10m DN32 PE100 SDR11 PN16 PIPE 4 DN32 POLY COMPRESSION 90deg. ELBOW 2 DN32 POLY COMPRESSION COUPLING 2 DN32 POLY COMPRESSION TO DN25 COPPER FEMALE ADAPTER 2 DN25 BSP BRASS TEE 2 DN25 BSP BRASS NIPPLE DN25 BSP BRASS BALL VALVE DN25 COPPER COMPRESSION UNION DN25 BSP BRASS 90deg. ELBOW 10 DN25 TO DN15 COPPER COMPRESSION FITTING 11 3m DN25 COPPER TUBE 12 3m DN15 COPPER TUBE DOSING LINE FROM BUND Item No. Qty Make & Number 20 1 DN50 - DN15 Sch.40 GREY uPVC REDUCING BUSH 21 2 DN15 Sch.40 GREY uPVC TOE NIPPLE 22 GRUNDFOS PVC PIPE CONNECTOR PART No.95712035 23 15m GRUNDFOS CHEMICAL DELIVER TUBE PART No.96653571 24 12m DN32 Sch.40 GREY uPVC PIPE 25 12 DN32 Sch.40 GREY uPVC 90deg. ELBOW 26 DN32 Sch.40 GREY uPVC 45deg. ELBOW 27 2 DN32 Sch.40 uPVC SOCKET UNION FLOWMETER Qty Item No. Make & Number 2 DN50 Sch.40 WHITE uPVC SOCKET UNION 40 41 1m DN50 Sch.40 WHITE uPVC PIPE 2 42 DN50 Sch.40 WHITE uPVC FULL FACE SOCKET FLANGE AS.2129 TABLE D 43 DN50 ENDRESS & HAUSER PROMAG W400 FLOWMETER 44 8 M16 x 80 316SS METRIC HEX HEAD BOLTS 45 8 M16 316SS METRIC NUTS 46 16 M16 316SS METRIC FLAT WASHERS 47 2 DN50 3mm VITON RUBBER INSERTION GASKET AS .2129 TABLE D

FUNDING

P.H. DESIGN W.O. No.

P.H. CONSTRUCTION W.O. N

DESIGNED RECORD APPROVED FUNDED BY Q.U.U. (/) EXTERNAL ()

A 2.16 AS CONSTRUCTED

DRAFTED

CAD FILE

DRAFTING CHECK

P HOUSTON

P. HOUSTON

P. HOUSTON


DESIGN CHECK

ORIGINAL SIGNED BY

DESIGN

SODIUM HYPOCHLORITE TANI	& BUND	PIPEWORE
--------------------------	--------	----------

Item No.	Qty	Make & Number			
60	1	FUSION 1,500L HDPE TANK			
61	1	FUSION HDPE BUND			
62	2	DN50 Sch.80 GREY uPVC FULL FACE SOCKET FLANGE AS.2129 TABLE D			
63	2	DN50 3mm VITON RUBBER INSERTION GASKET AS.2129 TABLE D			
64	1	DN80 3mm VITON RUBBER INSERTION GASKET AS 2129 TABLE D			
65	8	M16 x 100 316SS METRIC HEX HEAD BOLTS			
66	4	M16 x 120 316SS METRIC HEX HEAD BOLTS			
67	12	M16 316SS METRIC NUTS			
68	24	M16 316SS METRIC FLAT WASHERS			
69	2.5m	DN50 Sch.80 GREY uPVC PIPE			
70	2	DN50 Sch.80 GREY uPVC 90deg. ELBOW			
71	1	DN50 Sch.80 GREY uPVC 45deg. ELBOW			
72	2	DN50 Sch80. uPVC GEORG FISCHER DOUBLE UNION BALL VALVE c/w VITON SEALS			
73	1	DN50 Sch.80 GREY uPVC TEE			
74	1	DN50 - DN25 Sch.80 GREY uPVC REDUCING COUPLING			
75	1	DN50 Sch.80 GREY uPVC SOCKET/BSP FEMALE ADAPTER			
76	1	DN50 POLYPROPYLENE CAMLOCK TYPE F (BSP THREAD)			
77	1	DN50 POLYPROPYLENE CAMLOCK DUST CAP TYPE DC			
78	1m	DN25 Sch.80 GREY uPVC PIPE			
79	1	DN25 Sch80. uPVC GEORG FISCHER DOUBLE UNION BALL VALVE c/w VITON SEALS			
80		SPARE			
81		SPARE			
82		SPARE			
83	1	DN80 Sch.80 GREY uPVC FULL FACE SOCKET FLANGE AS.2129 TABLE D			
84	1	DN80 Sch.80 GREY uPVC 90deg. ELBOW			
85	1.5m	DN80 Sch.80 GREY uPVC PIPE			



AS CONSTRUCTED

ASSET/PROJECT KALBAR S.T.P.

HEIT ROAD

HYPOCHLORITE

TANK INSTALLATION

SIGNATURE DATE

SIGNATURE DATE

AND GUINS I KUG I EU

AWING TITLE

MATERIAL LIST

GUEENSLAI

GUEENSLAI

Urban Utilities

SHEET No. 5 OF 5

Α

QUEENSLAND URBAN UTILITIES DRAWING No. 486/5/5-0304-234

Q-Pulse Id: TM\$1600 Active: 27/04/2016 Page 40 of 44

ONSTRUCTION MANAGER

20-7-15

R.P.E.Q. No. DATE

R.P.E.Q. No. DATE



# KALBAR S.T.P. HEIT ROAD HYPOCHLORITE TANK INSTALLATION

SITE COVER SHEET - ELECTRICAL

DRAWING No.	Rev	DRAWING TITLE	Remarks
486/5/5-0304-250	A	DRAWING INDEX	AS CONSTRUCTED
486/5/5-0304-251	A	POWER DISTRIBUTION SCHEMATIC DIAGRAM	AS CONSTRUCTED
486/5/5-0304-252	A	EQUIPMENT & CABLE SCHEDULES	AS CONSTRUCTED
486/5/5-0304-253	A	PIPING & INSTRUMENTATION DIAGRAM	AS CONSTRUCTED
486/5/5-0304-254			
486/5/5-0304-255			
486/5/5-0304-256			
486/5/5-0304-257			
486/5/5-0304-258			
486/5/5-0304-259			
486/5/5-0304-260			
486/5/5-0304-261			
486/5/5-0304-262			
486/5/5-0304-263			
486/5/5-0304-264			
486/5/5-0304-265			

Registered Professional Engineer of Queensland
MR. J. F. LESTER
RPEQ 12981
DIV: ELECTRICAL
Signature: Date: 30/3/16

AS CONSTRUCTED

**Urban**Utilities

JPR Project No.: E15-C89875

EX QUEEN

SHEET NO. 1 OF 4
QUEENSLAND URBAN UTILITIES DRAWING NO. AMEND.
486/5/5-0304-250 A

NAME SIGNATURE DATE
QUEENSLAND URBAN UTILITIES DELEGATE

AS CONSTRUCTED DETAILS

I CERTIFY THAT THE "AS CONSTRUCTED" DETAILS
SHOWN ON THIS PLAN ARE A TRUE AND ACCURATE

J. & P. RICHARDSON

INDUSTRIES PTY LITE
ELECTRICAL CONTRACTORS AND ENGINEERS

1 82 001 952 325

SIGNED: DATE 30/3/16

NAME OF SIGNATORY JOHN LESTER

RPEQ No. or LICENCE: 12981

COMPANY NAME: J & P RICHARDSON Ind

START DATE: JUNE 2015 FINISH DATE FERRUARY 2011

FUNDING DRAFTED R. MIOTTI LILE 20.7-25 A 3.16 AS CONSTRUCTED DESIGN W.O. No. DRAFTING CHECK R. MIOTTI DESIGN R.P.E.Q. No. DATE APPROVED BY SIGNATURE DATE O 11.15 FOR CONSTRUCTION PH RM. JL RM. CONSTRUCTION W.O. No. CAD FILE LESTER 12981 27-11-15 DRAFTED DESIGNED APPEOLICE APPROVED FUNDED BY QUU () EXTERNAL () Q.U.U. FILE No. DESIGN CHECK R.P.E.Q. No.

ASSET/PROJECT KALBAR S.T.P.
HEIT ROAD
HYPOCHLORITE
TANK INSTALLATION

DRAWING TITLE
DRAWING INDEX

